

**ADDENDUM NO. 2**

**FLATLICK BRANCH PHASE II  
STREAM RESTORATION  
CONTRACT NO. CN13125088  
PROJECT NO. SD-000031- 097**

This Addendum consists of a total of 5 pages.

This Addendum is supplementary to the Contract Documents for **FLATLICK BRANCH PHASE II STREAM RESTORATION**, Fairfax County, Virginia.

All changes, additions or deletions included herein as Addendum No. 2 shall become a part of the Contract Documents as if originally called for in the Drawings, Specifications and Form of Bid.

**1. RESPONSES TO BIDDERS QUESTIONS:**

- 1.1. Can you please identify the limits for the coir matting, it is not clear on the drawings.
  - **RESPONSE:** See attached revised Riffle detail. The detail notes state that coir fabric is placed from the top of the reinforced bed material (starting at ½ G) to 12" beyond bankfull or through full width of bench to tie out with existing grade, which is greater, and is keyed in 6 inches at each ends with riparian seed mix underneath.
- 1.2. Is there any root pruning required for this project, if so, please define the locations.
  - **RESPONSE:** Yes, there is root pruning throughout the proposed channel area.
- 1.3. Please define the limits for the clay liner on the plans.
  - **RESPONSE:** See grading plan and attached Clay Liner detail.
- 1.4. Where are the clay fill locations? They are shown on the details but not on the plans.
  - **RESPONSE:** There are two areas indicated on the plan for clay fill. One is the clay plug at the upstream and downstream ends of abandoned

