3'-0 x 7'-0 DOOR

4'-0 x 6'-8 BARRED DOOR

3'-0 x 4'-0 WINDOW

100 WATT BULB

3- MERCURY LIGHT FIXTURES THIS CORRIDOR

12 x 12 AIR VENT IN BRICK

100 WATT BULB

4 TUBE FLOURESCENT LIGHT x 4'-0

3'-0 x 7'-0 METAL DOOR

SINK, WITH MIRROR, 100 WATT BULB ABOVE MIRROR

4'-0 x 5'-0 WINDOW

TYPICAL CELL WITH NO LIGHTS

SHOWER HEAD

TOILET

SINK

4 TUBE FLOURESCENT LIGHT x 4'-0

4'-0 x 5'-0 WINDOW

3'-0 x 8'-0 BARRED DOOR

9'-3 x 4'-0 EXPANDED METAL ENCLOSURE WITH 3'-0 x 8'-0 DOOR W/ 18 x 24 AIR VENT IN BRICK

100 WATT BULB (5 REQD) IN TUNNEL

9'-3 x 4'-0 EXPANDED METAL ENCLOSURE WITH 2'-0 x 6'-0 DOOR W/ 18 x 24 AIR VENT IN BRICK

2'-6 x 6'-8 WOOD DOOR

100 WATT INCANDESCENT BULB

4'-0 x 5'-0 WINDOW

3'-0 x 4'-0 WINDOW

4- 4 TUBE FLOURESCENT LIGHTS x 4'-0

4'-0 x 6'-8 BARRED DOOR

12 x 12 AIR VENT IN BRICK

5- MERCURY LIGHT FIXTURES THIS CORRIDOR

3'-0 x 6'-8 METAL DOOR

3'-0 x 7'-0 BARRED DOOR

3'-0 x 7'-0 DOOR

PORTABLE FLOOR FAN 3 BLADES - 30" DIA. 1/4 H.P., 800/1100 R.P.M.

FLOOR PLAN

APPROVALS:	D.C. DEPARTMENT OF CORRECTIONS OFFICE OF THE CHIEF ENGINEER
SUPERINTENDENT	D.C. CENTRAL FACILITY
	CONTROL CELLS
CHIEF ENGINEER	DRAWN BY: [illegible] DATE:
	CHECKED BY: DATE:
	SCALE: 1/4"=1'-0" SHEET 1 OF 1

CON-XX-042