Physician's Residence

D. C. Workhouse and Reformatory Historic District

Lorton, VA

Historic Structure Report

Physician's Residence

Historic Structure Report

For:

Fairfax County, Virginia
Department of Planning
and Zoning

June, 2009

Prepared By:

Frazier Associates, Architects

with

Lardner/klein, Landscape Architects

and

Wiley/Wilson, Engineers

Acknowledgements

Fairfax County Staff

Department of Planning and Zoning

Chris Caperton
Laurel Hill Project Coordinator

Linda Cornish Blank
Historic Preservation Planner

Leanna Hush O'Donnell
Planner III

Facilities Management Department

Marguerite Verville Guarino
Assistant Director,
Real Estate Development and Planning

John Howard
Project Manager

Luis O. Lopez
Management Analyst III

Fairfax County Park Authority

Kelly Davis
Project Manager,
Special Projects Branch

Elizabeth Crowell
Manager,
Cultural Resource Management and Protection

Karen Lindquist
Historic Preservation Program Coordinator,
Cultural Resource Management and Protection

Other

Mr. Ron Lipscomb
Former Resident, Physician's Residence

Project Consultants

Frazier Associates
ARCHITECTURE ▪ COMMUNITY DESIGN ▪ WAYFINDING
213 NORTH AUGUSTA STREET, STAUNTON, VA 24401
PHONE 540.886.6230 FAX 540.886.8629
www.frazierassociates.com

L/KLA
Lardner/Klein Landscape Architects, P.C.

Wiley|Wilson™
Constant Progress

Copyright © 2009 Frazier Associates, Lardner/Klein Landscape Architects, PC, Wiley/Wilson, Engineers, and Fairfax County. All rights reserved. No part of this publication, including text, photographs, illustrations, cover design, and icons, may be reproduced or transmitted in any form, by any means (electronic, photocopying, recording, or otherwise) without the prior written permission of the publishers. This document may be reproduced in whole or part for use in matters related to the Physician's Residence Project without prior written permission.

Contents

Executive Summary 1

I. Introduction

A. Purpose of Report 3
B. Preservation Objectives 3
C. Methods of Evaluation 4

II. Developmental History

A. Location of Property 5
B. Historic Background and Context 6
C. Architectural Evolution of the House 10
1. South Elevation 11
2. East Elevation 11
3. North Elevation 12
4. West Elevation 12
D. Evaluation of Significance 13

III. Property Description, Assessment, and Recommendations

A. Site 15
1. General Setting and Orientation 15
2. Outbuildings 16
3. Driveways, Parking, Sidewalks, and Patios 17
4. Yards and Plantings 18
5. Other Site Features 20
B. Exterior 21
1. Introduction and Existing Exterior Elevation Drawings 21
2. Foundation 24
3. Walls: Main House 25
4. Walls: Sunroom 26
5. Porches 27
6. Chimneys 28
7. Exterior Doorways and Doors 29
8. Windows and Shutters 30
9. Roof 31
10. Cornice, Eaves, and Gutters 32
11. Dormers 33

III. Property Description, Assessment, and Recommendations, cont'd

C. Interior 34

1. Floor Plans – Existing 34
   a. Basement 34
   b. First Floor 36
   c. Second Floor 38
   d. Attic 40
2. Stairways 41
3. Flooring 42
4. Wall and Ceiling Finish 43
5. Doorways and Doors 44
6. Decorative Features and Trim 45
7. Hardware 46
8. Building Systems 47
   a. HVAC 47
   b. Electrical and Lighting 47
   c. Plumbing 48
9. Structural System 49
10. Hazardous Materials 55

IV. Building Treatment Approach

A. Standards for the Treatment of Historic Buildings 57

B. Applying the Standards to the Physician's Residence 58

C. Treatment Zone Plans 59

1. South Elevation 59
2. North Elevation 59
3. East Elevation 60
4. West Elevation 60
5. Basement 61
6. First Floor 61
7. Second Floor 62
8. Attic 62

V. Architectural Program Considerations

A. Owner Program 63

B. Tenant Considerations 63

1. Shared Spaces 63

2. Handicap Access 63
3. Tenant Floor Plan Alternatives 64
a. Alternative 1 - Single Tenant 64
b. Alternative 2 - Three Tenants and Shared Space 65
c. Alternative 3 - Four Tenants and Shared Space 67
d. Alternative 4 - Five Tenants and Shared Space 68
C. Space Planning Criteria 70
1. Typical Office Sizes for Fairfax County Facilities 70
2. Built-in Workstations 70
D. Building Code Analysis 71
1. Governing Codes 71
2. Historic Buildings 71
3. Construction Type 71
4. Type of Occupancy 71
5. Area 71
6. Height 71
7. Building Elements and Materials (IEBC 703) 72
8. Fire Protection Systems 72
9. Occupancy (Table 1004.1.2) 72
10. Egress (IEBC 705) 72
11. Accessibility (ADAAG) 73
12. Minimum Plumbing Fixtures 73
13. Energy Conservation (IEBC Section 711) 73
14. Zoning 74
E. Preservation Policies 75

VI. Design Options and Cost Estimates

A. Introduction of Options and Criteria for Analysis 77
B. Criteria to Analyze Options 77
1. Overall Goals for Related Fairfax County Projects 77
2. Historical Significance of House and Site 77
3. Current Condition of House and Site 77
4. Range of Possible Uses that Fit House and Site 77
5. County, State, and National Historic Preservation Standards and Policies 77
6. Funding Amounts and Availability 77
7. Schedule Considerations 78
8. Operational Responsibilities 78

VI. Design Options and Cost Estimates, cont'd

C. Site Design Options 79

1. Option A1 (11 Spaces) 80
2. Option A2 (18 Spaces) 81
3. Option B1 (11 Spaces) 82
4. Option B2 (18 Spaces) 83

D. Building Design Options 84

1. Option 1 (Optimal Use of Building) 84
   a. Basement Floor Plan - Option 1 85
   b. First Floor Plan - Option 1 85
   c. Second Floor Plan - Option 1 86
   d. Attic Plan - Option 1 86
   e. South Elevation - Option 1 87
   f. North Elevation - Option 1 87
   g. West Elevation - Option 1 87
2. Option 2 (Increased Use of Building) 88
   a. Basement Floor Plan - Option 2 89
   b. First Floor Plan - Option 2 89
   c. Second Floor Plan - Option 2A 90
   d. Second Floor Plan - Option 2B 90
   e. Attic Plan - Option 2 91
   f. South Elevation - Option 2A and Option 2B 92
   g. North Elevation - Option 2A 92
   h. North Elevation - Option 2B 92
   i. West Elevation - Option 2A 93
   j. West Elevation - Option 2B 93
3. Building Options – Comparative Analysis 94
   a. Option 1 (Optimal Use of Building) 94
   b. Option 2 (Increased Use of Building) 94
   c. Space Utilization Summary – Office/Workstation Totals 94

E. Explanation of Cost Estimates 95

F. Cost Estimates 96

1. Option 1 (Optimal Use of Building) 96
2. Option 2 (Increased Use of Building) 98

Appendices

1. Memorandum of Agreement (MOA) 101
2. Bibliography 115
3. Additional Resources 117