




HMD Tranportation Advisory Council

May 11, 2011
BRIDGE REHABILITATION
BRIDGE ON RTE. 675 (BEULAH RD.)
OVER DULLES TOLL & ACCESS ROAD
FAIRFAX COUNTY

PROJ. No. 0675-029-944, Pier 3 Ext. (UPC 99540)
PROJ. No. 0675-029-945, Span 2 & Bridge Wid. (UPC 99541)







DAMAGED BEAM







Span 2, Beam 4: Crack in bottom flange and web due to November 2010 collision impact



TEMPORARY REPAIR






Span 2, Beam 4: Temporary repair completed in November 2010



SPAN REPLACEMENT OVER EB DTR




Entire Span 2 over EB DTR will be replaced to increase existing vertical clearance

New vertical clearance increased from 14 ft to 15 ft will require a design exception.




EXISTING BRIDGE TYPICAL SECTION



Existing bridge section consist of 24'-0" clear roadway and 1'-6" wide safety walks each side of the bridge.



EXISTING BRIDGE TYPICAL SECTION



- Widen bridge to maintain 2 traffic lanes during construction
- Use additional deck area to add exterior shoulders for each lane plus a sidewalk



Aerial View of Proposed Widening & Span Replacement



Proposed widening to west side, span 2 replacement and extended sidewalks




RIGHT OF WAY





TRAIL MAP





















Project Schedule & Cost

Proposed Project Schedule

| Complete Design | September 2011 |
|--------------------|------------------|
| Pier 3 Extension | June-August 2011 |
| Advertise Project | January 2012 |
| Start Construction | April 2012 |
| End Construction | August 2013 |

Cost Estimate

| | Approximate Cost Estimate | | | | |
|----------------------------------|---------------------------|-----|-------------|-------------|--|
| | PE | R/W | CN | Total | |
| Pier 3 Extension | \$110,000 | 0 | \$220,000 | \$330,000 | |
| Span 2 Repl & Bridge Widening | \$609,000 | 0 | \$3,738,000 | \$4,347,000 | |
| TOTAL | \$719,000 | 0 | \$3,958,000 | \$4,677,000 | |



THANK YOU