



# County of Fairfax, Virginia

## NOTICE OF AWARD

Date of Award: 9/15/2025

Multiple Awards were made as a result of IFB 2000004109. To review other contract awards you can search the contract register <http://www.fairfaxcounty.gov/contracts> by Contract Description "Asphalt Paving Services".

**CONTRACT TITLE:** Asphalt Paving Services

**SOLICITATION NUMBER:** IFB 2000004109

**CONTRACT NUMBER:** **4400014229**

**NIGP CODE:** 91394, 91396

**CONTRACT PERIOD:** Date of Award through December 31, 2030

**PRICES:** See Attached Pricing Schedule

**TERMS:** Net 30 Days

### **PART 2: WALKWAYS – PRIMARY**

**CONTRACTOR:**  
Tibbs Paving, Inc  
9320 Developers Drive  
Manassas, VA 20109.

**SUPPLIER CODE:**  
1000009989

Contact: Timothy Reed  
Telephone: (703) 330-1789  
E-mail: [accounting@tibbspaving.com](mailto:accounting@tibbspaving.com)

---

**DPMM CONTACT:** Katie Dawson, Contract Specialist  
Telephone: (703) 246-4516  
E-mail: [kathryn.dawson@fairfaxcounty.gov](mailto:kathryn.dawson@fairfaxcounty.gov)

### **ORDERING INSTRUCTIONS:**

Any Fairfax County Government Department and Fairfax County Public Schools may enter into FOCUS a shopping cart indicating the item/service required, the quantity, the payment terms and the delivery date. The shopping cart must be annotated with the contract number. Requests exceeding the small purchase threshold (\$10k) will be routed to DPMM and a purchase order will be executed.

DocuSigned by:  
**Kathryn Dawson**  
D27D7A3A9CC7407

Katie Dawson  
Contract Specialist I

**DISTRIBUTION:**  
DPWES - MSMD – Peter Vigliotti/e  
Park Authority – Bushra Mirza/e

Contract Specialist: Katie Dawson  
Assistant Contract Specialist – Team 2

---

**Department of Procurement & Material Management**  
12000 Government Center Parkway, Suite 427  
Fairfax, VA 22035-0013  
**Website:** [www.fairfaxcounty.gov/procurement](http://www.fairfaxcounty.gov/procurement)  
**Phone** 703-324-3201, **TTY:** 711, **Fax:** 703-324-3228

Notice of Award  
Contract 4400014229  
Page 2

**PART 2 -WALKWAYS**

ITEM #	ITEM DESCRIPTION	UOM	UNIT PRICE
<b>SECTION 1: UNIT PRICING TYPE 1 TRAIL ASPHALT PAVING AND OTHER TYPE 1 WALKWAYS</b>			
#1-1	SM-9.5A - 1 inch	SY	\$ 4.50
#1-2	SM-9.5A - 2 inches	SY	\$ 16.00
#1-3	SM-9.5A - 3 inches	SY	\$ 18.50
#1-4	Prime/Tack Coat	SY	\$ 1.15
#1-5	21-A Stone	TN	\$ 33.00
#1-6	1 inch deep mill	SY	\$ 3.50
#1-7	2 inch deep mill	SY	\$ 3.50
#1-8	3 inch deep mill	SY	\$ 4.50
#1-9	4" New Concrete sidewalk including 4" 21-A stone base	SY	\$ 75.00
#1-10	6" New Concrete walkway (8' wide) inc. 4" 21-A stone base and #4 Rebar 24" O.C.	SY	\$ 85.00
#1-11	4" Remove and replace Concrete sidewalk including 4" 21-A stone base	SY	\$ 82.00
#1-12	Remove & Replace 2" asphalt trail including 4" 21-A stone base	SY	\$ 46.00
#1-13	PFM Type II stone dust trail 2" compacted stone dust with 4" 21-A stone base	SY	\$ 14.00
#1-14	4" Concrete Trail section including 1'x 6" wide turn-down edge on 4" 21-A stone base	SY	\$ 40.00
<b>SECTION 2: UNIT PRICING TYPE 2 TRAIL ASPHALT PAVING AND OTHER TYPE 2 WALKWAYS</b>			
#2-1	SM-9.5A - 1 inch	SY	\$ 4.50
#2-2	SM-9.5A - 2 inches	SY	\$ 17.50
#2-3	SM-9.5A - 3 inches	SY	\$ 20.00
#2-4	Prime/Tack Coat	SY	\$ 1.15
#2-5	21-A Stone	TN	\$ 33.00
#2-6	# 2 Crushed Stone 2½ to 3" (For base or shoulder work)	TN	\$ 40.00
#2-7	1 inch deep mill	SY	\$ 4.50
#2-8	2 inch deep mill	SY	\$ 4.50
#2-9	3 inch deep mill	SY	\$ 7.00
#2-10	4" New Concrete sidewalk including 4" 21-A stone base	SY	\$ 75.00
#2-11	4" Remove and replace Concrete sidewalk including 4" 21-A stone base	SY	\$ 78.00
#2-12	6" New Concrete walkway (8' wide) inc. 4" 21-A base and #4 Rebar 24" O.C.	SY	\$ 80.00
#2-13	PFM Type II stone dust trail 2" compacted stone dust with 4" 21-A stone base	SY	\$ 16.00
#2-14	PFM Type I asphalt trail with 2" asphalt and 4" 21-A stone base	SY	\$ 24.00
#2-15	Remove & Replace 2" asphalt trail including 4" 21-A stone base	SY	\$ 49.00
#2-16	6" Concrete Trail including a 1'x 6" wide turn-down edge on 4" 21-A stone base	SY	\$ 85.00
<b>SECTION 3: LABOR AND EQUIPMENT RATES (MINIMUM 4 HOURS)</b>			
<b>MISCELLANEOUS CHARGES, NOT IN SECTION 1 &amp; 2</b>			
#3-1	Mini Roller (with Operator)	HR	\$ 18.00
#3-2	Dump truck (with driver)	HR	\$ 27.00
#3-3	Rubber tire front end loader (with Operator)	HR	\$ 18.00
#3-4	Backhoe (with Operator)	HR	\$ 18.00
#3-5	Skid Steer (with Operator)	HR	\$ 18.00
#3-6	Utility Vehicle (with Operator)	HR	\$ 18.00
#3-7	Removal of excess materials from site, (includes truck, driver & dump fees)	CY	\$ 34.00
#3-8	Laborer	HR	\$ 25.00
#3-9	Traffic Control	HR	\$ 145.00
#3-10	Transfer materials to small equipment and haul 500 LF	TN	\$ 18.00
<b>SECTION 4: UNIT PRICE FOR TRAIL RELATED SITE WORK</b>			
<b>MISCELLANEOUS CHARGES, NOT IN SECTION 1 &amp; 2</b>			
#4-1	Regular excavation & disposal	CY	\$ 45.00
#4-2	Cut to fill / onsite material	CY	\$ 14.00
#4-3	Clean and fill material	CY	\$ 14.00
#4-4	#57 Stone	TN	\$ 40.00
#4-5	Import & place /select material (Min, CBR-15)	CY	\$ 30.00
#4-6	Excavate 3 ft. wide drainage trench (average max 3ft) to outfall	LF	\$ 5.80
#4-7	Excavation were owner has directed additional depths beyond 6"	CY	\$ 5.80
#4-8	Core-drill to determine depth of asphalt and stone	EA	\$ 5.80
#4-9	Saw Cut in asphalt trail	LF	\$ 1.15
#4-10	Topsoil	CY	\$ 105.00
#4-11	Tree trimming	HR	\$ 25.00

Notice of Award  
 Contract 4400014229  
 Page 3

**PART 2 -WALKWAYS**

<b>ITEM #</b>	<b>ITEM DESCRIPTION</b>	<b>UOM</b>	<b>UNIT PRICE</b>
#4-12	Tree Root Pruning: saw cut 4' on each side of root intrusions and remove asphalt layer. Add 2" 21-A aggregate & compact to receive asphalt pavement on top.	SY	\$ 12.00
#4-13	Tree root removal	HR	\$ 80.00
#4-14	Tree Stump Removal (grind stump & backfill) 1" to 12" Diameter	EA	\$ 120.00
#4-15	Tree Stump Removal (grind stump & backfill) 13" to 24" Diameter	EA	\$ 240.00
#4-16	Tree Stump Removal (grind stump & backfill) 25" + Diameter	EA	\$ 290.00
#4-17	Cut down Tree and Chip branches: 6" to 12" Diameter	EA	\$ 400.00
#4-18	Cut down Tree and Chip branches: 13" to ≥ 24" Diameter	EA	\$ 880.00
#4-19	Cut down Tree and Chip branches: 25"+ Diameter	EA	\$ 1,500.00
#4-20	Steel edging installation along stone dust trails. (Edging is 1/8" by 6-inch in 10 foot lengths)	FT	\$ 25.00
#4-21	Ground Protection mats	SY	\$ 4.50
#4-22	Safety fence	FT	\$ 1.15
#4-23	Seeding to include fertilizer, lime, temporary/degradable rolled erosion control products (RECP). Initial watering is to be included in the price.	SY	\$ 2.50
#4-24	Sod to include fertilizer, lime, straw	SY	\$ 5.50
#4-25	Caulking (material & installation)	LF	\$ 4.50
#4-26	Truncated Domes (furnished & installed)	SF	\$ 80.00
#4-27	Handrails (DOJ 2010 ADA Standards for Accessible Design – Section 505 compliant)	LF	\$ 100.00
#4-28	ADA warning strip	EA	\$ 50.00
#4-29	Concrete Treated Aggregate, placed (CTA)	TN	\$ 45.00
#4-30	Class I Rip Rap, placed	TN	\$ 68.00
#4-31	Class II Rip Rap, placed	TN	\$ 92.00
#4-32	Class III Rip Rap, placed	TN	\$ 110.00
#4-33	Erosion Control 9'x6'x6" Reno Mattress, coated Wire diam. 0.087 in., supply and install, including stone per specifications	EA	\$ 400.00
#4-34	Erosion Control 6'x3'x3' Gabion Baskets, Mesh type 8x10, Wire diam. 0.120 in supply and install, including stone per specifications	EA	\$ 350.00
#4-35	Filter Fabric – VA Erosion and Se. Control Handbook, staked	SY	\$ 2.30
#4-36	2" asphalt trail (SM-9.5A) including 4" 21-A stone base and 8" surge stone sub-base on Mirafi 500x fabric or equivalent from VDOT's approved material list.	SY	\$ 53.00
#4-37	Seeding with Ernst native seed mix and annual rye and straw mulch	SY	\$ 1.75
#4-38	Crack filling	LF	\$ 1.00
#4-39	3-rail split rail fence	LF	\$ 17.50
#4-40	4-rail split rail fence	LF	\$ 28.00
#4-41	HR-1 metal guard rail, galvanized per VDOT Bridge Standards	LF	\$ 185.00
#4-42	HR-2 metal guard rail, galvanized per PFM	LF	\$ 197.00
#4-43	8"-12" HDPE culvert, installed	LF	\$ 24.00
#4-44	15" – 18" HDPE culvert, installed	LF	\$ 60.00
#4-45	24"-30" HDPE culvert, installed	LF	\$ 60.00
#4-46	36"-48" HDPE culvert, installed	LF	\$ 107.00
#4-47	54"-60" HDPE culvert, installed	LF	\$ 232.00
#4-48	8'-12" HDPE end sections, installed	EA	\$ 313.00
#4-49	15"-18" HDPE end sections, installed	EA	\$ 445.00
#4-50	24"-30" HDPE end sections, installed	EA	\$ 465.00
#4-51	36"-48" HDPE end sections, installed	EA	\$ 695.00
#4-52	54"-60" HDPE end sections, installed	EA	\$ 1,045.00
#4-53	8"-12" RCP culvert, installed	LF	\$ 82.00
#4-54	15" – 18" RCP culvert, installed	LF	\$ 135.00
#4-55	24"-30" RCP culvert, installed	LF	\$ 140.00
#4-56	36"-48" RCP culvert, installed	LF	\$ 250.00
#4-57	54"-60" RCP culvert, installed	LF	\$ 300.00
#4-58	8'-12" RCP end sections, installed	EA	\$ 855.00
#4-59	15" – 18" RCP end sections, installed	EA	\$ 1,500.00
#4-60	24"-30" RCP end sections, installed	EA	\$ 1,600.00
#4-61	36"-48" RCP end sections, installed	EA	\$ 1,700.00
#4-62	54"-60" RCP end sections, installed	EA	\$ 1,800.00
#4-63	8"-12" pipe, Concrete headwall 8" thick wall per detail. (include footing 2' x 1')	EA	\$ 1,400.00

Notice of Award  
 Contract 4400014229  
 Page 4

**PART 2 -WALKWAYS**

ITEM #	ITEM DESCRIPTION	UOM	UNIT PRICE
#4-64	24"-30" pipe, Concrete headwall 10" thick wall per detail. (include footing 2.5' x 1')	EA	\$ 1,500.00
#4-65	36"-48" pipe, Concrete headwall 10" thick wall per detail. (include footing 3.5' x 1')	EA	\$ 1,500.00
#4-66	54"-60" pipe, Concrete headwall 12" thick wall per detail. (include footing 4' x 1')	EA	\$ 1,500.00
#4-67	8"-12" de-watering underdrain to outfall. (includes #57 stone cover per detail)	LF	\$ 6.00

**INSTALLATION OF BOLLARDS BOTH STATIONARY AND REMOVABLE LOCKING BOLARDS PER FAIRFAX COUNTY PFM.**

#5-1	Furnish and install new stationary bollard per Fairfax County PFM plate 10-8	EA	\$ 450.00
#5-2	Furnish and install new removable locking bollard per Fairfax County PFM plate 11-8	EA	\$ 750.00
#5-3	Furnish and install new stationary concrete filled 6" steel pipe bollard.	EA	\$ 500.00
#5-4	Furnish and install new collapsible, locking bollard (Reference ATTACHMENT E)	EA	\$ 750.00
#5-5	Furnish and install new stationary 6" wood bollard, painted, per Fairfax County PFM plate 9-8	EA	\$ 174.00