



County of Fairfax, Virginia

To protect and enrich the quality of life for the people, neighborhoods and diverse communities of Fairfax County

HD Number: 200830246

Date of Issue: 01/27/2022

Alternative Onsite Sewage System Operation Permit

OWNER

John & Sheri Rhodes

PROPERTY

222 Donmore Drive

Great Falls, Virginia 22066

Map Reference # 0022 020044A

The above owner and/or subsequent owner is hereby granted permission for the operation of an Alternative Onsite Sewage System at the above referenced property, having a 750 gallons/day daily flow for a 5 - bedroom dwelling.

The continued validity of this permit is contingent upon compliance with the operation and maintenance requirements contained in Part 3 of the Regulations for Alternative Onsite Sewage Systems of the Virginia Department of Health (12VAC5-613-120 et seq.). Owners are advised to be aware of the operation and maintenance requirements for their system, including the requirement to have the system maintained and operated by a licensed Alternative Onsite Sewage System Operator.


This Alternative Onsite Sewage System is required to be inspected and sampled by a qualified operator within 180 days from the date of this Operation Permit. Thereafter, the system must be inspected annually and sampled once every five years. Reports must be submitted in accordance with Section 12VAC5-613-190 of the *Regulations* and are due on the 15th of the month following the inspection.

Failure to submit the required inspection and sample results shall be deemed a violation of the *Regulations*.

The issuance of an operation permit does not denote or imply any guarantee by the department that the sewage disposal system will function for any specified period of time. It shall be the responsibility of the owner or any subsequent owner to maintain, repair, or replace any sewage disposal system that ceases to operate in accordance with the regulations.



Environmental Health
Specialist



Environmental Health
Supervisor




Gloria Addo Ayensu, M.D., MPH
Health Director

Fairfax County Health Department
Division of Environmental Health
Onsite Sewage and Water Section
10777 Main Street, Suite 102, Fairfax, VA 22030
Phone: 703-246-2201 TTY: 711 Fax: 703-278-8157
www.fairfaxcounty.gov/hd



BK 27527 1342



County of Fairfax, Virginia

To protect and enrich the quality of life for the people, neighborhoods, and diverse communities of Fairfax County

February 8, 2021

John Rhodes TR
74 S Player Crest Circle
Spring, TX 77382

RE: Sewage Disposal System Construction Permit
Constructed on/at: 222 Donmore Drive, Great Falls VA 22066
TM# 0022 02 0044A

Health Department ID Number: 200830246
System Capacity: 5 Bedrooms/750 gallons per day

Dear John Rhodes TR:

This letter and the attached drawings, specifications, calculations, and the attached documentation dated March 25, 2020 constitute your permit to install a sewage disposal system on the property referenced above.

The Fairfax County Health Department (FCHD) hereby recognizes that the design submitted by Brian H. Phillips, AOSE, has been certified by the designer to comply with the requirements of the Code of Virginia and grants permission to install the system as designed in the area shown on the attached plans and specifications.

The sewage disposal system design is approved based on a 1.25 gal/ft²/day loading rate at an install depth of 20". Chapter 68.1 of the Fairfax County Code requires a minimum gravel depth of eight inches under the installed percolation piping and two inches over the piping. A minimum of 12 inches and a maximum of 20 inches of clean backfill shall be placed over the gravel. Untreated building paper or other suitable material shall be placed at the interface of the gravel and soil. All trench widths are required to be 2 feet and be installed 6 feet center to center.

If modifications or revisions are necessary between now and when the system is constructed, please contact the OSE who designed the system upon which this permit is based. Should revisions be necessary during construction, your contractor should consult with the OSE. The OSE is authorized to make minor adjustments in the location or design of the system provided that adequate documentation is provided to FCHD.

The OSE that submitted the design for this permit is required by §32.1-164.1 of the Code of Virginia to inspect the system at the time of the installation and provide an inspection report and completion statement to FCHD. Chapter 68.1 of the Fairfax County Code requires that no part of the system shall be covered with earth or used until inspected, corrections made if necessary, and approved by the FCHD. The sewage system may not be placed into operation until you have obtained an Operation Permit from FCHD.

Fairfax County Health Department
Division of Environmental Health
Onsite Sewage and Water Section
10777 Main Street, Suite 102, Fairfax, VA 22030
Phone: 703-246-2201 TTY: 711 Fax: 703-278-8157
www.fairfaxcounty.gov/hd



BK 27527 1343


John Rhodes TR
Health Department ID Number: 200830246
February 8, 2021

This permit is issued in accordance with the provisions of Title 32.1, Chapter 6 of the Code of Virginia as Amended, and § 12VAC5-610-340 of the Sewage Handling and Disposal Regulations of the Virginia Department of Health. The continued validity of this permit is contingent upon compliance with the operation and maintenance requirements contained in Part 3 of the Regulations for Alternative Onsite Sewage Systems of the Virginia Department of Health (12VAC5-613-120 et seq.). Owners are advised to be aware of the operation and maintenance instructions for their permitted alternative onsite sewage system and to follow them. Copies of the operation and maintenance instructions can be found by contacting the local health department for the locality where the onsite sewage disposal system is located.

This Construction Permit is null and void if site and soil conditions are changed from those shown on your application or if conditions are changed from those shown on the attached plans and specifications. FCHD may revoke or modify any permit if, at a later date, it finds that the system would threaten public health or the environment.

This authorization to construct a sewage disposal system expires August 8, 2022. This permit is not transferable to another location.


Sincerely,



Crystal M. Crampton
Environmental Health Specialist



Kevin R. Wastler
Environmental Health Supervisor



County of Fairfax, Commonwealth of Virginia.

The foregoing instrument was acknowledged before me this 9th

day of February, 2021, by


Crystal M. Crampton and Kevin R. Wastler
(Name of person seeking acknowledgement)


Janice Joshi

Notary Public

My Commission Expires: December 31st, 2023

A COPY TESTE:
JOHN T. FREY, CLERK

BY: 
Deputy Clerk

01/21/2022
RECORDED IN FAIRFAX COUNTY
TESTE: 
CLERK



County of Fairfax, Virginia

To protect and enrich the quality of life for the people, neighborhoods, and diverse communities of Fairfax County

February 8, 2021

John Rhodes TR
74 S Player Crest Circle
Spring, TX 77382

RE: Sewage Disposal System Construction Permit
Constructed on/at: 222 Donmore Drive, Great Falls VA 22066
TM# 0022 02 0044A

Health Department ID Number: 200830246
System Capacity: 5 Bedrooms/750 gallons per day

Dear John Rhodes TR:

This letter and the attached drawings, specifications, calculations, and the attached documentation dated March 25, 2020 constitute your permit to install a sewage disposal system on the property referenced above.

The Fairfax County Health Department (FCHD) hereby recognizes that the design submitted by Brian H. Phillips, AOSE, has been certified by the designer to comply with the requirements of the Code of Virginia and grants permission to install the system as designed in the area shown on the attached plans and specifications.

The sewage disposal system design is approved based on a 1.25 gal/ft²/day loading rate at an install depth of 20". Chapter 68.1 of the Fairfax County Code requires a minimum gravel depth of eight inches under the installed percolation piping and two inches over the piping. A minimum of 12 inches and a maximum of 20 inches of clean backfill shall be placed over the gravel. Untreated building paper or other suitable material shall be placed at the interface of the gravel and soil. All trench widths are required to be 2 feet and be installed 6 feet center to center.

If modifications or revisions are necessary between now and when the system is constructed, please contact the OSE who designed the system upon which this permit is based. Should revisions be necessary during construction, your contractor should consult with the OSE. The OSE is authorized to make minor adjustments in the location or design of the system provided that adequate documentation is provided to FCHD.

The OSE that submitted the design for this permit is required by §32.1-164.1 of the Code of Virginia to inspect the system at the time of the installation and provide an inspection report and completion statement to FCHD. Chapter 68.1 of the Fairfax County Code requires that no part of the system shall be covered with earth or used until inspected, corrections made if necessary, and approved by the FCHD. The sewage system may not be placed into operation until you have obtained an Operation Permit from FCHD.

Fairfax County Health Department

Division of Environmental Health
Onsite Sewage and Water Section
10777 Main Street, Suite 102, Fairfax, VA 22030
Phone: 703-246-2201 TTY: 711 Fax: 703-278-8157
www.fairfaxcounty.gov/hd




John Rhodes TR
Health Department ID Number: 200830246
February 8, 2021

This permit is issued in accordance with the provisions of Title 32.1, Chapter 6 of the Code of Virginia as Amended, and § 12VAC5-610-340 of the Sewage Handling and Disposal Regulations of the Virginia Department of Health. The continued validity of this permit is contingent upon compliance with the operation and maintenance requirements contained in Part 3 of the Regulations for Alternative Onsite Sewage Systems of the Virginia Department of Health (12VAC5-613-120 et seq.). Owners are advised to be aware of the operation and maintenance instructions for their permitted alternative onsite sewage system and to follow them. Copies of the operation and maintenance instructions can be found by contacting the local health department for the locality where the onsite sewage disposal system is located.

This Construction Permit is null and void if site and soil conditions are changed from those shown on your application or if conditions are changed from those shown on the attached plans and specifications. FCHD may revoke or modify any permit if, at a later date, it finds that the system would threaten public health or the environment.

This authorization to construct a sewage disposal system expires August 8, 2022. This permit is not transferable to another location.


Sincerely,



Crystal M. Crampton
Environmental Health Specialist



Kevin R. Wastler
Environmental Health Supervisor



County of Fairfax, Commonwealth of Virginia.

The foregoing instrument was acknowledged before me this 9th
day of February, 2021, by

Crystal M. Crampton and Kevin R. Wastler
(Name of person seeking acknowledgement)

Janice Joshi

Notary Public

My Commission Expires: December 31st, 2023

Record of Inspection - Private Water Supply System

Commonwealth of Virginia
Department of Health

Health Department

I.D. Number 200860270

F.H.A. or V.A. Case Number
If Applicable

Date 7-23-2020 Local Health Department Fairfax County

Owner John Rhodes Address 74 S Player Crest Circle Phone 703-341-9489
Spring, TX 77382

Exact Location of Premises 222 Danmore Drive Great Falls VA 22066

Subdivision Seneca Farms Section/Block 3 Lot 44A

Class of nonpublic drinking water well. 1) Class III A
2) Class III B X
3) Class III C
Date of installation 7-9-2020 4) Other

Northern Virginia Drilling

CONSTRUCTION INFORMATION

If information in any item below is secured from other sources (i.e. well log, etc.), so note.

1. Water well completion report filed as required by Sec. 2.18 Yes ☒ No ☐
2. Well Location: Distances from sources of pollution (See Table 3.1, Minimum Separation Distances) and Section 3.4 of the Private Well Regulations.
Building Sewer 50'+ Pretreatment Unit 50'+
Conveyance System 50'+ Subsurface Soil Absorption System 100'+
(nearest point). Property Line 50'+ Other
Site graded where necessary to divert water away from well? Yes ☒ No ☐ N/A ☐
3. Construction, General: (see Section 3.6 and 3.7 Private Well Regulations).
Total depth of well 560 feet. Type of casing Steel
Depth of casing 82 feet. Diameter of casing 6 inches.
Casing extends inches above ground 12". Exterior space sealed with neat cement grout to a depth of 55 feet. Screens constructed of N/A
free of rough edges and irregularities, with positive watertight seal between screen and casing?
Yes ☐ No ☐ N/A ☒ Well head and opening to the interior protected? Yes ☒ No ☐
Type of well seal Watertight Pitless adapter used? Yes ☒ No ☐ N/A ☐
Properly installed? Yes ☒ No ☐ N/A ☐ Proper venting? Yes ☒ No ☐ N/A ☐
4. Quantity: Yield and drawdown determined by continuous pumping of 1 hours. Drawdown feet. Yield 20 GPM. Type of storage Constant Pressure.
5. Quality: Sample tap provided at entry into system? Yes ☒ No ☐ Samples(s) collected? Yes ☒ No ☐
Results of samples. Satisfactory ☒ Unsatisfactory ☐ (attach copy of results of this form)

Based on the inspection of this water supply system and the information contained on the water well completion report attached, this water supply meets ☒ does not meet ☐ the requirements of the Private Well Regulations.

Remarks: 0-28': overburden; 28-35': sandstone; 35-73' grey granite;
73-78': void; 78-420': grey granite; 420'-495': blue granite;
495-560': grey granite

Date 1/26/22

Signed James Lakota

Date 1/27/22

Signed John Rhodes

Sanitarian

Date

Signed

Supervisory Sanitarian



County of Fairfax, Virginia

To protect and enrich the quality of life for the people, neighborhoods and diverse communities of Fairfax County

June 24, 2020

John Rhodes
74 S Player Crest Circle
Spring, TX 77382

RE: Private Well Construction Permit
Constructed on/at: 222 Donmore Dr
Great Falls, Virginia 22066
Tax map #: 0022 02 0044A

Health Department ID Number: 200860270

John Rhodes,

This letter and the attached site plan, dated June 17, 2020 from the *Certified Master Water Well System Provider*, constitute your permit to install a "Private Well" on the property referenced above. Your application for a permit was submitted pursuant to § 32.1-176.5:2 of the Code of Virginia, which requires the Virginia Department of Health (VDH) to accept designs for "Private Wells" from individuals licensed as *Certified Master Water Well System Provider*.

The Fairfax County Health Department (FCHD) hereby recognizes that the design submitted by Scott W. Miller, *Certified Master Water Well System Provider*, complies with the requirements of the Code of Virginia and grants permission to install the "Private Well" as designed in the area shown on the attached plans and specifications. This permit is not transferable to another location. Valid construction permits for "Private Wells" are transferable to new property owners.

If modifications or revisions are necessary between now and when the system is constructed, please contact the *Certified Master Water Well System Provider* who designed the system upon which this permit is based. Should revisions be necessary during construction, your contractor should consult with the *Certified Master Water Well System Provider*. The *Certified Master Water Well System Provider* is authorized to make minor adjustments in the location or design of the well if adequate documentation is provided to FCHD. In all cases, it shall be the landowner's responsibility to ensure that the water well is properly located on the landowner's property.

Fairfax County Health Department
Division of Environmental Health
Onsite Sewage and Water Section
10777 Main Street, Suite 102, Fairfax, VA 22030
Phone: 703-246-2201 TTY: 711 Fax: 703-278-8157
www.fairfaxcounty.gov/hd



June 24, 2020

John Rhodes

Health Department ID Number: 200860270

Pursuant to § 32.1-176.6 code of Virginia, FCHD shall have the authority to conduct such inspections as it may find reasonably necessary to ensure that the construction work conforms to applicable construction standards. The following items are required to be inspected or completed by FCHD:

- Inspection of the well prior to the grout pour and during the grout pour.
- Inspection of the "pitless" adapter.
- Bacteriological water sample analysis.
- Inspection of the final grading around the well.

Chapter 70.1 of the Fairfax County Code requires that no person shall place a private well in operation, or cause or allow a private well to be placed in operation, without obtaining a written inspection statement pursuant to 12VAC 5-630-310 and 12VAC 5-630-330. Prior to inspection statement being issued by FCHD, a copy of a Uniform Water Well Completion Report shall be provided to FCHD within 30 days of the completion of the well or completion of alterations thereto. The *Certified Master Water Well System Provider* shall perform a final inspection for the "Private Well" and provide inspection completion report to the FCHD.


This permit is issued in accordance with the provisions of Title 32.1, Chapter 6 of the Code of Virginia as Amended, and § 12VAC 5-630-230 of the Private Well Regulations of the Virginia Department of Health. This well construction permit is null and void when (i) conditions such as house location, sewage system location, sewerage system location, topography, drainage ways, or other site conditions are changed from those shown on the application, (ii) conditions are changed from those shown on the construction permit, or (iii) more than 54 months elapse from the date the permit was issued. Reapplication for the purposes of having an expired permit reissued shall be the responsibility of the owner, and such reapplication shall be handled as an initial application and comply fully with 12VAC 5-630-230.

The commissioner may revoke a construction permit or inspection statement for any of the following reasons:

- Failure to comply with the conditions of the permit;
- Violation of any part of this chapter for which no variance has been issued;
- Facts become known which reveal that a potential health hazard would be created or that the ground water resources may be adversely affected by allowing the proposed well to be installed or completed. (12VAC 5-630-290)

This authorization to construct a "Private Well" expires 54 months from the issue date.

Sincerely,



James LaRosa

Environmental Health Specialist


FAIRFAX COUNTY HEALTH DEPARTMENT
SEWAGE DISPOSAL SYSTEM/WELL WATER SUPPLY AS-BUILT

Tax Map ID: 022 02 0044a

Street Address: 222 Donmore Drive

Subdivision: Seneca Farms Sec. 3 Lot 44A

City, State, Zip: Great Falls, Virginia 22066



Completion Statement

Commonwealth of Virginia
State Department of Health

JAN 19 REC'D

22 - 2 - 44A

Health Department
Identification Number:

Fairfax County

Health Department

Name of Company/Corporation/Individual: Settle Excavating & Plumbing, LLC

Address: 332 W. Lee Hwy PMB 250 Warrenton, VA 20186

Telephone: 703-772-4040

Owner's Name: _____

Owner's Address: 222 Donmore Drive, Great Falls VA 22066

Location of Installation: Lot: 44A

Block: _____

Section: 3

Subdivision: Seneca Farms

Other: _____

I hereby certify that the onsite sewage disposal system has been installed and completed in accordance with the construction permit issued
(Date) 3/25/2020 and is in compliance with Part D of the Sewage Handling and Disposal Regulations and when appropriate the plans and
specifications for the project.

18 Jan 2022

Date

James R. Settle

Signature and Title

Onsite Sewage System Installer License
Master Alt. # 1944001662

1043

AOSE/PE Inspection Report and Completion Statement

Commonwealth of Virginia
State Department of Health

Fairfax County Health Department

Health Department ID #: 200830246

Tax Map ID: 2-2-02-044A

Name of AOSE/PE: Brian H. Phillips

License # 1940001374

Contactors Name: Settle Excavating and Plumbing

License # 27010032072

Owner's Name: John and Sheri Rhodes

Owner's Address: 74 South Player Crest Circle

The Woodlands, TX 77382

Location of Installation: 222 Donmore Drive, Great Falls, VA 22066

Subdivision: Seneca Farms


Block:

Section:

Lot: 44A

Inspection Results		
Component	Comments, Materials, Etc. Deficiencies Observed, Date Deficiencies Observed, Corrective Actions Required	Date Approved
Water Supply Location and Construction	Class IIIB well, measurements pulled. Well permit # 200860270 & 210420206. By others. See note below.	*
Building Sewer	4" SCH40 PVC; >1 1/4" fall per 10'	3/26/2021
Septic Tank	1500 Gallon Hanover TJ Tank w/ATU	3/26/2021
Inlet-Outlet Structure	Sealed Unit	3/26/2021
Pump and Pump Station	2000 gallon Hanover TS Tank w/ Zoeller N98 pump. 450gal ADF, 112.5 gal/dose, 4 doses/day. 42 GPM; Run =2:39m, Rest=6h. P1: Ct=6, ETM=0:00h. P2: Ct=16, ETM=00:02h. Peak Ct=7, Alarm Ct=5.	1/6/2022
Conveyance Method	2" SCH40 PVC force main.	3/26/2021
Distribution Box or Pressure Manifold	6 port concrete surge box supplying 10 port concrete d-box with plastic levelers , both on concrete pads.	3/26/2021
Header, Conveyance, Drip, Chambers, Etc.	4" SCH40 PVC	3/26/2021
Absorption Trenches and Dispersal Field	5 trench laterals, each 75' long, 2' wide, and 6' on center. 4" black plastic perforated, corrugated drain pipe.	3/26/2021
(Other Components: Treatment Unit, etc.)	MicroFAST 0.75 ATU	1/6/2022
Note	Well location was changed by driller and builder. Soils, Inc. was not notified of the change and had no input as to the new location and was permitted by others.	*

Attach observed deficiencies and corrective actions taken on a separate completion statement as necessary



2.43

AOSE/PE Completion Statement: As-Built Drawing


Commonwealth of Virginia
State Department of Health

Health Department ID Number: 200830246

Tax Map # 2-2-02-044A

Triangulate critical system components to fixed reference points.

See attached as-built



☒ Check here if the as built is on a separate page attached to this form.
(Attachment must display Health Department ID number, tax map number, and must be signed & dated by the AOSE/PE)

I hereby certify that on 1/6/2022 I, or an employee under my direct supervision, inspected this sewage system's construction. The onsite system has been installed and completed in accordance with the construction permit issued 2/9/2021 and is in compliance with the *Sewage Handling & Disposal Regulations (12VAC5-610 et seq)*, the *Alternative Onsite Sewage Regulations (12VAC5-613)*, and the *Private Well Regulations (12VAC5-630 et seq)*, when applicable, and the plans and specifications for this project.

AOSE/PE Signature: _____



Date: 1/25/2022

Print Name: Brian H. Phillips

3 of 3

12/10/20212 T1812

222 Donmore Drive
Great Falls, VA 22066
GPIN/TMID 2-2-02-0044A
HDID 200830246



SOILS INC.

- Well Tank to well = 291'
- Septic Tank & Grinder Pump Tank to Septic 119'
- Tank to closest property line 177'

LEGEND FOR GRADING PLANS


- EXISTING CONTOUR
PROPOSED CONTOUR
CASTING SPOT ELEVATION
PROPOSED SPOT ELEVATION
PROPOSED CLEARING LIMITS
TREE PROTECTION
STD & SPEC 3.38
DIT FENCE
STD & SPEC 3.05
CONSTRUCTION ENTRANCE
STD & SPEC 3.01
TEMPORARY SECTIONS
STD & SPEC 3.01
PERMANENT SECTIONS
STD & SPEC 3.02
CULVERT INLET PROTECTION
STD & SPEC 3.08
SUPER DIT FENCE
INLET PROTECTION
STD & SPEC 3.04
DIVERSION DUNE
STD & SPEC 3.08
RIGHT-OF-WAY DIVERSION
STD & SPEC 3.11
SEGMENT TIE-IN
STD & SPEC 3.07
----- DENOTES ROOT PRUNING

CULVERT / BRIDGE NOTE:

THE CULVERT / BRIDGE IS BEING PLACED WITHIN THE SWALE THAT CARRIES OFF-SITE RUNOFF THROUGH THE SITE. WORK TO INSTALL THE CULVERT / BRIDGE SHALL BE PERFORMED AS PART OF PHASE 2 CONSTRUCTION AND SHALL BE DONE SIMPLY BEHIND THE PROTECTION OF A DIVERSION DUNE. ONCE THE CULVERT IS INSTALLED AND THE AREA STABILIZED THE DUNE CAN BE REMOVED AT THE INSPECTOR'S DISCRETION. THE CULVERT SHALL BE COVERED WITH SOIL AND TOPPED OR STONE TO CREATE A NATURAL SWALE THROUGH THE CULVERT AND NOT HAVE A SMOOTH CONCRETE BOTTOM THAT WILL INCREASE FLOW VELOCITY.

PHASED CONSTRUCTION NOTE:

DUE TO THE LARGE SWALE AND AMOUNT OF OFFSITE WATER RUNNING THROUGH THE SITE AND ENTERING THE CULVERT UNDER DONMORE DRIVE A PHASED CONSTRUCTION DESIGN IS PROPOSED. THE FIRST PHASE WILL CONSIST OF THE HOUSE AREA, PROPOSED ROAD AND A PORTION OF THE DRIVEWAY. THIS AREA WILL BE MOVED AND STABILIZED PRIOR TO CONSTRUCTION WITHIN THE PHASE 2 WORK AREA WHICH CONSISTS OF THE REMAINDER OF THE DRIVEWAY, CULVERT BRIDGE AND SEPTIC FIELD. AT SITE INSPECTIONS DISCRETION THERE MAY BE MINIMAL OVERLAP OF WORK WITHIN THE TWO AREAS. THE PHASED DESIGN IS TO MAINTAIN OFF-SITE WATER FLOW THROUGH THE SITE IN THE LEAST DISRUPTIVE MANNER THROUGHOUT CONSTRUCTION. THIS SHEET SHOWS THE PHASE 2 CONSTRUCTION. THIS CONSTRUCTION WILL WORK WITHIN THE SWALE RUNNING THROUGH THE SITE. THE DESIGN CALLS FOR A 8" PVC LEVEL SPREADER AT THE UPPER SWALE CROSSING AND A DIVERSION DUNE AT THE LOWER PORTION TO DIRECT RUNOFF AROUND THE AREA OF CULVERT INSTALLATION. ONCE THE CULVERT IS INSTALLED AND THE AREA STABILIZED THEN THE DIVERSION DUNE CAN BE REMOVED AND THE SWALE ALLOWED TO FOLLOW ITS NATURAL COURSE. WORK WITHIN THE SWALE AREA SHOULD BE APPROACHED AS IF WORKING WITHIN A LIVE STREAM. WORK SHOULD BE SHIFT AND CEASE DURING TIMES OF MINIMAL RAIN. AREAS SHALL BE STABILIZED QUICKLY ONCE WORK IS COMPLETED.



PROPOSED DISTURBED AREA = 74,486 SF OR 1.71 ACRES

RETAINING WALL NOTE:

THE PROJECT PROPOSES RETAINING WALLS OF VARIOUS HEIGHTS. ANY NEW RETAINING WALL OVER 30 INCHES (2.5' IN HEIGHT) SHALL REQUIRE A SEPARATE PERMIT AND SHALL BE DESIGNED BY OTHERS. THIS PLAN IS SHOWING THE GRADES AND LOCATION FOR THE WALLS AND DOES NOT CONSTITUTE A FULL DESIGN FOR PERMIT. WALL TYPE, FOUNDATION, SUPPORT, TIE-BACKS AND MATERIALS SHALL BE DETERMINED BY THE DESIGN ENGINEER FOR DURING THE WALL INSTALLATION PROCESS.

REVISION NOTE:

THIS REVISION IS FOR THE REVISION OF THE PROPOSED. DETERMINING THE FINAL SITE. THIS WAS REQUIRED TO REMOVE A DRAINAGE STRUCTURE AREA, UNDERSTANDING AND TO SOFTEN GRADES ALONG SIDES OF ROAD.

GRAPHIC SCALE
SCALE 1"=20'
SCALE 1"=20'

CIVIL SPUR

SITE PLANNING - DESIGN - CONSULTING
829 WEST BROAD STREET, SUITE 200, FALLS CHURCH, VA 22046
OFFICE (703) 883-7113 CELL (540) 207-5601
EMAIL: ROSE@CIVILSPUR.COM

PHASE 2 CONSTRUCTION PLAN
222 DONMORE DRIVE
FAIRFAX, VA 22031
DRANESVILLE DISTRICT #1
FAIRFAX, VIRGINIA

REVISION	DATE

SCALE 1"=20'



SHEET 30 OF 3




County of Fairfax, Virginia

To protect and enrich the quality of life for the people, neighborhoods, and diverse communities of Fairfax County

February 25, 2021

John Rhodes TR
74 S Player Crest Circle
Spring, TX 77382



RE: Private Well Construction Permit
Constructed on/at: 222 Donmore Drive
Great Falls, VA 22066
Tax map #: 0022 02 0044A

Health Department ID Number: 210420206

Dear John Rhodes TR,

This letter and the attached site plan, dated February 10, 2021 from the *Certified Master Water Well System Provider*, constitute your permit to install a "Private Well" on the property referenced above. Your application for a permit was submitted pursuant to § 32.1-176.5:2 of the Code of Virginia, which requires the Virginia Department of Health (VDH) to accept designs for "Private Wells" from individuals licensed as *Certified Master Water Well System Provider*.

The Fairfax County Health Department (FCHD) hereby recognizes that the design submitted by Scott W. Miller, *Certified Master Water Well System Provider*, complies with the requirements of the Code of Virginia and grants permission to install the "Private Well" as designed in the area shown on the attached plans and specifications. This permit is not transferable to another location. Valid construction permits for "Private Wells" are transferable to new property owners.

If modifications or revisions are necessary between now and when the system is constructed, please contact the *Certified Master Water Well System Provider* who designed the system upon which this permit is based. Should revisions be necessary during construction, your contractor should consult with the *Certified Master Water Well System Provider*. The *Certified Master Water Well System Provider* is authorized to make minor adjustments in the location or design of the well if adequate documentation is provided to FCHD. In all cases, it shall be the landowner's responsibility to ensure that the water well is properly located on the landowner's property.

Fairfax County Health Department

Division of Environmental Health
Onsite Sewage and Water Section

10777 Main Street, Suite 102, Fairfax, VA 22030
Phone: 703-246-2201 TTY: 711 Fax: 703-278-8157
www.fairfaxcounty.gov/hd



Pursuant to § 32.1-176.6 code of Virginia, FCHD shall have the authority to conduct such inspections as it may find reasonably necessary to ensure that the construction work conforms to applicable construction standards. The following items are required to be inspected or completed by FCHD:

- Inspection of the well prior to the grout pour and during the grout pour.

Chapter 70.1 of the Fairfax County Code requires that no person shall place a private well in operation, or cause or allow a private well to be placed in operation, without obtaining a written inspection statement pursuant to 12VAC 5-630-310 and 12VAC 5-630-330. Prior to inspection statement being issued by FCHD, a copy of a Uniform Water Well Completion Report shall be provided to FCHD within 30 days of the completion of the well or completion of alterations thereto. The *Certified Master Water Well System Provider* shall perform a final inspection for the "Private Well" and provide an inspection completion report to the FCHD.

This permit is issued in accordance with the provisions of Title 32.1, Chapter 6 of the Code of Virginia as Amended, and § 12VAC 5-630-230 of the Private Well Regulations of the Virginia Department of Health. This well construction permit is null and void when (i) conditions such as house location, sewage system location, sewerage system location, topography, drainage ways, or other site conditions are changed from those shown on the application, (ii) conditions are changed from those shown on the construction permit, or (iii) more than 54 months elapse from the date the permit was issued. Reapplication for the purposes of having an expired permit reissued shall be the responsibility of the owner, and such reapplication shall be handled as an initial application and comply fully with 12VAC5-630-230.

The commissioner may revoke a construction permit or inspection statement for any of the following reasons:

- Failure to comply with the conditions of the permit;
- Violation of any part of this chapter for which no variance has been issued;
- Facts become known which reveal that a potential health hazard would be created or that the ground water resources may be adversely affected by allowing the proposed well to be installed or completed. (12VAC5-630-290)

This authorization to construct a "Geothermal Well System" expires 54 months from the issue date.

Sincerely,



Crystal Crampton
Environmental Health Specialist II

Record of Inspection - Private Water Supply System

Commonwealth of Virginia
Department of Health

Health Department

I.D. Number 210420206

F.H.A. or V.A. Case Number
If Applicable

Date 02/25/2021

Local Health Department Fairfax

Owner John Rhodes

Address 745 PLAYER CREST CR.
SPRING, TX 77382

Phone _____

Exact Location of Premises 222 DON MORE DR, GREAT FALLS, VA 22066

Subdivision SENECA FARMS

Section/Block 3

Lot 44A

Class of nonpublic drinking water well. 1) Class III A _____

2) Class III B _____

3) Class III C _____

Date of installation 06/2/21 4) Other ✓ Geothermal X4

CONSTRUCTION INFORMATION

If information in any item below is secured from other sources (i.e. well log, etc.), so note.

1. Water well completion report filed as required by Sec. 2.18 Yes ☒ No ☐
2. Well Location: Distances from sources of pollution (See Table 3.1, Minimum Separation Distances) and Section 3.4 of the Private Well Regulations.

Building Sewer N/A

Pretreatment Unit N/A

Conveyance System N/A

Subsurface Soil Absorption System N/A

(nearest point). Property Line N/A

Other _____

Site graded where necessary to divert water away from well? Yes ☐ No ☐ N/A ☒

3. Construction, General: (see Section 3.6 and 3.7 Private Well Regulations).

Total depth of well 400 feet. Type of casing N/A

Depth of casing N/A feet. Diameter of casing N/A inches.

Casing extends inches above ground N/A. Exterior space sealed with neat cement grout to a depth of 400 feet. Screens constructed of N/A

free of rough edges and irregularities, with positive watertight seal between screen and casing? Yes ☐ No ☐ N/A ☒

Well head and opening to the interior protected? Yes ☐ No ☐ N/A ☒

Type of well seal N/A

Pitless adapter used? Yes ☐ No ☐ N/A ☒

Properly installed? Yes ☐ No ☐ N/A ☒

4. Quantity: Yield and drawdown determined by continuous pumping of N/A hours. Drawdown N/A feet. Yield N/A GPM. Type of storage N/A

5. Quality: Sample tap provided at entry into system? Yes ☐ No ☒ Samples(s) collected? Yes ☐ No ☒

Results of samples. Satisfactory ☐ Unsatisfactory ☐ (attach copy of results of this form) N/A

Based on the inspection of this water supply system and the information contained on the water well completion report attached, this water supply meets ☒ does not meet ☐ the requirements of the Private Well Regulations.

Remarks: _____

Date 06/29/21

Signed _____

James O'Leary

Date 6/30/21

Signed _____

Dr. [Signature]

Sanitarian

Date _____

Signed _____

Supervisory Sanitarian

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 210420206
VDH PWSID # _____
Geothermal

*Indicates required field or section
**Indicates required field or section, if applicable

1. Contact Information*

Contact:	Name	Address	Phone
Owner	John Rhodes TR	745 PLAZA CREST CJA SPRING TX	703-220-0269
Driller	AD. VA. DRILLING INC.	1136 INDUSTRIAL RD. MANASSAS VA	703-361-6859
System Provider	2719000310	1136 INDUSTRIAL RD. MANASSAS VA	703-361-6859

2. Well Location*

Physical Address:	<u>222 DOWNSIDE DR. GREAT FALLS V.A.</u>	County/City:	<u>FAIRFAX CO.</u>
Subdivision Name:	<u>SENECA FARM</u>	Section:	<u>3</u>
		Block:	
		Lot:	<u>44A</u>
Tax Map/GPIN #:	<u>22-02-0044A</u>		
Latitude:	<u>N</u>	Longitude:	<u>W</u>
Datum Source	Horizontal:	☐ WGS84 ☐ NAD83 ☐ NAD27	
Lat/Long Source (Check One):	☐ Map ☐ GPS ☐ PPDGPS ☐ Survey ☐ Imagery ☐ WAAS		
Location Information Collected By:	<u>2719000310</u>		
Physical Location Description:	<u>FRONT OF HOUSE NEAR FRONT STEOP</u>		

3. Facility & Use*

Type of Facility (Check One):	Type of Use (Check All That Apply):
☒ Private	☐ Drinking/Domestic Use ☐ Agricultural ☐ Food Processing
☐ Waterworks	☐ Manufacturing ☐ Irrigation ☐ Injection
☐ Observation/Monitoring Well	☒ Geothermal (Cooling/Heating) ☐ Fire Safety
	☐ Closed
	☐ Open: ☐ Returned to Surface
	☐ Returned to Aquifer

4. Well Construction*

Well designation, Name or Number	<u>210420206</u>				
Date Started:	<u>6-2-21</u>	Date Completed:	<u>6-14-21</u>	Type Rig:	<u>AIR ROTARY</u>
Class Well (Check One):	☐ I ☐ IIA ☐ IIB ☐ IIIA ☐ IIIB ☐ IIIC ☐ IIID ☐ IIIE ☒ IV				
Construction Type (Check One):	☒ New ☐ Existing-Modified:	☐ Well ☐ Pump:	Date		
Well Depth:	<u>400</u> ft.	Total Hole (borehole) Depth:	<u>400</u> ft.	Depth to Bedrock:	<u>96</u> ft.
Hole Size (Include reamed zones):	<u>6</u> inches from <u>0</u> to <u>400</u> ft.	Inches from		to	
Height of Casing above Land Surface:		ft.		inches	
Casing Size (I.D.) and Materials: (below)		Total Depth of Casing:		ft.	
inches from to ft. ☐ infilled		Material		Weight per ft.	or wall thickness in.
inches from to ft. ☐ infilled		Material		Weight per ft.	or wall thickness in.
inches from to ft. ☐ infilled		Material		Weight per ft.	or wall thickness in.
Screen Size & Mesh:					
inches from to ft. ☐ infilled		Mesh Size		Type	
inches from to ft. ☐ infilled		Mesh Size		Type	
inches from to ft. ☐ infilled		Mesh Size		Type	
Water Zones: from to ft.		from to ft.		from to ft.	
Gravel Pack:					
Size: Type:		from to ft.	Size: Type:		from to ft.
Grout Type:			Grouting Method:		Type of Seal:
☐ Bentonite Slurry ☐ Neat Cement		from to ft.	☐ Poured from surface		☐ pitless adapter
☐ Bentonite pellets/chips ☐ Concrete			☐ Poured through tremmie pipe		☐ sanitary seal
☐ Neat Cement (6% bentonite)		from to ft.	☐ Pumped from bottom upward		
Camera Survey: ☐ Yes ☐ No			Date Conducted:		
Additional Well Construction Form Information Attached:		☐ Yes ☐ No			

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 210420206
VDH PWSID # _____

Well designation, Name or Number: _____

5. Disinfection

Well Disinfected: ☐ Yes ☐ No Date: _____

6. Abandonment (*When abandoning the well, Sections 1 thru 4 must be completed and/or attach original GW-2)

Date Started:	Date Completed:
Static Water Level (unpumped level measured):	ft.
Casing Size (I.D.) and Materials:	Casing Pulled: ☐ Yes ☐ No ☐ Uncased Well
Depth of Fill:	Type and Source of Fill:
Grout: From <u>405'</u> to <u>0</u> Type: <u>RETAIN SURF</u>	From _____ to _____ Type: _____
Method of permanently marking location:	

7. Pump Test**

Static Water Level (unpumped level measured):	ft.
Date:	Method (Check One): ☐ Water Tape ☐ Airline ☐ Transducer ☐ Other
Stabilized measured pumping water level:	ft.
Date:	Method (Check One): ☐ Top of Well ☐ Top of Casing ☐ Surface Level
Test Pump Intake Depth:	ft. Stabilized Yield: _____ gpm after _____ hours
Natural Flow: ☐ Yes ☐ No	Flow Rate _____ gpm
Estimated Well Yield:	gpm

8. Pump Data**

Type: ☐ submersible ☐ Turbine ☐ Shallow Jet ☐ Deep Jet ☐ Other: _____	Motor HP: _____
Production Pump Intake Depth: _____ ft	Rated Capacity: _____ gpm at _____ ft TDH

9. Geologic Information

Type Logs: _____	Aquifer Test Performed: _____
Water Quality Results Attached: Yes ☐ No ☐	

Comments: 4-400FT. CLASS IV GEO-THERMAL WELLS
GROUTED FROM 400FT. TO GROUND SURFACE

Formation _____	Lithology _____	Province _____	Geologic Map Used _____
Elevation _____			
For Office Use			

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 210720206
VDH PWSID # _____

*Indicates required field or section
**Indicates required field or section, if applicable

10. Driller's Log (Use additional sheets if necessary)*

Well designation, Name or Number:				
Depth (feet)		Type of Rock or Soil	Remarks	Drilling Time (Min.)
From	To	(Color, material, fossils, hardness, etc.)	(Water, caving, cavities, etc.)	
0	96'	OVERBURDEN		
96	400'	Grey GRANITE		
6" HDPE 0 TO 400 FT. 1 1/4" HDPE GEO-THERMAL LOOP 0 TO 400 FT.				

11. Certification

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is to the best of my knowledge and belief true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations.

Signature*: _____

Date: 6-14-21

License Number: 2719000310

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 21042206
VDH PWSID # _____

*Indicates required field or section

**Indicates required field or section, if applicable

Additional Well Construction Data


(Use and submit only if additional space is needed)

12. Additional Well Construction Data

Well designation, Name or Number:											
Physical Location:				Date Started:				Date Completed:			
Hole Size (Include reamed zones):											
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
Casing Size (I.D.) and Materials:											
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
Screen Size & Mesh:											
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
Water Zones:											
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
Gravel Pack:											
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Grout Type:				from	to	ft.	Grouting Method:				
☐ Bentonite Slurry				from	to	ft.	☐ Poured from surface				
☐ Bentonite pellets/chips				from	to	ft.	☐ Poured through tremmie pipe				
☐ Neat Cement				from	to	ft.	☐ Pumped from bottom upward				
☐ Neat Cement (6% bentonite)											



ONSITE SEWAGE DISPOSAL SYSTEM AND/OR WELL CONSTRUCTION
PERMIT APPLICATION



Property Address: 222 Donmore Drive

Property City and Zip Code: Great Falls V A 22066

Tax Map Number: 0022 02 0044A

Residential ☒ Commercial ☐

Is this a private sector OSE/PE submission? Yes ☐ No ☒ If yes, is the OSE/PE package with cover sheet attached? Yes ☐ No ☐

Is this application submitted under 163.6? Yes ☐ No ☐

Does this property serve as your (owner) principal place of residence? Yes ☐ No ☒ Multiple sites? ☐ Yes ☒ No

PERMIT OR SERVICE REQUESTED

- | | | |
|---|--|--|
| ☐ Individual Drinking Water Supply | ☐ Certification Letter | ☐ Pump and Haul |
| ☐ Irrigation Well | ☐ Construction Permit | ☐ Voluntary Upgrade |
| ☐ Well Abandonment | ☐ Repair of Existing System | ☐ Minor Modification |
| ☒ Geothermal Well | ☐ Subdivision | ☐ Courtesy Inspection |
| ☐ Well Repair | ☐ Convert Existing Well | |

Number of Bedrooms:

WATER SUPPLY

SEWAGE DISPOSAL

Basement Plumbing Fixtures? Yes ☒ No ☐

Is the water supply:

Is the sewage disposal:

Is this a Replacement Well? Yes ☐ No ☒

Public ☐ Private ☒

Public ☒ Private ☐

Foundation Chemically Treated? Yes ☒ No ☐

APPLICANT

Name: Northern Virginia Drilling Inc

Mailing Address: 11356 Industrial Road

Phone: Office 703-361-6859 Cell 703-203-4607

Manassas VA 20109

Email: neil.self@nvdinc.com

PROPERTY OWNER

Name: John Rhodes

Mailing Address: 74 S Player Crest Circle

Phone: 703-341-9489

Spring TX 77382

Email: johnrrhodes10@gmail.com

IF COMMERCIAL PROPERTY

Estimated Daily Water Usage (GPD):

GPD calculations submitted: Yes ☐ No ☐

SUMMARY OF PROPOSED WORK

Drill 5 Geothermal well 400 ft each Close loop Groute from bottom to

Top

I give permission to Fairfax County Health Department to enter onto the property during normal business hours for the purpose of processing this application and to perform quality assurance checks of evaluations and designs until an operation permit is approved.

Signature

Print Name Scott Miller

Date

02/09/2021

Property Owner ☐

Agent ☒

For Department Use Only

Approved by EH Remarks Approved

Approval Date 2-12-21

Certification Approval Date HSEPTIC

HWELL 210420206

Project #

Date Lot Approved Type System

of Bedrooms

GPD

Perc Rate Depth Septic Tank Gallons

Active Lin.Ft.

Reserve Lin.Ft.

Building Permit Number

Fee Amount

Receipt Number

PAID FEB 11 2021

\$ 508

931683 DM

REQUIRED DOCUMENTATION

The required documentation for each application type is listed below. Please provide all documentation and fees at the time the application is submitted. Please initial that pertinent documentation has been provided. Thank you.

Certification Letter

Applicant Initials

1. Site and Soil Evaluation Report
2. Surveyed property plat (3 copies) - to include:
 - a. Metes and Bounds of property
 - b. Soil profile hole locations, perc or K-Sat hole locations
 - c. Proposed well location and well specifications (when a private well is proposed)
 - d. Within 200 feet of the absorption area the following must be shown: existing or proposed wells, springs, cisterns or sewage disposal systems, existing or proposed buildings
 - e. Information on proposed treatment level, proposed trench bottom area and proposed sewage volume and flow
 - f. Proposed perimeter of soil absorption area, including reserve area if required
 - g. All recorded easements
3. Perc or K-Sat results or Perc Waiver Request
4. If permeability limiting feature is less than 18" from ground surface, the following must be provided:
 - a. Verification that the site is not flooded during the wet season
 - b. Demonstration that there is sufficient hydraulic gradient to move the applied effluent off the site
 - c. Water mounding calculations
5. Fee provided
 - a. Sewage Disposal System with flow of 1000 GPD or less
 - \$310.00 VDH cert letter fee
 - \$10.00 VDH indemnification fee
 - \$200.00 County SDS application fee
 - Total** \$520.00 per site**
 - b. Sewage Disposal System with flow greater than 1000 GPD
 - \$1390.00 VDH cert letter fee
 - \$10.00 VDH indemnification fee
 - \$200.00 County SDS application fee
 - Total** \$1600.00 per site**

SM

SM

Repair of Existing System

Applicant Initials

1. Completed Malfunction Assessment Form ☒ Check box if **not** applicable
2. Site and Soil Evaluation Report ☒ Check box if **not** applicable
3. Surveyed Property Plat (3 copies) - to include: ☐ Check box if **not** applicable
 - a. Metes and Bounds of property
 - b. Soil profile hole locations, perc or K-Sat hole locations ☒ Check box if **not** applicable
 - c. Well location when a private well exists
 - d. Complete construction drawing/design of proposed sewage system (including all elevations)
 - e. Within 200 feet of the absorption zone or treatment unit the following must be shown:
existing or proposed wells, springs, cisterns or sewage disposal systems, existing or proposed buildings
4. Perc or K-Sat results or Perc Waiver Request ☒ Check box if **not** applicable
5. Alternative system design/hydraulic plans ☒ Check box if **not** applicable
6. Water mounding calculations if distance to restriction is less than 18"
7. Pump plans (3 sets) ☒ Check box if **not** applicable

SM

REQUIRED DOCUMENTATION

Construction Permit

Applicant Initials

Is this a revised design package? Yes ☐ No ☒ If yes, only provide complete documentation of all changes.

SM

1. Site and Soil Evaluation Report
2. If Site Grading Plan is required, provide 1 approved or proposed copy. If submitting with a proposed copy of the Site Grading Plan, the submission will be held for up to 15 days pending approval of the Site Grading Plan.
3. If Site Grading Plan is **not** required, 3 copies of a surveyed property plat must be provided, all to include:
 - a. Metes and Bounds of property
 - b. Soil profile hole locations, perc or K-Sat hole locations ☒ Check box if **not** applicable
 - c. Proposed well location and well specifications (when a private well is proposed)
 - d. Complete construction drawing/design of proposed sewage system (including all elevations)
4. Within 200 feet of the absorption zone or treatment unit the following must be shown:
existing or proposed wells, springs, cisterns or sewage disposal systems, existing or proposed buildings
5. Perc or K-Sat results or Perc Waiver Request
6. Alternative system design/hydraulic plans ☒ Check box if **not** applicable
7. If permeability limiting feature is less than 18" from ground surface, the following must be provided:
 - a. Verification that the site is not flooded during the wet season
 - b. Demonstration that there is sufficient hydraulic gradient to move the applied effluent off the site
 - c. Water mounding calculations
8. Pump plans (3 sets) if applicable
9. Is the proposed sewage disposal system an alternative design? Yes ☐ No ☐
10. Fee provided

SM

SM

a. If application is within 18 months of receiving a certification letter, no fee is required.

b. If applying under 9a., provide certification letter.

c. Sewage Disposal System with flow of 1000 GPD or less

\$215.00 VDH Construction Permit fee

\$10.00 VDH indemnification fee

\$200.00 County SDS application fee **Total** \$425.00**

If #8 is "yes"

\$200.00 County alternative SDS review fee

Total \$625.00 per site**

d. Sewage Disposal System with flow greater than 1000 GPD

\$1390.00 VDH Construction Permit fee

\$10.00 VDH indemnification fee

\$200.00 County SDS application fee **Total** \$1600.00**

If #8 is "yes"

\$200.00 County alternative SDS review fee

Total \$1800.00 per site**

Minor Modification

A minor modification may include, but is not limited to, relocation of sewer line, force main, conveyance line, etc. to meet set back to proposed construction such as an addition or pool; tie in new sewer line for proposed addition (e.g. pool house) to be connected to existing sewer line; relocation of septic tank and/or pump chamber. The following must be provided when a minor modification will be made:

1. Surveyed Property Plat (3 copies) - to include:

- i. Metes and Bounds of property
- ii. Well location when a private well exists

2. Architectural Plans, if applicable

3. Pump Plans (3 sets if applicable)

4. Fairfax County Building Permit Application

5. Fee provided

a. VDH minor modification fee **\$100.00**


b. If associated with a building permit review - add **\$85.00**

REQUIRED DOCUMENTATION			
Individual Drinking Water Well ☐	Geothermal Well ☐	Irrigation Well ☒	Convert Existing Well ☐
			Applicant Initials _____
1. Surveyed property plat (3 copies) to include: a. Metes and Bounds of property b. Proposed well location and well specifications c. Sanitary survey showing any obvious source of toxic or dangerous substances within 200ft of the proposed private well d. All recorded easements			
2. Fee provided - \$500.00 If this is a replacement well at the applicant's primary residence , no fee is required _____			
Well Abandonment	Applicant Initials _____	Well Repair	Applicant Initials _____
1. Completed 1st page of this application	_____	Completed 1st page of this application with detailed summary of proposed work	_____
2. IF NOT primary residence, add \$500.00 fee	_____		_____
Pump and Haul			Applicant Initials _____
1. Copy of contract with a licensed Sewage Handling Contractor			_____
2. Copy of Pump and Haul application			_____
3. Detailed construction schedule for completion of permanent disposal site			_____
4. Proof of Bonding			_____
5. Completed Malfunction Assessment Form (if application is due to malfunctioning system)			_____
6. Plans, specifications, fees and other data as required by the Health Department			_____
Voluntary Upgrade			Applicant Initials _____
1. Completed 1st page of this application			_____
2. Call 703-246-2201 to schedule a consultation			_____
Courtesy Inspection			Applicant Initials _____
1. Site and Soil Evaluation Report			_____
2. Describe the site or soil feature you have identified as marginal or questionable: _____			
3. What is the question to be discussed? _____			

CERTIFICATION STATEMENT

I hereby certify that the evaluations and/or designs contained herein were conducted in accordance with the *applicable provisions of* the Fairfax Code, Chapter 68.1: the Individual Sewage Disposal Facilities Code, Fairfax Code, Chapter 70.1: Private Well Water Ordinance, the Sewage Handling and Disposal Regulations (12 VAC54-610), the Private Well Regulations (12 VAC5-630), the Regulations for Alternative Onsite Sewage Systems (12 VAC5-613) and all other applicable laws, regulations and policies implemented by the Virginia Department of Health. I further certify that I currently possess any professional license required by the laws and regulations of the Commonwealth that have been duly issued by the applicable agency charged with licensure to perform the work contained herein.


☒ The work attached to this cover page has been conducted under an exemption to the practice of engineering, specifically the exemption in Code of Virginia Section 54.1-402.A.11

WWSP/OSE/PE Signature  License# 2719000339 Date 02/09/2021
 Print name Scott Miller

Geothermal

Form GW-2
Revised 8/19/2016
Page 1 of 4

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT



DEQ Well #
VSSS Local #
VDH IDN # 210420206
VDH PWSID #

*Indicates required field or section
**Indicates required field or section, if applicable

1. Contact Information

Contact:	Name	Address	Phone
Owner	John Rhodes TR	745 PAYER CREST CJA SPRING TX	703-220-0269
Driller	NO. VA. DRILLING INC.	11356 INDUSTRIAL RD. MANASSAS VA	703-361-6859
System Provider	2719000310	11356 INDUSTRIAL RD. MANASSAS VA	703-361-6859

2. Well Location*

Physical Address:	222 DOWNING DR GREAT FALLS V.A.	County/City:	FAIRFAX CO.
Subdivision Name:	SEVERA FARM	Section:	3
		Block:	
		Lot:	44A
Tax Map/GPIN #:	22-02-0024A		
Latitude:	N	Longitude:	W
Datum Source	Horizontal:	☐ WGS84 ☐ NAD83 ☐ NAD27	
Lat/Long Source (Check One):	☐ Map ☐ GPS ☐ PPDGPS ☐ Survey ☐ Imagery ☐ WAAS		
Location Information Collected By:	2719000310		
Physical Location Description:	FRONT OF HOUSE NEAR FRONT STEOP		

3. Facility & Use*

Type of Facility (Check One):	Type of Use (Check All That Apply):
☒ Private	☐ Drinking/Domestic Use ☐ Agricultural ☐ Food Processing
☐ Waterworks	☐ Manufacturing ☐ Irrigation ☐ Injection
☐ Observation/Monitoring Well	☒ Geothermal (Cooling/Heating) ☐ Fire Safety
	☐ Closed
	☐ Open: ☐ Returned to Surface
	☐ Returned to Aquifer

4. Well Construction*

Well designation, Name or Number: 210420206			
Date Started: 6-2-21	Date Completed: 6-14-21	Type Rig: AIR ROTARY	
Class Well (Check One): ☐ I ☐ IIA ☐ IIB ☐ IIA ☐ IIB ☐ IIC ☐ IID ☐ IIE ☒ IV			
Construction Type (Check One): ☒ New ☐ Existing-Modified: ☐ Well ☐ Pump: Date			
Well Depth: 400 ft.	Total Hole (borehole) Depth: 400 ft.	Depth to Bedrock: 96 ft.	
Hole Size (Include reamed zones): 6 inches from 0 to 400 ft.		Inches from to ft.	
Height of Casing above Land Surface: ft. inches			
Casing Size (I.D.) and Materials: (below)		Total Depth of Casing: ft.	
inches from to ft. ☐ infilled	Material	Weight per ft.	or wall thickness in.
inches from to ft. ☐ infilled	Material	Weight per ft.	or wall thickness in.
inches from to ft. ☐ infilled	Material	Weight per ft.	or wall thickness in.
Screen Size & Mesh:			
inches from to ft. ☐ infilled	Mesh Size	Type	
inches from to ft. ☐ infilled	Mesh Size	Type	
inches from to ft. ☐ infilled	Mesh Size	Type	
Water Zones: from to ft.		from to ft.	from to ft.
Gravel Pack:			
Size: Type: from to ft.	Size: Type: from to ft.		
Grout Type:		Grouting Method:	
☐ Bentonite Slurry ☐ Neat Cement	from to ft.	☐ Poured from surface	Type of Seal:
☐ Bentonite pellets/chips ☐ Concrete	from to ft.	☐ Poured through tremmie pipe	☐ pitless adapter
☐ Neat Cement (6% bentonite)	from to ft.	☐ Pumped from bottom upward	☐ sanitary seal
Camera Survey: ☐ Yes ☐ No		Date Conducted:	
Additional Well Construction Form Information Attached: ☐ Yes ☐ No			

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 210420206
VDH PWSID # _____

Well designation, Name or Number: _____

5. Disinfection

Well Disinfected: ☐ Yes ☐ No Date: _____

6. Abandonment (*When abandoning the well, Sections 1 thru 4 must be completed and/or attach original GW-2)

Date Started:	Date Completed:
Static Water Level (unpumped level measured):	ft.
Casing Size (I.D.) and Materials:	Casing Pulled: ☐ Yes ☐ No ☐ Uncased Well
Depth of Fill:	Type and Source of Fill:
Grout: From <u>405'</u> to <u>0</u> Type: <u>Return SURF</u>	From _____ to _____ Type: _____
Method of permanently marking location:	

7. Pump Test**

Static Water Level (unpumped level measured):		ft.	
Date:	Method (Check One):	☐ Water Tape	☐ Airline ☐ Transducer ☐ Other
Stabilized measured pumping water level:		ft.	
Date:	Method (Check One):	☐ Top of Well	☐ Top of Casing ☐ Surface Level
Test Pump Intake Depth:	ft	Stabilized Yield:	gpm after _____ hours
Natural Flow:	☐ Yes ☐ No	Flow Rate	gpm
Estimated Well Yield:		gpm	

8. Pump Data**

Type: ☐ submersible ☐ Turbine ☐ Shallow Jet ☐ Deep Jet ☐ Other: _____	Motor HP:		
Production Pump Intake Depth:	ft	Rated Capacity:	gpm at _____ ft TDH

9. Geologic Information

Type Logs:	Aquifer Test Performed:
Water Quality Results Attached: Yes _____ No _____	

Comments: 4-400FT CLASS IV Geo-THERMAL WELLS
GROUTED FROM 400FT. TO GROUND SURFACE

Formation _____	Lithology _____	Province _____	Geologic Map Used _____
Elevation _____			
For Office Use			

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 210120206
VDH PWSID # _____

*Indicates required field or section
**Indicates required field or section, if applicable

10. Driller's Log (Use additional sheets if necessary)*

Well designation, Name or Number:				
Depth (feet)		Type of Rock or Soil	Remarks	Drilling Time (Min.)
From	To	(Color, material, fossils, hardness, etc.)	(Water, caving, cavities, etc.)	
0	96'	OVERBURDEN		
96'	400'	GREY GRANITE		
6" Hole 0 to 400 FT. 1 1/4" HDPE Geo-THERMAL LOOP 0 to 400 FT.				

11. Certification

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is to the best of my knowledge and belief true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations.

Signature*: [Signature]

Date: 6-14-21

License Number: 2719000310

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 21042206
VDH PWSID # _____

*Indicates required field or section
**Indicates required field or section, if applicable

Additional Well Construction Data

(Use and submit only if additional space is needed)

12. Additional Well Construction Data

Well designation, Name or Number:											
Physical Location:				Date Started:				Date Completed:			
Hole Size (Include reamed zones):											
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
Casing Size (I.D.) and Materials:											
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
Screen Size & Mesh:											
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
Water Zones:											
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
Gravel Pack:											
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Size	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Grout Type:					from		to	ft.	Grouting Method:		
☐ Bentonite Slurry					from		to	ft.	☐ Poured from surface		
☐ Bentonite pellets/chips					from		to	ft.	☐ Poured through tremmie pipe		
☐ Neat Cement (6% bentonite)					from		to	ft.	☐ Pumped from bottom upward		
☐ Neat Cement											
☐ Concrete											

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

RECEIVED
JAN 10 2022
By JGS DEQ Well #
USGS Local #
VDH HDIN # 200860270
VDH PWSID #

*Indicates required field or section
**Indicates required field or section, if applicable

1. Contact Information*

Contact:	Name	Address	Phone
Owner	<u>JOHN RHODES</u>	<u>745 PLAZA CREST CIR SPRING TX</u>	<u>540-222-0581</u>
Driller	<u>NO. VA. DRILLING INC.</u>	<u>11356 INDUSTRIAL RD. MANASSAS VA</u>	<u>703-361-6859</u>
System Provider	<u>2719000310</u>	<u>11356 INDUSTRIAL RD. MANASSAS VA</u>	<u>703-361-6859</u>

2. Well Location*

Physical Address:	<u>222 MONROE DR. GREAT FALLS VA</u>	County/City:	<u>FAIRFAX CO.</u>
Subdivision Name:		Section:	
		Block:	
		Lot:	
Tax Map/GPIN #:	<u>22 02 0044 A</u>		
Latitude:	<u>N</u>	Longitude:	<u>W</u>
Datum Source	Horizontal: ☐ WGS84 ☐ NAD83 ☐ NAD27		
Lat/Long Source (Check One):	☐ Map ☐ GPS ☐ PPDGPS ☐ Survey ☐ Imagery ☐ WAAS		
Location Information Collected By:	<u>2719000310</u>		
Physical Location Description:	<u>FRONT OF PROP SEATTLE GRADE</u>		

3. Facility & Use*

Type of Facility (Check One):	Type of Use (Check All That Apply):
☒ Private	☒ Drinking/Domestic Use ☐ Agricultural ☐ Food Processing
☐ Waterworks	☐ Manufacturing ☐ Irrigation ☐ Injection
☐ Observation/Monitoring Well	☐ Geothermal (Cooling/Heating) ☐ Fire Safety
	☐ Closed
	☐ Open: ☐ Returned to Surface
	☐ Returned to Aquifer

4. Well Construction*

Well designation, Name or Number:	<u>200860270</u>		
Date Started:	<u>7-8-20</u>	Date Completed:	<u>7-9-20</u>
	Type Rig:	<u>AIR ROTARY</u>	
Class Well (Check One):	☐ I ☐ IIA ☐ IIB ☐ IIIA ☒ IIIB ☐ IIIC ☐ IIID ☐ IIIE ☐ IV		
Construction Type (Check One):	☒ New ☐ Existing-Modified: ☐ Well ☐ Pump: Date		
Well Depth:	<u>560</u> ft.	Total Hole (borehole) Depth:	<u>560</u> ft.
	Depth to Bedrock:	<u>28</u> ft.	
Hole Size (Include reamed zones):	<u>10</u> inches from <u>0</u> to <u>82</u> ft. <u>6</u> inches from <u>82</u> to <u>560</u> ft.		
Height of Casing above Land Surface:	<u>2</u> ft. <u>0</u> inches		
Casing Size (I.D.) and Materials: (below)	Total Depth of Casing: <u>82</u> ft.		
<u>6 7/8</u> inches from <u>12</u> to <u>82</u> ft. ☐ infilled	Material	<u>STEEL</u>	
Weight per ft. <u>13</u> or wall thickness <u>1/8</u> in.			
inches from to ft. ☐ infilled	Material	Weight per ft. or wall thickness in.	
inches from to ft. ☐ infilled	Material	Weight per ft. or wall thickness in.	
Screen Size & Mesh:			
inches from to ft. ☐ infilled	Mesh Size	Type	
inches from to ft. ☐ infilled	Mesh Size	Type	
inches from to ft. ☐ infilled	Mesh Size	Type	
Water Zones: from <u>535</u> to <u>537</u> ft.	from to ft.	from to ft.	from to ft.
Gravel Pack:			
Size: Type: from to ft.	Size: Type: from to ft.	from to ft.	
Grout Type:	Grouting Method:		
☐ Bentonite Slurry ☒ Neat Cement	☐ Poured from surface		
☐ Bentonite pellets/chips ☐ Concrete	☐ Poured through tremmie pipe		
☐ Neat Cement (6% bentonite)	☒ Pumped from bottom upward		
Camera Survey: ☐ Yes ☐ No	Date Conducted:		
Additional Well Construction Form Information Attached: ☐ Yes ☒ No			

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 2008060270
VDH PWSID # _____

Well designation, Name or Number*: _____

5. Disinfection

Well Disinfected: ☒ Yes ☐ No Date: 3-18-21

6. Abandonment (*When abandoning the well, Sections 1 thru 4 must be completed and/or attach original GW-2)

Date Started:	Date Completed:
Static Water Level (unpumped level measured):	ft.
Casing Size (I.D.) and Materials:	Casing Pulled: ☐ Yes ☐ No ☐ Uncased Well
Depth of Fill:	Type and Source of Fill:
Grout: From to Type:	From to Type:
Method of permanently marking location:	

7. Pump Test**

Static Water Level (unpumped level measured):	<u>60</u> ft.
Date:	Method (Check One): ☐ Water Tape ☐ Airline ☐ Transducer ☐ Other
Stabilized measured pumping water level:	ft.
Date:	Method (Check One): ☐ Top of Well ☐ Top of Casing ☐ Surface Level
Test Pump Intake Depth:	<u>560</u> ft Stabilized Yield: <u>20</u> gpm after <u>1</u> hours
Natural Flow: ☐ Yes ☒ No	Flow Rate gpm
Estimated Well Yield: gpm	

8. Pump Data**

Type: ☒ submersible ☐ Turbine ☐ Shallow Jet ☐ Deep Jet ☐ Other: _____	Motor HP: <u>3</u>
Production Pump Intake Depth: <u>500'</u> ft	Rated Capacity: <u>19.2</u> gpm at <u>350'</u> ft TDH

9. Geologic Information

Type Logs:	Aquifer Test Performed:
Water Quality Results Attached: Yes ☐ No ☐	

Comments:

Formation _____	Lithology _____	Province _____	Geologic Map Used _____
Elevation _____			
For Office Use			

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 200860270
VDH PWSID # _____

*Indicates required field or section
**Indicates required field or section, if applicable

10. Driller's Log (Use additional sheets if necessary)*

Well designation, Name or Number:				
Depth (feet)		Type of Rock or Soil	Remarks	Drilling Time (Min.)
From	To	(Color, material, fossils, hardness, etc.)	(Water, caving, cavities, etc.)	
0	28	OVERBORDEN	INSTALLED -	
28	35	SANDSTONE	EXTRA CAS-	
35	73	GREY GRANITE	ING TO THE	
73	78	VOID	VENT WELL	
78	400	GREY GRANITE	LOAK CAVE	
400	475	BLUE GRANITE	IN	
475	560	GREY GRANITE		

11. Certification

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is to the best of my knowledge and belief true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations.

Signature*: [Signature] Date: 7-9-20

License Number: 2719000310

COMMONWEALTH OF VIRGINIA
UNIFORM WATER WELL COMPLETION REPORT

DEQ Well # _____
USGS Local # _____
VDH HDIN # 20080270
VDH PWSID # _____

*Indicates required field or section

**Indicates required field or section, if applicable

Additional Well Construction Data

(Use and submit only if additional space is needed)

12. Additional Well Construction Data

Well designation, Name or Number:											
Physical Location:				Date Started:				Date Completed:			
Hole Size (Include reamed zones):											
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
inches	from	to	ft.	inches	from	to	ft.	inches	from	to	ft.
Casing Size (I.D.) and Materials:											
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
inches	from	to	ft.	☐ infilled	Material	Weight per ft.	or wall thickness	in.			
Screen Size & Mesh:											
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
inches	from	to	ft.	☐ infilled	Mesh Size	Type					
Water Zones:											
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
From	to	ft.	From	to	ft.	From	to	ft.	From	to	ft.
Gravel Pack:											
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Size:	Type:	From	to	ft.	Size:	Type:	From	to	ft.		
Grout Type:				from	to	ft.	Grouting Method:				
☐ Bentonite Slurry				from	to	ft.	☐ Poured from surface				
☐ Bentonite pellets/chips				from	to	ft.	☐ Poured through tremmie pipe				
☐ Neat Cement (6% bentonite)				from	to	ft.	☐ Pumped from bottom upward				
☐ Neat Cement											
☐ Concrete											

NOTED PUBLIC COUNTY HEALTH DEPARTMENT

Page 1 of 4

WELL Only OSE/PE/WWSP Report For:

☒ Well Construction Permit
 ☐ Well Repair Permit
 ☐ Well Abandonment Permit
 ☐ Well Modification Permit

Property Location:

911 Address 222 DONMORE DRIVE City GREAT FALLS 22066

Lot 44A Section 3 Subdivision

GPIN or Tax Map # 0022-02-0044A Health Department ID #

Latitude Longitude

Applicant or Client Mailing Address

Name NORTHERN VIRGINIA DRILLING INC.

Address 11356 INDUSTRIAL ROAD

City MANASSAS State VA Zip Code 20109

Prepared by: OSE ☐ PE ☐ WWSP ☒

Name SCOTT MILLER License # 2719000339

Address 11356 INDUSTRIAL ROAD

City MANASSAS State VA Zip Code 20109

Date of Submission Date Revision 1

OSE/PE/WWSP Job ID Date Revision 2


List of attachments (e.g., Private Well Worksheet, Construction Drawings, Abandonment Worksheet, etc.)


Certification Statement

I hereby certify that the evaluations and/or designs as submitted comply with the applicable provisions of the Private Well Regulations (12 VACS-630-10 et seq.) and all other applicable laws and regulations enforced by the Virginia Department of Health. I further certify that I currently possess the professional license required to perform work evidenced by the application by the laws of the Commonwealth as promulgated by the supervising agency.

I recommend that a (select one): Construction permit ☒ Repair permit ☐ be (select one) Issued ☐

Modification permit ☐ Abandonment permit ☐ Denied ☐

OSE/PE/WWSP Signature  Date JUNE 17, 2020



Well SpecificationsVDH Use Only
HDIN:**Applicant Information**Name: NORTHERN VA DRILLING INC Address: 11356 INDUSTRIAL RD
OFFICE CE'S
Phone: 703-361-6854 703 203-4607 MANASSAS VA**Location Information**Tax Map/GPIN #: 0022 02 0044A Property Address: 222 DONMORE DRIVE
Subdivision: SENECA FARM Section: 3 Block: 22006 Lot: 44A
Directions: SEE ATTACHMENT**General Information**Well Purpose (select all that apply): ☒ Domestic Drinking Water ☐ Agricultural
☐ Irrigation ☐ Industrial/Commercial ☐ Geothermal
Well Class: 3-B Minimum Casing Depth: 55 ft.
Estimated Water Usage: _____ Minimum Grout Depth: 55 ft.**Horizontal Setbacks**Distance from Building Sewer: 156 ft. Distance from Pretreatment Unit(s): 304 ft.
Distance from Conveyance System: 215 ft. Distance from Absorption Area: 153 ft.
Distance from Property Line: 94 ft. Distance from foundations: 304 ft.
Distance from other source(s) of contamination: 200 ft.
List other source(s): _____Note: NEW HOUSE NEEDS WELL

Construction Drawings - Well Only

Property ID: 0022 02 0044A


SEE ATTACHMENT



Schematic drawing of private well and topographic features. Show the lot lines of the building lot and building site, sketch of property showing any topographic features which may impact on the design of the well, all existing and/or proposed structures including sewage disposal systems and wells (actual and permitted) within 200 feet of the well area. The scale drawing of all sewage disposal systems shall show sewer lines, pretreatment unit, pump station, conveyance system, and subsurface soil absorption system, reserve area, etc.



ON-SITE SEWAGE DISPOSAL SYSTEM AND/OR WELL CONSTRUCTION
PERMIT APPLICATION



Property Address: 222 DONMORE DRIVE

Property City and Zip Code: GREAT FALLS 22066

Tax Map Number: 0022 02 0044A

Residential ☒

Commercial ☐

Is this a private sector OSE/PE submission? Yes ☐ No ☒ If yes, is the OSE/PE package with cover sheet attached? Yes ☐ No ☐

Is this application submitted under 163.6? Yes ☐ No ☐

Does this property serve as your (owner) principal place of residence? Yes ☒ No ☐

Multiple sites? ☐ Yes ☒ No

PERMIT OR SERVICE REQUESTED

☒ Individual Drinking Water Supply

☐ Irrigation Well

☐ Well Abandonment

☐ Geothermal Well

☐ Well Repair

☐ Certification Letter

☐ Construction Permit

☐ Repair of Existing System

☐ Subdivision

☐ Convert Existing Well

☐ Pump and Haul

☐ Voluntary Upgrade

☐ Minor Modification

☐ Courtesy Inspection

Number of Bedrooms: 4

Basement Plumbing Fixtures? Yes ☐ No ☒

Is this a Replacement Well? Yes ☐ No ☒

Foundation Chemically Treated? Yes ☒ No ☐

WATER SUPPLY

Is the water supply:

Public ☐

Private ☒

SEWAGE DISPOSAL

Is the sewage disposal:

Public ☐

Private ☒

APPLICANT

Name: Northern Virginia Drilling Inc

Mailing Address: 11356 Industrial Road

Phone: Office 703-361-6859 Cell 703-203-4607

Manassas VA 20109

Email: neil.self@nvdinc.com

PROPERTY OWNER

Name: JOHN RHODES

Mailing Address: 745 PLAYER CREST CIRCLE

Phone: 832-625-8382

SPRING TX 77382

Email: JOHNRRHODES10A@gmail.com

IF COMMERCIAL PROPERTY

Estimated Daily Water Usage (GPD):

GPD calculations submitted: Yes ☐ No ☐

SUMMARY OF PROPOSED WORK

Drill new well and grout it

I give permission to Fairfax County Health Department to enter onto the property during normal business hours for the purpose of processing this application and to perform quality assurance checks of evaluations and designs until an operation permit is approved.

Signature

Scott W. Miller

Print Name

SCOTT MILLER

Date

JUNE 17, 2020

Property Owner ☐

Agent ☒

For Department Use Only

Approved by PS Remarks Approval Date 6-22-20

Certification Approval Date HSEPTIC HWELL 200860270 Project #

Date Lot Approved Type System # of Bedrooms GPD

Perc Rate Depth Septic Tank Gallons Active Lin.Ft. Reserve Lin.Ft.

Building Permit Number Fee Amount Receipt Number

REQUIRED DOCUMENTATION

The required documentation for each application type is listed below. Please provide all documentation and fees at the time the application is submitted. Please initial that pertinent documentation has been provided. Thank you.

Certification Letter

Applicant Initials

1. Site and Soil Evaluation Report
2. Surveyed property plat (3 copies) - to include:
 - a. Metes and Bounds of property
 - b. Soil profile hole locations, perc or K-Sat hole locations
 - c. Proposed well location and well specifications (when a private well is proposed)
 - d. Within 200 feet of the absorption area the following must be shown: existing or proposed wells, springs, cisterns or sewage disposal systems, existing or proposed buildings
 - e. Information on proposed treatment level, proposed trench bottom area and proposed sewage volume and flow
 - f. Proposed perimeter of soil absorption area, including reserve area if required
 - g. All recorded easements
3. Perc or K-Sat results or Perc Waiver Request
4. If permeability limiting feature is less than 18" from ground surface, the following must be provided:
 - a. Verification that the site is not flooded during the wet season
 - b. Demonstration that there is sufficient hydraulic gradient to move the applied effluent off the site
 - c. Water mounding calculations
5. Fee provided

a. Sewage Disposal System with flow of 1000 GPD or less	\$310.00 VDH cert letter fee \$10.00 VDH indemnification fee \$200.00 County SDS application fee Total** \$520.00 per site
b. Sewage Disposal System with flow greater than 1000 GPD	\$1390.00 VDH cert letter fee \$10.00 VDH indemnification fee \$200.00 County SDS application fee Total** \$1600.00 per site

SM

Repair of Existing System

Applicant Initials

1. Completed Malfunction Assessment Form ☐ Check box if **not** applicable
2. Site and Soil Evaluation Report ☐ Check box if **not** applicable
3. Surveyed Property Plat (3 copies) - to include: ☐ Check box if **not** applicable
 - a. Metes and Bounds of property
 - b. Soil profile hole locations, perc or K-Sat hole locations ☐ Check box if **not** applicable
 - c. Well location when a private well exists
 - d. Complete construction drawing/design of proposed sewage system (including all elevations)
 - e. Within 200 feet of the absorption zone or treatment unit the following must be shown:
existing or proposed wells, springs, cisterns or sewage disposal systems, existing or proposed buildings
4. Perc or K-Sat results or Perc Waiver Request ☐ Check box if **not** applicable
5. Alternative system design/hydraulic plans ☐ Check box if **not** applicable
6. Water mounding calculations if distance to restriction is less than 18"
7. Pump plans (3 sets) ☐ Check box if **not** applicable

REQUIRED DOCUMENTATION

Construction Permit

Applicant Initials _____

Is this a revised design package? Yes ☐ No ☐ If yes, only provide complete documentation of all changes. _____

1. Site and Soil Evaluation Report _____

2. If Site Grading Plan is required, provide 1 approved or proposed copy. If submitting with a proposed copy of the Site Grading Plan, the submission will be held for up to 15 days pending approval of the Site Grading Plan. _____

3. If Site Grading Plan is **not** required, 3 copies of a surveyed property plat must be provided, all to include: _____

a. Metes and Bounds of property _____

b. Soil profile hole locations, perc or K-Sat hole locations ☐ Check box if **not** applicable _____

c. Proposed well location and well specifications (when a private well is proposed) _____

d. Complete construction drawing/design of proposed sewage system (including all elevations) _____

4. Within 200 feet of the absorption zone or treatment unit the following must be shown: _____

existing or proposed wells, springs, cisterns or sewage disposal systems, existing or proposed buildings _____

5. Perc or K-Sat results or Perc Waiver Request _____

6. Alternative system design/hydraulic plans ☐ Check box if **not** applicable _____

7. If permeability limiting feature is less than 18" from ground surface, the following must be provided: _____

a. Verification that the site is not flooded during the wet season _____

b. Demonstration that there is sufficient hydraulic gradient to move the applied effluent off the site _____

c. Water mounding calculations _____

8. Pump plans (3 sets) if applicable _____

9. Is the proposed sewage disposal system an alternative design? Yes ☐ No ☐ _____

10. Fee provided _____

a. If application is within 18 months of receiving a certification letter, no fee is required. _____

b. If applying under 9a., provide certification letter. _____

c. Sewage Disposal System with flow of 1000 GPD or less **\$215.00** VDH Construction Permit fee
\$10.00 VDH indemnification fee
\$200.00 County SDS application fee **Total** \$425.00** _____
If #8 is "yes" **\$200.00** County alternative SDS review fee
Total \$625.00 per site** _____

d. Sewage Disposal System with flow greater than 1000 GPD **\$1390.00** VDH Construction Permit fee
\$10.00 VDH indemnification fee
\$200.00 County SDS application fee **Total** \$1600.00** _____
If #8 is "yes" **\$200.00** County alternative SDS review fee
Total \$1800.00 per site** _____

Minor Modification

A minor modification may include, but is not limited to, relocation of sewer line, force main, conveyance line, etc. to meet set back to proposed construction such as an addition or pool; tie in new sewer line for proposed addition (e.g. pool house) to be connected to existing sewer line; relocation of septic tank and/or pump chamber. The following must be provided when a minor modification will be made:

1. Surveyed Property Plat (3 copies) - to include: _____

i. Metes and Bounds of property _____

ii. Well location when a private well exists _____

2. Architectural Plans, if applicable _____

3. Pump Plans (3 sets if applicable) _____

4. Fairfax County Building Permit Application _____

5. Fee provided _____

a. VDH minor modification fee **\$100.00**

b. If associated with a building permit review - add **\$85.00**

REQUIRED DOCUMENTATION			
Individual Drinking Water Well ☒	Geothermal Well ☐	Irrigation Well ☐	Convert Existing Well ☐
1. Surveyed property plat (3 copies) to include: a. Metes and Bounds of property b. Proposed well location and well specifications c. Sanitary survey showing any obvious source of toxic or dangerous substances within 200ft of the proposed private well d. All recorded easements			Applicant Initials SM
2. Fee provided - \$500.00 If this is a replacement well at the applicant's primary residence , no fee is required _____			
Well Abandonment	Applicant Initials	Well Repair	Applicant Initials
1. Completed 1st page of this application	_____	Completed 1st page of this application with detailed summary of proposed work	_____
2. IF NOT primary residence, add \$500.00 fee	_____		
Pump and Haul			Applicant Initials
1. Copy of contract with a licensed Sewage Handling Contractor			_____
2. Copy of Pump and Haul application			_____
3. Detailed construction schedule for completion of permanent disposal site			_____
4. Proof of Bonding			_____
5. Completed Malfunction Assessment Form (if application is due to malfunctioning system)			_____
6. Plans, specifications, fees and other data as required by the Health Department			_____
Voluntary Upgrade			Applicant Initials
1. Completed 1st page of this application			_____
2. Call 703-246-2201 to schedule a consultation			
Courtesy Inspection			Applicant Initials
1. Site and Soil Evaluation Report			_____
2. Describe the site or soil feature you have identified as marginal or questionable: _____			
3. What is the question to be discussed? _____			

CERTIFICATION STATEMENT

I hereby certify that the evaluations and/or designs contained herein were conducted in accordance with the *applicable provisions* of the Fairfax Code, Chapter 68.1: the Individual Sewage Disposal Facilities Code, Fairfax Code, Chapter 70.1: Private Well Water Ordinance, the Sewage Handling and Disposal Regulations (12 VAC54-610), the Private Well Regulations (12 VAC5-630), the Regulations for Alternative Onsite Sewage Systems (12 VAC5-613) and all other applicable laws, regulations and policies implemented by the Virginia Department of Health. I further certify that I currently possess any professional license required by the laws and regulations of the Commonwealth that have been duly issued by the applicable agency charged with licensure to perform the work contained herein.

☒ The work attached to this cover page has been conducted under an exemption to the practice of engineering, specifically the exemption in Code of Virginia Section 54.1-402.A.11

WWSP/OSE/PE Signature _____

License# 2719000339 Date 6/17/2020

Print name _____

SCOTT MILLER

WELL ONLY OSE/PE/WWSP Report For:

☒ Well Construction Permit
 ☐ Well Repair
 ☐ Well Abandonment Permit
 ☐ Well Modification Permit

Property Location:

911 Address 222 Donmore Drive City, State, Zip: Great Falls, VA 22066
 Lot: 44A Section: 3 Subdivision: Seneca Farms
 GPIN or Tax Map #: 0022-02-0044A Health Dept. ID #: _____
 Latitude: _____ Longitude: _____

Owner :

Name: John and Sheri Rhodes
 Address: 74 South Player Crest Circle The Woodlands, TX 77382

Prepared by:

OSE Name: Brian H. Phillips License # 1940001374
 Address: 8399 West Main Street, Marshall, VA 20115
 PE Name: _____ License # _____
 Address: _____

Date of Report: 3/25/2020



Date of Revision #1: _____

OSE/PE/WWSP Job # T1812

Date of Revision #2: _____

Contents/Index of this report:

1. Cover Sheet
2. Well System Specifications
3. Construction Drawing-Well



Certification Statement

I hereby certify that the evaluations and/or designs contain herein were conducted in accordance with the applicable provisions of the Private Well Regulations (12VAC5-630-10 et seq.) and all other applicable laws, regulations, and policies enforced by the Virginia Department of Health. I further certify that I currently possess the professional license required to perform work evidenced by the application by the laws of the Commonwealth as promulgated by the supervising agency.

HEALTH DEPARTMENT COPY

I recommend that a: ☒ Construction Permit ☐ Repair permit ☒ Issued
☐ Modification Permit ☐ Abandonment permit ☐ Denied

OSE/PE Signature: _____

Date: 3/25/2020

SYSTEM SPECIFICATIONS**VDH USE ONLY**

HDIN: _____

Application InformationName: John and Sheri RhodesAddress: 74 South Player Crest CirclePhone: 0The Woodlands, TX 77382**Location Information**Tax Map/GPIN #: 0022-02-0044AProperty Address: 222 Donmore DriveSubdivision: Seneca FarmsSection: 3

Block: _____

Lot: 44A

Directions:

General Information

Well Purpose (select all that apply):



Domestic Drinking Water



Agricultural



Irrigation




Industrial/Commercial



Geothermal

Well Class: 3BMinimum Casing Depth: 50 ft.Estimated Water Usage: 750 gpdMinimum Grout Depth: 50 ft.**Horizontal Setbacks**Distance from Building Sewer: 50 ft., min. Distance from Pretreatment Unit(s): 50 ft., min.Distance Conveyance System: 50 ft., min. Distance to Absorption Area: 100 ft., min.Distance from Property Line: 74.4 ft., min. Distance from Foundations: 50 ft., min.Distance from other source(s) of contamination: 100 ft., min.List other sources: NA

Notes:





ONSITE SEWAGE DISPOSAL SYSTEM AND/OR WELL CONSTRUCTION
PERMIT APPLICATION

COUNTY OF FAIRFAX

MAR 26 2020

Property Address: 222 Donmore Drive

Property City and Zip Code: Great Falls, VA 22066

Tax Map Number: 2-2-02-0044A

Residential ☒ Commercial ☐

Is this a private sector WWSP/OSE/PE submission? Yes ☒ No ☐ Is the WWSP/OSE/PE package with cover sheet attached? Yes ☒ No ☐

Is this application submitted under 163.6? Yes ☐ No ☒ If installing in an RPA have you included a waiver from LDS? Yes ☐ No ☐

Does this property serve as your (owner) principal place of residence? Yes ☐ No ☒ Multiple sites? Yes ☐ No ☒

PERMIT OR SERVICE REQUESTED

- | | | |
|--|---|--|
| ☒ Individual Drinking Water Supply | ☐ Certification Letter | ☐ Pump and Haul |
| ☐ Irrigation Well | ☒ Construction Permit | ☐ Voluntary Upgrade |
| ☐ Well Abandonment | ☐ Repair of Existing System | ☐ Minor Modification |
| ☐ Geothermal Well | ☐ Subdivision | ☐ Courtesy Inspection |
| ☐ Well Repair | ☐ Convert Existing Well | |

Number of Bedrooms: 5

Basement Plumbing Fixtures? Yes ☒ No ☐

Is this a Replacement Well? Yes ☒ No ☐

Foundation Chemically Treated? Yes ☒ No ☐ Borate? Yes ☐ No ☒

WATER SUPPLY

Is the water supply:
Public ☐ Private ☒

SEWAGE DISPOSAL

Is the sewage disposal:
Public ☐ Private ☒

APPLICANT

Name: Soils Inc.

Mailing Address: 8399 W. Main Street

Phone: 540-364-1122

Marshall, VA 20115

Email: brian.phillips@soils-inc.com

PROPERTY OWNER

Name: John Rhodes

Mailing Address: 74 S Player Crest Cir

Phone: 703-395-0101-Mike Ibrahim

Spring, TX, 77382

Email: patrick@pondroofing.com

IF COMMERCIAL PROPERTY

Estimated Daily Water Usage (GPD):

GPD calculations submitted: Yes ☐ No ☐

SUMMARY OF PROPOSED WORK

Client would like an alternative septic design review for a new SFD.

1. WELL

I give permission to Fairfax County Health Department to enter onto the property during normal business hours for the purpose of processing this application and to perform quality assurance checks of evaluations and designs until an operation permit is approved.

Signature

Print Name Brian H. Phillips

Date

03/25/2020

Property Owner ☐ Agent ☒

For Department Use Only

Approved by EL Remarks App WSS & AESS DESIGN Approval Date 4.7.20

Certification Approval Date 200830246 HSEPTIC 200840270 HWELL 200840270 project #

Date Lot Approved Type System # of Bedrooms GPD

Perc Rate Depth Septic Tank Gallons Active Lin.Ft. Reserve Lin.Ft.

Building Permit Number 200780135 Fee Amount 700 Receipt Number 908704

REQUIRED DOCUMENTATION

The required documentation for each application type is listed below. Please provide the documentation and fees at the time the application is submitted. Please initial that pertinent documentation has been provided. Thank you.

Certification Letter

Applicant Initials

1. Site and Soil Evaluation Report _____
2. Surveyed property plat (3 copies) - to include: _____
 - a. Metes and Bounds of property _____
 - b. Soil profile hole locations, perc or K-Sat hole locations _____
 - c. Proposed well location and well specifications (when a private well is proposed) _____
 - d. Within 200 feet of the absorption area the following must be shown: existing or proposed wells, springs, cisterns or sewage disposal systems, existing or proposed buildings _____
 - e. Information on proposed treatment level, proposed trench bottom area and proposed sewage volume and flow _____
 - f. Proposed perimeter of soil absorption area, including reserve area if required _____
 - g. All recorded easements _____
3. Perc or K-Sat results or Perc Waiver Request _____
4. If permeability limiting feature is less than 18" from ground surface, the following must be provided: _____
 - a. Verification that the site is not flooded during the wet season _____
 - b. Demonstration that there is sufficient hydraulic gradient to move the applied effluent off the site _____
 - c. Water mounding calculations _____
5. Fee provided _____
 - a. Sewage Disposal System with flow of 1000 GPD or less **\$310.00** VDH cert letter fee
 \$10.00 VDH indemnification fee
 \$200.00 County SDS application fee
 Total \$520.00 per site _____
 - b. Sewage Disposal System with flow greater than 1000 GPD **\$1390.00** VDH cert letter fee
 \$10.00 VDH indemnification fee
 \$200.00 County SDS application fee
 Total \$1600.00 per site _____

Repair of Existing System

Applicant Initials

1. Completed Malfunction Assessment Form ☐ Check box if **not** applicable _____
2. Site and Soil Evaluation Report ☐ Check box if **not** applicable _____
3. Surveyed Property Plat (3 copies) - to include: ☐ Check box if **not** applicable _____
 - a. Metes and Bounds of property b. Soil profile hole locations, perc or K-Sat hole locations
 - c. Well location when a private well exists d. Complete SDS design (including elevations)
 - e. Identify all (existing or proposed) drinking water sources, buildings, and sewage disposal systems within 200 feet of the absorption area
4. Perc or K-Sat results or Perc Waiver Request ☐ Check box if **not** applicable _____
5. Alternative system design/hydraulic plans ☐ Check box if **not** applicable _____
6. Water mounding calculations if distance to restriction is less than 18" ☐ Check box if **not** applicable _____
7. Pump plans (3 sets) ☐ Check box if **not** applicable _____
8. Fee Provided _____
 - a. Sewage Disposal System ≤ 1000 GPD **\$225.00** with OSE/PE documentation, **\$425.00** w/o OSE/PE documentation _____
 - b. Sewage Disposal System > 1000 GPD **\$1400** with OSE/PE documentation _____

REQUIRED DOCUMENTATION

Construction Permit

Applicant Initials

Is this a revised design package? Yes ☐ No ☒

1. Site and Soil Evaluation Report
2. If new dwelling or renovation is proposed complete architectural drawings are required.
3. If Site Grading Plan is required by LDS, provide 1 approved or proposed copy.
4. If Site Grading Plan is **not** required by LDS, 3 copies of a surveyed property plat must be provided, all to include:
 - a. Metes and Bounds of property
 - b. Soil profile hole locations, perc or K-Sat hole locations ☐ Check box if **not** applicable
 - c. Proposed well location and well specifications (when a private well is proposed)
 - d. Complete construction drawing/design of proposed sewage system, including all elevations.
5. Within 200 feet of the absorption zone or treatment unit the following must be shown:
existing or proposed wells, springs, cisterns or sewage disposal systems, existing or proposed buildings
6. Perc or K-Sat results or Perc Waiver Request
7. Alternative system design/hydraulic plans ☐ Check box if **not** applicable
8. If permeability limiting feature is less than 18" from ground surface, the following must be provided:
 - a. Verification that the site is not flooded during the wet season
 - b. Demonstration that there is sufficient hydraulic gradient to move the applied effluent off the site
 - c. Water mounding calculations
9. Pump plans (3 sets) if applicable
10. Is the proposed sewage disposal system an alternative design? Yes ☒ No ☐
11. Fee provided

BHP

BHP

BHP

BHP

BHP

BHP

a. If application is within 18 months of receiving a certification letter, no fee is required unless #10 is yes, then add \$200

b. If applying under 11a., provide certification letter.

c. Sewage Disposal System with flow of 1000 GPD or less **\$215.00** VDH Construction Permit fee
\$10.00 VDH indemnification fee
\$200.00 County SDS application fee **Total \$425.00**

If #10 is "yes" add **\$200.00** County alternative SDS review fee

Total \$625.00 per site

d. Sewage Disposal System with flow greater than 1000 GPD **\$1390.00** VDH Construction Permit fee
\$10.00 VDH indemnification fee
\$200.00 County SDS application fee **Total \$1600.00**

If you are submitting your SGP to HD instead

If #10 is "yes" add **\$200.00** County alternative SDS review fee

of LDS, provide a min of 4 copies and add \$85.00

Total \$1800.00 per site

Minor Modification

A minor modification may include, but is not limited to, relocation of sewer line, force main, conveyance line, etc. to meet set back to proposed construction such as an addition or pool; tie in new sewer line for proposed addition (e.g. pool house) to be connected to existing sewer line; relocation of septic tank and/or pump chamber. The following must be provided when a minor modification will be made:

1. Surveyed Property Plat (3 copies) - to include:

- i. Metes and Bounds of property
- ii. Well location when a private well exists

2. Architectural Plans, if applicable
3. Pump Plans (3 sets if applicable)
4. Fairfax County Building Permit Application
5. Fee provided
 - a. VDH minor modification fee **\$100.00**
 - b. If associated with a building permit review - add **\$85.00**

REQUIRED DOCUMENTATION

Individual Drinking Water Well ☒	Geothermal Well ☐	Irrigation Well ☐	Convert Existing Well ☐	Applicant Initials BHP
1. Surveyed property plat (3 copies) to include: a. Metes and Bounds of property b. Proposed well location and well design package c. Sanitary survey showing any obvious source of toxic or dangerous substances within 200ft of the proposed private well d. All recorded easements				
2. Fee provided - \$500.00 If this is a replacement well at the applicant's primary residence , no fee is required				BHP
Well Abandonment	Applicant Initials	Well Repair	Applicant Initials	
1. Completed 1st page of this application		Completed 1st page of this application with detailed summary of proposed work		
2. IF NOT primary residence, add \$500.00 fee				
Pump and Haul	Pump and Haul application must be signed and initialed by property owner			Owner's Initials
1. Copy of contract with a licensed Sewage Handling Contractor				
2. Copy of VDH Pump and Haul application				
3. Detailed construction schedule for completion of permanent disposal site				☐ Check box if not applicable
4. Proof of Bonding ☐ not required if <u>emergency</u> pump and haul				
5. Completed Malfunction Assessment Form (if application is due to malfunctioning system)				
6. Plans, specifications, fees and other data as required by the Health Department				
7. Owner gives FCHD permission to inspect property during normal business hours for duration of the pump and haul				
Voluntary Upgrade				Applicant Initials
1. Completed 1st page of this application	3. Fee provided ≤ 1000 GPD - \$225			
2. Call 703-246-2201 to schedule a consultation	>1000 GPD - \$1400			
Courtesy Inspection				Applicant Initials
1. Site and Soil Evaluation Report				
2. Describe the site or soil feature you have identified as marginal or questionable:				
3. What is the question to be discussed?				
Certification Statement				
If the certification statement on the evaluation and/or design contains the references to the Fairfax County Code (as below) in addition to 610, 613, and 630 then the evaluator/designer does not have to complete this section.				
I hereby certify that the evaluations and/or designs contained herein were conducted in accordance with the applicable provisions of the Fairfax Code, Chapter 68.1: the Individual Sewage Disposal Facilities Code, Fairfax Code, Chapter 70.1: Private Well Water Ordinance, the Sewage Handling and Disposal Regulations (12 VAC54-610), the Private Well Regulations (12 VAC5-630), the Regulations for Alternative Onsite Sewage Systems (12 VAC5-613) and all other applicable laws, regulations and policies implemented by the Virginia Department of Health. I further certify that I currently possess any professional license required by the laws and regulations of the Commonwealth that have been duly issued by the applicable agency charged with licensure to perform the work contained herein.				
☒ The work attached to this cover page has been conducted under an exemption to the practice of engineering, specifically the exemption in Code of Virginia Section 54.1-402.A.11				
Print name	Brian H. Phillips		License#	1940001374
			Date	03/25/2020
WWSP/OSE/PE Signature				

LOW EQUALIZATION - TIME DOST SYSTEMS INSPECTION SHEET

PERMIT #: 200830246

PLAN APPROVAL DATE: 4.7.20

LOCATION: 222 Donmore Drive

TAX Map #: 002 02 00444

DESCRIPTION	PER PLANS	PER INSPECTION	DATE / INITIALS	COMMENTS
PUMP CHAMBER ACCESS IS 12" ABOVE GRADE AND GRADED PROPERLY	(YES) NO	(YES) NO	JPL 01/06/22	
ELECTRICAL JUNCTION BOX IS 6" ABOVE GRADE	(YES) NO	(YES) NO	JPL 01/06/22	
PUMP CHAMBER ACCESS RISER DIAMETER	30 IN.	30 IN.	3-31-21 CC	
CHAMBER CONSTRUCTION IS SATISFACTORY	(YES) NO	(YES) NO		
Chamber Manufacturer & Size	HANOVER 2000 TJ	Hanover 2000		
Chamber Volume	36.4 GAL./IN.	36.4 GAL./IN.		
PUMPS INSTALLED PROPERLY	(YES) NO	(YES) NO	JPL 01/06/22	
Make	Zoeller	Zoeller	Zoeller	
Model #	N98	N98	N98	
Dosing Volume	112.5 GAL.	/ GAL.	/	
Expected Flow Rate	32 GPM	/ GPM	/	
Expected Run Time	210 SEC.	/ SEC.	/	
Actual Flow Rate: Pump #1		43 GPM	JPL 01/06/22	
Actual Flow Rate: Pump #2		42 GPM	JPL 01/06/22	
Actual Run Time		159 SEC.		
Standard Rest Time		6 HRS. MIN.		
Peak Rest Time		48 HRS. MIN.		
CHECK VALVES INSTALLED PROPERLY	(YES) NO	(YES) NO		
Type	BRASS	BRASS	3-31-21 CC	
FORCE MAIN INSTALLED PROPERLY	(YES) NO	(YES) NO	JPL 3/26	
Size	2.067 IN.	2.0 IN.		
Material	PVC	PVC		
Installation Depth	24 IN.	24" IN.		
FLOATS INSTALLED PROPERLY	(YES) NO	YES NO		
Number	4	4	JPL 01/06/22	
Type	Diff.	Male		
DISTANCE HIGH LEVEL ALARM / LAG ALARM IS BELOW INLET	13.4 IN.	13.4 IN.		
DISTANCE OVERRIDE / PEAK ENABLER IS ABOVE FLOOR	34.4 IN.	35 IN.		
DISTANCE TIMER / ENABLER IS ABOVE FLOOR	23 IN.	23 IN.		
DISTANCE REDUNDANT OFF IS ABOVE FLOOR	18 IN.	18 IN.		
FLOW EQUALIZATION ZONE	20.6 IN.	20" IN.		
CONTROL PANEL INSTALLED PROPERLY		(YES) NO		
Make	AMERICAN ONSITE	AMERICAN ONSITE		
Model #	DEPRAB124AJL0P(C)RCA	DEPRAB124-AJLP(C)RCA		
Are Alarms And Pump Controls On Separate Circuit Breakers		(YES) NO	JPL 01/06/22	per BOB tested positive w/ cond. dtd
Do Floats Alternate Properly		(YES) NO		
Does The Panel Have Current Sensors To Sound Alarm If Pumps Are Not Working		(YES) NO	JPL 01/06/22	not observed Setup.
Does Override / Peak Enabler Function Properly		(YES) NO		
Event Counter Initial Setting: Pump #1		6		
Elapsed Time Meter Initial Setting: Pump #1		0h 0m		
Event Counter Initial Setting: Pump #2		16		
Elapsed Time Meter Initial Setting: Pump #2		0h 2m		
4" CONCRETE BLOCK OR EQUIVALENT SET UNDER BOTH PUMPS	(YES) NO	(YES) NO	3-31-21 CC	
SURFACE DRAINAGE DIRECTED AWAY FROM ALL TANKS	(YES) NO	(YES) NO	JPL 01/06/22	24" cover

ATV Blower shown function

BIO-MICROBICS MICROFAST TREATMENT SYSTEM INSPECTION SHEET

Permit #: 200830246

Plans Approved: 4.7.20

Location: 222 Donmore Drive

Tax Map #: 00202 0044A


DESCRIPTION	PER DESIGN	PER INSPECTION	DATE / INITIAL
MicroFAST Tank Manufacturer	HANOVER	Hanover	3-31-21 CC
Size	1500 TJ	1500 TJ	↓
MicroFAST Unit Size	0.75	0.75	↓
Is The MicroFAST Unit Designed With A Lid Or On Leg Extensions?	LEGS		
Length of Air Supply Line From The Blower To MicroFAST Unit (Must NOT Be Greater Than 100 Feet)	<100 FT.	<100 FT.	JPL 1/6/22
Is The Air Supply Line A Minimum Of 2 Inches In Diameter?	☒ YES NO	YES NO	Backfilled
Is The Air Supply Line To The MicroFAST Unit Secured To Prevent Vibration Induced Damage?	☒ YES NO	YES NO	Backfilled
Is There Positive Fall On The Air Supply Line From The Blower Control System To The MicroFAST Unit?	☒ YES NO	YES NO	Backfilled
Is The Air Supply Line Secured With Noncorrosive Clamps Every 2 Feet?	☒ YES NO	YES NO	Backfilled
Is Blower Control System Located Above Grade?	☒ YES NO	☒ YES NO	yes
Is Blower Control System Located On Solid Surface Or Concrete Base?	BASE		yes
Is The Blower Functioning Properly?	☒ YES NO	YES NO	yes
Is There A 24 Inch Tank Riser Over The Inlet Tee?	☒ YES NO	YES ☒ NO	72"
Is Vent Pipe Located Above Grade To Avoid Infiltration?	☒ YES NO	☒ YES NO	JPL 1/6/22
Is Cap For Vent Pipe A Minimum Of 7.1 Square Inches?	☒ YES NO	☒ YES NO	↓
Is Cap For The Vent Pipe Secured With Stainless Steel Screws?	☒ YES NO	☒ YES NO	↓
Does The Vent Pipe Cap Have An Insect Screen?	☒ YES NO	☒ YES NO	↓
What Is The Distance Between The Bottom Of The Unit And The Bottom Of The Tank?	N/A IN.	N/A IN.	↓
Is There A 6 Inch Inspection / Pumpout Port Over The Treatment Zone?	☒ YES NO	☒ YES NO	↓
Is The 6 Inch Inspection / Pumpout Port Above Grade?	☒ YES NO	☒ YES NO	↓
Is The 6 Inch Inspection / Pumpout Port Cap Secured?	☒ YES NO	☒ YES NO	↓
Is The 6 Inch Inspection / Pumpout Port Securely Fastened To The Tank?	☒ YES NO	☒ YES NO	↓
How Much Backfill Is Over Tank?	IN.	24" IN.	↓

NOTES

Microfast # 34931

LEGEND FOR GRADING PLANS

- EXISTING CONTOUR — 30 —
 PROPOSED CONTOUR — 20 —
 EXISTING SPOT ELEVATION +00
 PROPOSED SPOT ELEVATION +12.5
- PROPOSED CLEARING LIMITS LOD ————
- TREE PROTECTION
 STD. & SPEC. 3.38 TP — TP — TP —
- SILT FENCE
 STD. & SPEC. 3.05 SF
- CONSTRUCTION ENTRANCE
 STD. & SPEC. 3.02 CE
- TEMPORARY SEEDING
 STD. & SPEC. 3.31 TS
- PERMANENT SEEDING
 STD. & SPEC. 3.32 PS
- CULVERT INLET PROTECTION
 STD. & SPEC. 3.08 CIP
- SUPER SILT FENCE
 STD. & SPEC. 3.07 SSF
- INLET PROTECTION
 STD. & SPEC. 3.07 IP
- DIVERSION DIKE
 STD. & SPEC. 3.09 ID
- RIGHT-OF-WAY DIVISION
 STD. & SPEC. 3.11 RW
- SEDIMENT TRAP
 STD. & SPEC. 3.07 ST
- XXXXXXXXXXXXXXXXXXXX — DENOTES ROOT PRUNING



PROPOSED DISTURBED AREA = 74,488 SF OR 1.71 ACRES

PAGE 4

GRADING PLAN AND EROSION AND SEDIMENT CONTROLS PHASE II

222 DONMORE DRIVE
 LOT 44A SEC. 3
 SENECA FARMS
 DRANESVILLE DISTRICT #1
 FAIRFAX, VIRGINIA

REVISION	DATE

SCALE: 1"=30'

GRAPHIC SCALE
 0' 15' 30' 60'

SCALE: 1"=30'

SHEET 3 OF 9

COMMONWEALTH OF VIRGINIA
 ANNEMARIE M. TURNER
 Lic. No. 037035
 05-26-20
 PROFESSIONAL ENGINEER

CIVIL SPUR


DESIGN — CONSULTING
 SITE PLANNING — CONSULTING
 929 WEST BROAD STREET #200, FALLS CHURCH VA, 22046
 OFFICE (703) 653-7175 CELL (540) 207-5681
 EMAIL: ROGER@CIVILSPUR.COM

1. ALL CONSTRUCTION MATERIALS AND METHODS MUST CONFORM TO APPLICABLE LOCAL CODES AND STATE REGULATIONS.
2. ALL PIPE JOINTS SHALL BE PRIMED AND CHEMICALLY SEALED.
3. ANY DEVIATION FROM THIS DESIGN MUST BE APPROVED BY THE DESIGNER PRIOR TO INSTALLATION OF THE SYSTEM.
4. ELECTRICAL WIRING TO BE INSTALLED UNDER THE DIRECT SUPERVISION OF OF A LICENSED ELECTRICAL CONTRACTOR, ACCORDING TO NEC, STATE & LOCAL ELECTRICAL CODES AS APPLICABLE.
5. CONTRACTOR IS TO INSTALL CONCRETE TANKS ON UNIFORMLY FIRM AND STABLE COMPACTED GROUND, CRUSHED STONE IS RECOMMENDED TO PROVIDE UNIFORM SUPPORT TO THE TANK BOTTOMS.
6. SEPTIC TANK MUST BE WATERTIGHT AND CONFORM TO APPLICABLE STATE & LOCAL CODES & REQUIREMENTS.
7. CONTRACTOR MUST NOTIFY "MISS UTILITY" AND HAVE A CLEARED TICKET PRIOR TO STARTING EXCAVATION AT THE SITE.
8. CONTRACTOR IS RESPONSIBLE FOR ANY REQUIRED AMOUNT OF IMPORTED FILL (IN PLACE).

1. REFER TO SITE DRAWINGS AND NOTES FOR SPECIAL REQUIREMENTS.
2. MACHINERY SHOULD AVOID THE PERCOLATION AREA.
3. MACHINERY MUST NEVER TRAVERSE THE EXCAVATED OR EXPOSED PERCOLATION AREA.
4. IF WOODED, SPECIAL CARE MUST BE TAKEN IN CLEARING THE DRAINFIELD AREA.
5. CONTRACTOR MUST PROVIDE ADEQUATE ACCESS FOR CORRECT INSTALLATION.
6. THE SEWAGE SYSTEM MUST BE INSTALLED DURING DRY CONDITIONS.

1. INSTALL THE ABSORPTION AREA ON CONTOUR UNLESS THERE IS A GRADE CUT SPECIFIED ON THE DRAWINGS OR IN THE NOTES PROVIDED IN THIS DESIGN PACKAGE.
2. DO NOT SMEAR OR COMPACT THE PERCOLATION AREA DURING EXCAVATION.

1. MINIMUM BACKFILL COVER OVER THE AGGREGATE IS 12".
2. MAXIMUM BACKFILL COVER OVER THE AGGREGATE IS 20".
3. BACKFILL WITH SUITABLE LOOSE MATERIAL (SANDY LOAM TO SANDY CLAY LOAM) FREE OF LARGE OR DAMAGING OBJECTS. SEED AND STRAW BACKFILLED OR DISTURBED AREAS (OR PLACE SOD WHEN REQUIRED).
4. PROVIDE EROSION PROTECTION FOR BACKFILL MATERIAL IN ACCORDANCE WITH STATE & LOCAL STANDARDS AND MAINTAIN UNTIL PERMANENT PROTECTION IS ESTABLISHED.
5. BACKFILL SHOULD BE GRADED TO PREVENT INFILTRATION OF SURFACE WATER AND DIVERT SURFACE WATER RUN OFF AWAY FROM THE SYSTEM COMPONENTS.
6. DO NOT GRADE WITHIN 20' OF THE PROPOSED SYSTEM DISPOSAL AREA(S).
7. KEEP DRIVEWAY A MINIMUM OF 10' FROM THE SEPTIC SYSTEM AND ITS COMPONENTS.
8. ALL UTILITIES TO BE $\geq 10'$ TO THE SEWAGE SYSTEM.
9. ALL DF COMPONENTS TO BE A MINIMUM OF 10' FROM THE PROPERTY LINES, 10' FROM WALKOUT BASEMENT FOUNDATION AND 20' FROM PORTIONS OF FOUNDATION THAT ARE BURIED.



[A] 138.6' SCH40 PVC SEWER LINE @
 AT 1.68%
 [B] 109.5' SCH40 PVC SEWER LINE @
 INSTALL AT 2-4%
 [C] BIOMICROBICS 0.75 MICROFAST ATU
 (DROP IN) UNIT IN HANOVER
 PRECAST 1500 GAL TANK
 IN=348.67
 OUT=348.54
 FG=352.0

- D HANOVER PRECAST 2000 GAL TJ
 PUMP TANK W/ RISER FOR
 SAMPLING
 IN=348.44
 OUT=348.27
 FG=352.0
 E 2" SCH40 PVC FORCE MAIN-236.0'
 F 6-PORT CONCRETE SURGE BOX
 WITH SANITARY "T"
 G 10-PORT CONCRETE
 DISTRIBUTION BOX
 H 6" PVC SLEEVE UNDER
 DRIVEWAY-63.4'



SOILS INC.

8399 WEST MAIN ST, MARSHALL, VA 20115
P.844.447.SOIL (7645) F.540.364.2060

PROJECT: 222 DONMORE DRIVE
DATE: 04/02/2020 JOB NO. T1812
PAGE: 2 OF 8
SCALE: 1"=40'
GPIN OR TM #: 2-2-02-0044A
COUNTY/STATE: FAIRFAX COUNTY, VA



County of Fairfax, Virginia

To protect and enrich the quality of life for the people, neighborhoods, and diverse communities of Fairfax County

February 8, 2021

John Rhodes TR
74 S Player Crest Circle
Spring, TX 77382

RE: Sewage Disposal System Construction Permit
Constructed on/at: 222 Donmore Drive, Great Falls VA 22066
TM# 0022 02 0044A

Health Department ID Number: 200830246
System Capacity: 5 Bedrooms/750 gallons per day

Dear John Rhodes TR:

This letter and the attached drawings, specifications, calculations, and the attached documentation dated March 25, 2020 constitute your permit to install a sewage disposal system on the property referenced above.

The Fairfax County Health Department (FCHD) hereby recognizes that the design submitted by Brian H. Phillips, AOSE, has been certified by the designer to comply with the requirements of the Code of Virginia and grants permission to install the system as designed in the area shown on the attached plans and specifications.

The sewage disposal system design is approved based on a 1.25 gal/ft²/day loading rate at an install depth of 20". Chapter 68.1 of the Fairfax County Code requires a minimum gravel depth of eight inches under the installed percolation piping and two inches over the piping. A minimum of 12 inches and a maximum of 20 inches of clean backfill shall be placed over the gravel. Untreated building paper or other suitable material shall be placed at the interface of the gravel and soil. All trench widths are required to be 2 feet and be installed 6 feet center to center.

If modifications or revisions are necessary between now and when the system is constructed, please contact the OSE who designed the system upon which this permit is based. Should revisions be necessary during construction, your contractor should consult with the OSE. The OSE is authorized to make minor adjustments in the location or design of the system provided that adequate documentation is provided to FCHD.

The OSE that submitted the design for this permit is required by §32.1-164.1 of the Code of Virginia to inspect the system at the time of the installation and provide an inspection report and completion statement to FCHD. Chapter 68.1 of the Fairfax County Code requires that no part of the system shall be covered with earth or used until inspected, corrections made if necessary, and approved by the FCHD. The sewage system may not be placed into operation until you have obtained an Operation Permit from FCHD.

Grantor: RHODES, JOHN
Date/Time: 1/21/2022 10:48:39 AM
Book/Page: 27527/1341
Recorded in FAIRFAX CIRCUIT COURT
TESTE: JOHN T. FREY

Grantee: FAIRFAX COUNTY HEALTH
Instrument: 2022006634.001
of Pages: 3

John T. Frey

Fairfax County Health Department
Division of Environmental Health
Onsite Sewage and Water Section
10777 Main Street, Suite 102, Fairfax, VA 22030
Phone: 703-246-2201 TTY: 711 Fax: 703-278-8157
www.fairfaxcounty.gov/hd




John Rhodes TR
Health Department ID Number: 200830246
February 8, 2021

This permit is issued in accordance with the provisions of Title 32.1, Chapter 6 of the Code of Virginia as Amended, and § 12VAC5-610-340 of the Sewage Handling and Disposal Regulations of the Virginia Department of Health. The continued validity of this permit is contingent upon compliance with the operation and maintenance requirements contained in Part 3 of the Regulations for Alternative Onsite Sewage Systems of the Virginia Department of Health (12VAC5-613-120 et seq.). Owners are advised to be aware of the operation and maintenance instructions for their permitted alternative onsite sewage system and to follow them. Copies of the operation and maintenance instructions can be found by contacting the local health department for the locality where the onsite sewage disposal system is located.

This Construction Permit is null and void if site and soil conditions are changed from those shown on your application or if conditions are changed from those shown on the attached plans and specifications. FCHD may revoke or modify any permit if, at a later date, it finds that the system would threaten public health or the environment.

This authorization to construct a sewage disposal system expires August 8, 2022. This permit is not transferable to another location.

Sincerely,



Crystal M. Crampton
Environmental Health Specialist



Kevin R. Wastler
Environmental Health Supervisor



County of Fairfax, Commonwealth of Virginia.

The foregoing instrument was acknowledged before me this 9th
day of February, 20 21, by

Crystal M. Crampton and Kevin R. Wastler
(Name of person seeking acknowledgement)

Janice Joshi


Notary Public

My Commission Expires: December 31st, 2023

Operation and Maintenance Manual

SOILS INC.

MicroFAST 0.75 Pump to
Gravity System
at
222 Donmore Drive
Great Falls, VA 22066



Provided by:
Soils, Inc.
8331 W. Main Street
Marshall, VA 20115

Work Order Number: T1812
January 7, 2022

Table of Contents

Introduction 1

System Information 2

Control Functions..... 3

Guidelines for Operation 4

Inspection Schedule 6

Sampling Information 8

Owner Responsibilities 9

Appendices

- System Completion Statement
- As-Built Drawing
- MicroFAST owners manual

Introduction

Your new septic system is a major advancement over the septic systems of the past. Previously, the soil media was relied upon to provide nearly all of the wastewater treatment. With advancements in onsite wastewater treatment the burden has been significantly shifted to the Advanced Treatment Unit (ATU).

This manual provides information to help you monitor the health of your system and ensure the longest possible lifespan.

Please contact a qualified service provider or your local health department before performing any work on your septic system. Most work requires a health department permit and/or a qualified licensed professional to perform the work.

Contact Information:

System Designer

Soils, Inc.
8331 W. Main St.
Marshall, VA 20115
Phone: (540) 364-1122
Fax: (540) 364-2060
Soils-inc.com

Preferred Service Provider

Markham Smith
(703) 615-5000 (cell)
8331 W. Main St.
Marshall, VA 20115
Phone: (540) 364-1122
mark.smith@soils-inc.com

System Installer

Settle Excavating and Plumbing
5811 Windsor Retreat
Warrenton, VA 20186
(540) 699-0167

System Information

System Location:	222 Donmore Drive, Great Falls, VA 22066
Treatment System:	MicroFAST 0.75 Advanced Treatment Unit in a 2000 gallon Hanover Precast septic tank.
Disposal Method:	Pump to Gravity
Dispersal Method:	5 trenches, each 75' long. 4" black plastic perforated, corrugated drain pipe.
Design Loading:	750-gpd peak daily flow, 5 bedrooms

Note: Additional information on system layout, components, etc. is included in the System Installation Completion Statement in the Appendices.

Repair parts for your system can be found at VAMAC Plumbing Supply
The closest VAMAC locations to the above referenced property are:

3501 Jefferson Davis Hwy.
Fredericksburg, VA 22408
(540) 898-2096

13794 Telegraph Road
Woodbridge, VA 22192
(703) 494-5449

11186 Leadbetter Road
Ashland, VA 23005
(804) 752-4680

601 McGhee Road
Winchester, VA 22603
(540) 535-1983

14 Cardinal Park Dr. SE
Leesburg, VA 20175
(703) 771-7990

8020 Centreville Rd.
Manassas, VA 20111
(703) 330-8990

700 Industrial Rd.
Warrenton, VA 20186
(540) 349-0081

750 Germanna Highway
Culpeper, VA 22701
(540) 399-2150

Control Functions

Make arrangements with a reliable service person to provide regular monitoring and maintenance, and place the service person's phone number on or in your control panel. The external control/alarm panel for your septic system should only be managed by a licensed service provider. Making changes to the operational conditions of your system can lead to system failure and voiding of any warranties, resulting in costly repairs and/or replacement.

Pump Control Panel

Your Pump Control Panel contains an alarm function to notify you of a problem with the system. The audible alarm can be silenced by utilizing the toggle switch located on the side of the panel box or the button located on the front cover. The alarm light will remain on until the alarm condition is fixed.

When the alarm activates it means the effluent level in the pump tank is outside the normal range. This usually occurs for one of two reasons: a) the pump has ceased to operate, or b) there has been a substantial inflow of sewage into the tank in a short period of time. The latter often occurs when a leaky toilet or faucet is adding a steady stream of water into the system. Your local hardware store will carry do-it-yourself kits to test for toilet leaks. If the inflow is from a known source that you can control, you should immediately shut off that flow into your drainage system. If you determine that an errant plumbing fixture is not the source of the problem, contact your service provider at once, as it is likely a pump issue. With normal use, the tank has a reserve storage capacity good for about 24 hours, so it is best if you restrict water usage until you can get your service provider on site.

MicroFAST Control Panel

The MicroFAST control panel provides an alarm to notify you when there is no power going to the ATU blower. To silence this alarm simply press the button labelled "Alarm." It is important to call your service provider right away if this alarm goes off, as it means the ATU is not functioning and therefore the effluent in the system is not being properly treated.

Guidelines for Operation

As a homeowner you can take measures to ensure the proper operation of your system. There are three general categories: What you put into your system, How much you put into your system, and How you maintain your system.

What you put into your system

It is very important that you are conscious of what you are putting into your system. Your ATU unit and drainfield host a sensitive ecosystem of microbes and bugs to treat the sewage. This balance can be easily upset if harmful chemicals or high strength waste is introduced to the system. Below you will find a list of items that should not be put into the system:

- Hair Combing
- Disposable Diapers
- Tampons
- Dental Floss
- Gauzes Bandages
- Oil
- Baby Wipes
- Thinners
- Pesticides
- Coffee Grounds
- Sanitary Napkins
- Condoms
- Cigarette Butts
- Fat/Grease
- Paper Towels
- Paints
- Prescriptions

This list is just a sample of items that should not be put into your septic system. If you ever have a question as to whether you should put something into your septic system, call your licensed service provider, or err on the side of caution and do not put it into your septic system. A good rule of thumb is this:

**If it hasn't passed through you then it should not enter your septic system.
Toilet tissue is the only exception.**

Additionally, never add any "septic system additives" to your system. Your ATU is a sophisticated system and when operating correctly will not need any special additives. These additives can upset the balance of the system and create significant problems.

The use of garbage disposals is not recommended with your system.

Operation Guidelines (Continued)

How much you put into your system

Almost as important as what you put into your system is how much you put in. Your system is designed for a particular gallon per day (GPD) loading. This is generally based on 75 gallons per person and 2 people per bedroom (150 gallons per bedroom). For your particular daily design rate, see the "System Information" portion of this manual.

In general, this should not be an issue if you adhere to the occupancy limits of your system.

Several steps you can take to help avoid hydraulically overloading your system include:

- *Spreading laundry out over the entire week as opposed to doing multiple loads at a single time (e.g., Saturday morning)*
- *Avoid doing multiple water-intensive tasks at the same time (e.g., laundry, dishes, showers, baths)*
- *Install low flow fixtures*
- *Be conservative with your water usage*

How you maintain your system

Neither of the two above items will matter if you do not properly maintain your system. The first and most important thing you can do is to have a maintenance contract with a licensed service provider. In fact, having a contract with a licensed service provider is required by Virginia statute (see next section).

A licensed service provider will be able to catch potential problems and fix them before they become major issues, thereby saving you money in the long run. We highly recommend not simply going with the lowest cost service provider as that may cost you far more in the long run.

While your service provider will periodically check and provide maintenance to your system, you will need to keep the system healthy on a day-to-day basis. In addition to following the guidelines on what (and what not) to put in the system, proper maintenance of the drainfield area is very important. Keep all the vegetation on and around the drainfield cut down and prevent any trees from encroaching on the drainfield area. The area around the treatment works should also be well maintained so all surface water is diverted away from the tanks and not allowed to pool on or around the tanks. Additionally, you should not drive heavy equipment over your drainfield tanks or tanks. The only equipment that should be driven on or around these components is a small riding mower.

With these simple steps your septic system should operate well and last you for many years.

Inspection Schedule

Inspections are an integral part of ensuring the proper operation of your system. As such, the State of Virginia requires that you maintain a service contract with a licensed service provider. While we recommend that you use the licensed service provider listed, any *licensed* service provider may be used.

All inspection and reports shall adhere to the minimum requirements prescribed in the *Alternative Onsite Sewage System Regulations*. The following Code Sections govern inspections and reports:

12VAC5-613-150. Operator requirements for AOSS with flows up to 40,000 GPD, minimum frequency of visits

The owner of each AOSS shall have that AOSS visited by an operator in accordance with Table 4.

<i>Avg. Daily Flow</i>	<i>Initial Visit</i>	<i>Regular visits following initial visit</i>
≤1,000 GPD	Within 180 calendar days of the issuance of the operation permit	Every 12 months
>1,000 GPD to 10,000		Quarterly

Table 4. Minimum Operator Visit Frequency for AOSSs up to 40,000 GPD

12VAC5-613-180. Mandatory visits; inspection requirements

When an operator is required to make a visit to an AOSS the operator shall, at a minimum, accomplish the following:

1. Inspect all components of the AOSS and conduct field measurements, sampling, and other observations required by this chapter, the O&M manual, or deemed necessary by the operator to assess the performance of the AOSS and its components.
2. Review and evaluate the operation of the AOSS, perform routine maintenance, make adjustments, and replace worn or dysfunctional components with functionally equivalent parts such that the system can reasonably be expected to return to normal operation.
3. If the AOSS is not functioning as designed or in accordance with the performance requirements of this chapter and, in the operator's professional judgment, cannot be reasonably expected to return to normal operation through routine operation and maintenance report immediately to the owner the remediation efforts necessary to return the AOSS to normal operation.

Inspection Schedule(Continued)

12VAC5-613-190. Reports

When required to file a report, the operator shall complete the report in a form approved by the division. In accordance with § 32.1-164 H of the Code of Virginia, the operator shall file each report using a web-based system and pay the required fee. The operator may, solely at his own discretion, file reports in addition to those required by this chapter. Each report shall be filed by the 15th of the month following the month in which the visit occurred and shall include the following minimum elements:

1. The name and license number of the operator;
2. The date and time of the report;
3. The purpose of the visit, such as required visit, follow-up, or reportable incident;
4. A summary statement stating whether:
 - a. The AOSS is functioning as designed and in accordance with the performance requirements of this chapter;
 - b. After providing routine operation and maintenance, the operator believes the AOSS will return to normal operation; or
 - c. The system is not functioning as designed or in accordance with the performance requirements of this chapter and additional actions are required by the owner to return the AOSS to normal operation;
5. All maintenance performed or adjustments made, including parts replaced;
6. The results of field measurements, sampling, and observations;
7. The name of the laboratory that analyzed samples, if appropriate; and
8. A statement certifying the date the operator provided a copy of the report in electronic or hard copy form to the owner.

Sampling Information

Sampling is an important measure of how your system is performing. It can help identify issues before they become significant and reduce the likelihood of system failure or environmental contamination. As such, Virginia requires periodic sampling of your system. This sampling should be taken care of by your licensed service provider. The following are the Code Sections governing sampling:

12VAC5-613-100. Performance requirements; laboratory sampling and monitoring

- A. Sampling shall be done in accordance with the requirements in the Alternative Onsite Sewage System Regulations. Samples shall be taken from the sampling port or the pump tank if a sampling port has not been provided with your system (See Installation Completion Statement for sampling port location).
- B. All effluent samples must be taken at the end of all treatment, prior to the point where the effluent is discharged to the soil treatment area unless changed pursuant to 12VAC5-613-90 or 12VAC5-613-210. The designer shall identify the sampling points. When required, the sampling point for chlorine disinfection shall be at the end of the chlorine contact tank if TRC is to be used to measure compliance.
- C. All sampling and monitoring shall be conducted according to procedures approved under 40 CFR Part 136 or alternative methods approved by the U.S. Environmental Protection Agency unless other procedures have been specified in this chapter.
- D. The owner of each small AOSS must ensure that an initial grab sample of the effluent from the treatment unit is collected within 180 days of system operation. The sample must be analyzed in accordance with 40 CFR Part 136 or alternative methods approved by the U.S. Environmental Protection Agency within the first 180 days of operation. Thereafter, if the treatment unit has received general approval, a grab sample is required once every five years. Samples shall be analyzed for BOD5 and, if disinfection is required, fecal coliform. Treatment units utilizing chlorine disinfection may alternatively sample for TRC instead of fecal coliform. Sample results shall be submitted to the local health department by the 15th of the month following the month in which the sample was taken.

Owner Responsibilities

As the owner of an Alternative Onsite Sewage System (AOSS) you have several State mandated responsibilities. Below is the state code section detailing homeowner responsibilities.

12VAC5-613-140. Owner responsibilities

It is the owner's responsibility to do the following:

1. Have the AOSS operated and maintained by an operator;
2. Have an operator visit the AOSS at the frequency required by this chapter;
3. Have an operator collect any samples required by this chapter;
4. Keep a copy of the log provided by the operator on the property where the AOSS is located in electronic or hard copy form, make the log available to the department upon request, and make a reasonable effort to transfer the log to any future owner;
5. Follow the O&M manual and keep a copy of the O&M manual in electronic or hard copy form for the AOSS on the property where the AOSS is located, make the O&M manual available to the department upon request, and make a reasonable effort to transfer the O&M manual to any future owner; and
6. Comply with the onsite sewage system requirements contained in local ordinances adopted pursuant to the Chesapeake Bay Preservation Act (§ 10.1-2100 et seq. of the Code of Virginia) and the Chesapeake Bay Preservation Area Designation and Management Regulations (9VAC10-20) when an AOSS is located within a Chesapeake Bay Preservation Area.

SOILS INC.

8399 W. Main St.
Marshall, VA 20115
Phone: (540) 364-1122
Fax: (540) 364-2060
soils-inc.com

1043

AOSE/PE Inspection Report and Completion Statement

Commonwealth of Virginia
State Department of Health

Fairfax County Health Department

Health Department ID #: 200830246

Tax Map ID: 2-2-02-044A

Name of AOSE/PE: Brian H. Phillips

License # 1940001374

Contactors Name: Settle Excavating and Plumbing

License # 27010032072

Owner's Name: John and Sheri Rhodes

Owner's Address: 74 South Player Crest Circle

The Woodlands, TX 77382

Location of Installation: 222 Donmore Drive, Great Falls, VA 22066

Subdivision: Seneca Farms

Block: _____

Section: _____

Lot: 44A

Inspection Results

Component	Comments, Materials, Etc. Deficiencies Observed, Date Deficiencies Observed, Corrective Actions Required	Date Approved
Water Supply Location and Construction	Class IIIB well, measurements pulled. Well permit # 200860270 & 210420206. By others. See note below.	*
Building Sewer	4" SCH40 PVC; >1 1/4" fall per 10'	3/26/2021
Septic Tank	1500 Gallon Hanover TJ Tank w/ATU	3/26/2021
Inlet-Outlet Structure	Sealed Unit	3/26/2021
Pump and Pump Station	2000 gallon Hanover TS Tank w/ Zoeller N98 pump. 450gal ADF, 112.5 gal/dose, 4 doses/day. 42 GPM; Run =2:39m, Rest=6h. P1: Ct=6, ETM=0:00h. P2: Ct=16, ETM=00:02h. Peak Ct=7, Alarm Ct=5.	1/6/2022
Conveyance Method	2" SCH40 PVC force main.	3/26/2021
Distribution Box or Pressure Manifold	6 port concrete surge box supplying 10 port concrete d-box with plastic levelers , both on concrete pads.	3/26/2021
Header, Conveyance, Drip, Chambers, Etc.	4" SCH40 PVC	3/26/2021
Absorption Trenches and Dispersal Field	5 trench laterals, each 75' long, 2' wide, and 6' on center. 4" black plastic perforated, corrugated drain pipe.	3/26/2021
(Other Components: Treatment Unit, etc.)	MicroFAST 0.75 ATU	1/6/2022
Note	Well location was changed by driller and builder. Soils, Inc. was not notified of the change and had no input as to the new location and was permitted by others.	*

Attach observed deficiencies and corrective actions taken on a separate completion statement as necessary.

2.43


AOSE/PE Completion Statement: As-Built Drawing

Commonwealth of Virginia
State Department of Health

Health Department ID Number: 200830246 Tax Map # 2-2-02-044A

Triangulate critical system components to fixed reference points.

See attached as-built



☒ Check here if the as built is on a separate page attached to this form.
(Attachment must display Health Department ID number, tax map number, and must be signed & dated by the AOSE/PE)

I hereby certify that on 1/6/2022 I, or an employee under my direct supervision, inspected this sewage system's construction. The onsite system has been installed and completed in accordance with the construction permit issued 2/9/2021 and is in compliance with the *Sewage Handling & Disposal Regulations (12VAC5-610 et seq)*, the *Alternative Onsite Sewage Regulations (12VAC5-613)*, and the *Private Well Regulations (12VAC5-630 et seq)*, when applicable, and the plans and specifications for this project.

AOSE/PE Signature:

Date: 1/25/2022


Print Name:

Brian H. Phillips


3 of 3

12/10/20212 T1812

222 Donmore Drive
Great Falls, VA 22066
GPIN/TMID 2-2-02-0044A
HDID 200830246



A1 = 91'	B1 = 115'
A2 = 84'	B2 = 122'
A3 = 274'	B3 = 340'
A4 = 246'	B4 = 307'
D5 = 70'	C5 = 62'



SOILS INC.




Better Water. Better World.®

FAST® Owner's Manual

FOR USE WITH

(NSF Std 40 & 245) **MicroFAST®** 0.5, 0.75, 0.9, 1.5
(non-NSF certified) **MicroFAST®** 3.0, 4.5, 9.0
(ETV/EPA tested) **RetroFAST®** 0.150, 0.250, 0.375
NitriFAST® 0.5, 0.75, 0.9, 1.5, 3.0, 4.5, 9.0
HighStrengthFAST® 1.0, 1.5, 3.0, 4.5, 9.0



FAST Owner's Manual © 2009 Bio-Microbics, Inc. Revised December 2009.
FAST, MicroFAST, RetroFAST, NitriFAST, and HighStrengthFAST are registered trademarks used under license.

OWNER'S MANUAL

FOR USE WITH FAST® SYSTEMS:

(NSF® Std 40/245 cert.)
(Non-NSF cert.)

(ETV®/EPA tested)

MicroFAST® 0.5, 0.75, 0.9, 1.5
MicroFAST® 3.0, 4.5, 9.0
NitriFAST® 0.5, 0.75, 0.9, 1.5, 3.0, 4.5, 9.0
HighStrengthFAST® 1.0, 1.5, 3.0, 4.5, 9.0
RetroFAST® .150, .250, .375

GENERAL INFORMATION

All FAST® products are ETL certified for safety (electrical, environmental, etc.). One or more of the following patents protects this process: 3,966,599; 3,966,608; 3,972,965; 5,156,742. Certified by NSF International, the MicroFAST® 0.5, 0.75, 0.9 and 1.5 systems meets NSF Standard 40, Class 1 and Standard 245 certifications for single-residence wastewater treatment devices. If you have questions regarding any Bio-Microbics products, please contact us:

800-753-FAST (3278) or (913) 422-0707
e-mail: onsite@biomicrobics.com

Dear FAST® System Owner

Congratulations! You have a FAST® (Fixed Activated Sludge Treatment) wastewater treatment system installed on your property.

At the forefront of green technology, the FAST® System by Bio-Microbics meets the highest industry treatment standards. Based on environmentally sound and simple scientific principles, the FAST® process is our continued commitment to improve small onsite treatment capabilities. You can take pride in knowing that, with the FAST® system, you will help ensure a clean environment for future generations.

Please take time to read this FAST® Owner's Manual, you will learn important safety precautions, review detailed information on proper use and care of your system. Designed for minimal operator attention, the FAST® System contains only one moving part – the blower. By consistently following a maintenance schedule and being mindful of what can go down your drains, you can enjoy the lasting benefits FAST® Wastewater Treatment System for decades to come.

Top things you can do to prolong the life of your system:


1. Have the FAST® system inspected and tank pumped as necessary.
2. Keep track of the substances entering your system, please review the list of Do's & Don'ts
3. Keep the FAST® System operating - do not turn off the blower.
4. Care for your drain field or irrigation system (if incorporated into your FAST® System).

If you should desire any further assistance, please contact Bio-Microbics at sales@biomicrobics.com or call us at 800-753-FAST (3278).

Thank you again for using FAST®!

Sincerely,

Bio-Microbics Team





Authorized to NSF Certified Standard 40

NSF INTERNATIONAL

CERTIFIED SYSTEMS SERVICE POLICY

All NSF (National Sanitation Foundation) Standard 40 Class I and 245 certified wastewater treatment systems (MicroFAST® 0.5, 0.75, 0.9, 1.5) have an initial two-year service agreement included with the system's initial purchase price (two service calls per year). The NSF service calls **ONLY** cover NSF Standard 40 certified systems; other components of the septic system are NOT covered.

If there are any deficiencies in the FAST® system's operation or components, the service person will notify the owner in writing and detail when these deficiencies can be fixed.

The company listed on the blower housing or control panel label performs this service. During an NSF service call, the service company shall inspect the blower for proper operation, visually inspect the system's effluent for clarity, clean the blower air filter and assure proper function of the control panel. If these service calls are not performed on your NSF certified system, or not all of the items are checked, please call Bio-Microbics at:

For continual service of NSF certified systems beyond the first two years, an extended service agreement is available through your local Distributor or current service provider. This policy should provide the same services and may include any additional service that are required by local regulation. For continual service of NSF certified systems beyond the first two years, an extended service agreement is available through your local

ABOUT FAST®: The FAST® (Fixed Activated Sludge Treatment) system uses naturally occurring bacteria (biomass) to treat sewage for dispersal into the environment. This continuous process provides the biomass with waste (food) and air in a suitable environment. Dead bacteria and non-biodegradable waste settle and accumulate in the bottom of the septic tank for periodic removal.

The FAST® process consists of the treatment unit and blower. The blower provides air to the system via the air supply pipe. The air supply pipe and draft tube create an air lift. The air lift mixes oxygen and waste throughout the media inside the tank. Bacteria grows on the media and digests the waste. A vent pipe expels harmless vapors created by the process.

INTRODUCING SUBSTANCES INTO THE SYSTEM: While the FAST® wastewater treatment system will process most waste produced by the average household, introducing large amounts of substances into the system may reduce the efficiency of the system or stop the treatment process by destroying the biomass. These substances can be grouped as: prohibited substances and limited-use substances. Please refer to the **"DO'S AND DON'TS"** list to get familiar with **What You Can Put Down the Drain** to maximize the system's efficiency and reduce the time period between septic tank pump-outs.

IN GENERAL: If a substance is harmful to humans or is anti-biotic in nature, it should not be put into any septic system - including FAST®.

If you have a question regarding the effect of a particular substance on the FAST® system, call your Bio-Microbics service technician.

WARNING

DO NOT ENTER THE SEPTIC TANK. Hazards exist in a septic system. All precautions must be followed when inspecting the system. Keep tank openings covered at all times. Only authorized service personnel should service a septic system. Lethal gases, high voltage electricity, and other deadly hazards associated with the system.

WARNING


Only qualified service staff should open access ports and/or covers. Infectious organisms exist in a septic tank. If any contact with wastewater, immediately wash and disinfect all exposed areas and contact personal physician. Failure to do so could result in severe sickness or death.

SYSTEM COMPONENTS

The FAST® wastewater treatment system typically includes the following components:

A. Blower & Housing
B. Control Panel
C. Air Piping
D. Vent(s) and Observation Port
E. Access
F. FAST® Module
G. Tank
H. Outlet to Drain field

GENERAL LAYOUT



*PLEASE NOTE:

There may be associated equipment with your system: pumps (before and/or after the FAST® unit), distribution box, disinfection system, irrigation system, remote alarm, auto dialer, etc.

ONGOING SERVICE

⚠ WARNING

Only qualified service staff should open access ports and/or covers. Infectious organisms exist in a septic tank. If any contact with wastewater, immediately wash and disinfect all exposed areas and contact personal physician. Failure to do so could result in severe sickness or death.

⚠ CAUTION

Avoid pumping down a tank after periods of heavy rain or when the ground water is likely to be above the bottom of the concrete tank. Emptying the tank under these conditions could cause the tank to float up and become dislodged.

As the FAST® system processes the raw domestic waste (producing sludge and sloughed-off bacteria), the dead bacteria and non-biodegradable waste settle and accumulate in the bottom of the septic tank for periodic removal. The periodic removal time interval will change depending on the size of the system and varying load conditions.

TANK PUMPING PROCEDURE: As Required by Measurement of Sludge Depth

To determine the sludge depth accurately, open up the access ports/cover(s) to the primary zone (settling compartment), insert a sludge-measuring instrument, and take samples. If sludge is 18" (inches) deep or takes up 75% of the area below the port connecting settling compartment to secondary zone (which contains the FAST system), have the tank pumped out. All stricter, applicable regulations supersede these operational directions.

Also, check the sludge depth of the secondary zone. Open the access ports/cover(s) to the secondary zone and measure sludge depth. If sludge depth in the secondary zone is greater than 14" (inches), it is necessary to pump the bio-solids out.

Always pump out both zones of the system even if only one zone may require it.

1. Open the access ports/cover(s) and insert the hose. Be sure to **pump out both settling and treatment chambers** of the system.
2. Once the unit has been pumped out, **immediately refill the tank with clean water** to reduce the risk of the tank floating and to minimize the impact on treatment. Close the access ports/cover(s) making sure it is watertight.
3. **Properly dispose of the solids** in compliance with local and state regulations.

SEASONAL/INTERMITTENT USE PROPERTIES FAST® wastewater treatment system will function normally during short periods of inactivity, even if there is no wastewater flowing to the system. The power to the system should be left on during this time. Typical examples of extended periods of intermittent use and suggested operational procedures:

- **Summer use property** (shut down all winter) - blower should be turned off at end of summer and restarted upon return.
- **Weekend property** (used at least once every three weekends) - maintain normal operation or utilize FAST's SFR® blower timer feature on control panel. Consult your service provider and local regulations prior to any system changes.

Check with local regulations before attempting: If property is seldom used and blower is shut down completely for an extended period of time (i.e. summer use only), we suggest to arrange through your local service provider restarting the blower a week or two prior to returning to the property.

⚠ WARNING

Only authorized service personnel should service a septic system and its components. Deadly hazards such as lethal gases and high voltage electricity are associated with the system.

⚠ CAUTION

Introducing harmful or damaging substances into the FAST system may void the warranty.

LIMITED WARRANTY

Bio-Microbics, Inc. warrants every new residential FAST® system against defects in materials and workmanship for a period of two years after installation or three years from date of shipment, subject to the following terms and conditions, (Commercial FAST system for a period of one year after installation or eighteen months from date of shipment, whichever occurs first, subject to the following terms and conditions):

During the warranty period, if any part is defective or fails to perform as specified when operating at design conditions, and if the equipment has been installed and is being operated and maintained in accordance with the written instructions provided by Bio-Microbics, Inc., Bio-Microbics, Inc. will repair or replace at its discretion such defective parts free of charge. Defective parts must be returned by owner to Bio-Microbics, Inc.'s factory postage paid, if so requested. The cost of labor and all other expenses resulting from replacement of the defective parts and from installation of parts furnished under this warranty and regular maintenance items such as filters or bulbs shall be borne by the owner. This warranty does not cover general system misuse, aerator components which have been damaged by flooding or any components that have been disassembled by unauthorized persons, improperly installed or damaged due to altered or improper wiring or overload protection. This warranty applies only to the treatment plant and does not include any of the structure wiring, plumbing, drainage, septic tank or disposal system. Bio-Microbics, Inc. reserves the right to revise, change or modify the construction and/or design of the FAST system, or any component part or parts thereof, without incurring any obligation to make such changes or modifications in present equipment. Bio-Microbics, Inc. is not responsible for consequential or incidental damages of any nature resulting from such things as, but not limited to, defect in design, material, or workmanship, or delays in delivery, replacements or repairs.

THIS WARRANTY IS IN LIEU OF ALL OTHER WARRANTIES EXPRESS OR IMPLIED. BIO-MICROBICS SPECIFICALLY DISCLAIMS ANY IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. NO REPRESENTATIVE OR PERSON IS AUTHORIZED TO GIVE ANY OTHER WARRANTY OR TO ASSUME FOR BIO-MICROBICS, INC., ANY OTHER LIABILITY IN CONNECTION WITH THE SALE OF ITS PRODUCTS.

Keep for your Records



Module System Serial Number: _____

System Designer Name: _____

Designer Phone: _____

Health Official Name: _____

Health Official Phone: _____

Manufacturer Name: Bio-Microbics, Inc.

Manufacturer Phone: 1-800-753-FAST (3278)

Installed By: _____

Installer Phone: _____


Maintenance Provider Name: _____

Maintenance Provider Phone: _____



8450 Cole Parkway • Shawnee, KS 66227 • USA
Ph: 913-422-0707 • Fax: 913-422-0808
800-753-FAST (3278) • www.biomicrobics.com


REVISED BY: DEVLIN COLA



1 Basement Plan
3/16" = 1'-0"

note: *

ALL BEDROOM (SLEEPING ROOMS) SHALL HAVE AN EMERGENCY ESCAPE WINDOW (IRC 2012.310). THIS WINDOW SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5.7 SQ. FT. WITH A CLEAR HEIGHT OF 24 INCHES AND A CLEAR WIDTH OF 20 INCHES. THE MAXIMUM HEIGHT OF THE CLEAR OPENING FROM THE FLOOR IS 44 INCHES (IRC 2012.310).



WINDOW DETAIL

GENERAL NOTES:

1. UNLESS INDICATED OTHERWISE, DIMENSIONS ARE TO FACE OF FRAMING.
2. VERIFY ALL EXTERIOR RISER AND TREAD DIMENSIONS IN THE FIELD.
3. ALL SMOKE/CARBON MONOXIDE DETECTORS TO BE HARDWIRED TO DEDICATED CIRCUIT, INTERCONNECTED & PROVIDED WITH BATTERY BACKUP.
4. PROVIDE CARBON MONOXIDE ALARMS PER R315.1.
5. ALL STAIRS HANDRAILS AND GUARDS SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION R311 AND R312 OF THE 2012 IRC.
6. SEE FRAMING PLANS FOR COORDINATION OF POST REQUIREMENTS.
7. ALL INTERIOR PARTITIONS NOT DIMENSIONED SHALL BE 5 1/2" ANGLES ARE 90 AND OR 45 UNLESS NOTED OTHERWISE.
8. REFER TO EXTERIOR ELEVATIONS & DOOR/WINDOW SCHEDULE FOR WINDOW HEAD HEIGHTS.
10. ALL DOOR DIMENSIONS GIVEN IN FEET AND INCHES.

WALL TYPES

TYPICAL EXTERIOR WALL: 2"x6" WOOD STUDS 16" O.C. WITH R-15 OPEN CELL SPRAY FOAM INSULATION, 1/2" OSB SHEATHING, TYVEK BUILDING WRAP, AND SIDING. SEE ELEVATIONS. INTERIOR FINISH TO BE 1/2" GYP. BOARD.

TYPICAL INTERIOR WALL: 2"x4" STUDS 16" O.C. WITH 1/2" GYP. BOARD EACH SIDE.

THOMSON & COOKE ARCHITECTS

5155 MACARTHUR BLVD NW
WASHINGTON DC 20016
202-686-6583
WWW.THOMSONCOOKE.COM

Rhodes Residence
222 Donmore Drive Great Falls VA 22066

© THOMSONCOOKE ARCHITECTS

Basement Plan

10-15-2019	PRELIMINARY PRICING ISSUE
11-20-2019	PPS ADDENDUM - REV 1
03-16-2020	PERMIT SET

A100



1 First Floor Plan

note: *

ALL BEDROOM (I.E. SLEEPING ROOMS) SHALL HAVE AN EMERGENCY ESCAPE WINDOW (IRC 2012.310). THIS WINDOW SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5.7 SQ. FT WITH A CLEAR HEIGHT OF 24 INCHES AND A CLEAR WIDTH OF 20 INCHES. THE MAXIMUM HEIGHT OF THE CLEAR OPENING FROM THE FLOOR IS 44 INCHES (IRC 2012.310)



WINDOW DETAIL

GENERAL NOTES:

1. UNLESS INDICATED OTHERWISE, DIMENSIONS ARE TO FACE OF FRAMING.
2. VERIFY ALL EXTERIOR RISER AND TREAD DIMENSIONS IN THE FIELD.
3. ALL SMOKE/CARBON MONOXIDE DETECTORS TO BE HARDWIRED TO DEDICATED CIRCUIT, INTERCONNECTED & PROVIDED WITH BATTERY BACKUP.
4. PROVIDE CARBON MONOXIDE ALARMS PER §13.1.5.
5. ALL START HANDRAILS AND GUARDS SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION R312.11 AND R312.2 OF THE 2012 IRC.
6. SUBMITTING PLANS FOR COORDINATION OF POST REQUIREMENTS.
7. ALL INTERIOR PARTITIONS NOT DIMENSIONED SHALL BE 3 1/2".
8. ALL ANGLES ARE 90 AND OR 45 UNLESS NOTED OTHERWISE.
9. REPAIR EXTERIOR ELEVATORS & DOOR/WINDOW SCHEDULES FOR WINDOW HEAD HEIGHTS.
10. ALL DOOR DIMENSIONS GIVEN IN FEET AND INCHES.

WALL TYPES

TYPICAL EXTERIOR WALL: 2"x6" WOOD STUDS 16" O.C. WITH R-15 OPEN CELL SPRAY FOAM INSULATION, 1/2" OSB SHEATHING, TYVEK BUILDING WRAP, AND SIDING; SEE ELEVATIONS. INTERIOR FINISH TO BE 1/2" GYP. BOARD.

TYPICAL INTERIOR WALL: 2"x4" STUDS 16" O.C. WITH 1/2" GYP BOARD EACH SIDE.

THOMSON & COOKE ARCHITECTS

Rhodes Residence
222 Donmore Drive Great Falls VA 22066

3155 MACARTHUR BLVD NW
WASHINGTON DC 20016
202.686.6583
WWW.THOMSONCOOKE.COM


First Floor Plan

10-15-2019	PRELIMINARY PRICING ISSU
11-20-2019	PPS ADDENDUM - REV 1
03-16-2020	PERMIT SET

A101




1 Second Floor Plan
3/16" = 1'-0"



note: *

ALL BEDROOM (E.E. SLEEPING ROOMS) SHALL HAVE AN EMERGENCY ESCAPE WINDOW (IRC 2012, 310). THIS WINDOW SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5.7 SQ. FT. WITH A CLEAR HEIGHT OF 24 INCHES AND A CLEAR WIDTH OF 20 INCHES. THE MAXIMUM HEIGHT OF THE CLEAR OPENING FROM THE FLOOR IS 44 INCHES (IRC 2012, 310).



WINDOW DETAIL

GENERAL NOTES:

1. UNLESS INDICATED OTHERWISE, DIMENSIONS ARE TO FACE OF FRAMING.
2. VERIFY ALL EXTERIOR RISER AND TREAD DIMENSIONS IN THE FIELD.
3. ALL SMOKE/CARBON MONOXIDE DETECTORS TO BE HARDWIRED TO DEDICATED CIRCUIT, INTERCONNECTED & PROVIDED WITH BATTERY BACKUP.
4. PROVIDE CARBON MONOXIDE ALARMS PER R315.1.
5. ALL STAIRS HANDRAILS AND GUARDS SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION R311 AND R312 OF THE 2012 IRC.
6. SEE FRAMING PLANS FOR COORDINATION OF POST REQUIREMENTS.
7. ALL INTERIOR PARTITIONS NOT DIMENSIONED SHALL BE 3/4" TYP.
8. ALL ANGLES ARE 90 AND OR 45 UNLESS NOTED OTHERWISE.
9. REFER TO EXTERIOR ELEVATIONS & DOOR/WINDOW SCHEDULE FOR WINDOW HEAD HEIGHTS.
10. ALL DOOR DIMENSIONS GIVEN IN FEET AND INCHES.

WALL TYPES

TYPICAL EXTERIOR WALL: 2"x6" WOOD STUDS 16" O.C. WITH R-15 OPEN CELL SPRAY FOAM INSULATION, 1/2" OSB SHEATHING, TYVEK BUILDING WRAP, AND SIDING; SEE ELEVATIONS. INTERIOR FINISH TO BE 1/2" GYP. BOARD.

TYPICAL INTERIOR WALL: 2"x4" STUDS 16" O.C. WITH 1/2" GYP BOARD EACH SIDE.

THOMSON & COOKE ARCHITECTS


5155 MACARTHUR BLVD NW
WASHINGTON DC 20016
202.686.6583
WWW.THOMSONCOOKE.COM

Rhodes Residence
222 Donmore Drive Great Falls VA 22066


Second Floor
Plan

10-15-2019	PRELIMINARY PRICING ISSUE
11-20-2019	PPS ADDENDUM - REV 1
03-16-2020	PERMIT SET


A102




1 Shed Foundation Plan
1/4" = 1'-0"




2 Shed 1st Floor Plan
1/4" = 1'-0"




3 Roof Plan
1/4" = 1'-0"




4 Shed Front Elevation
1/4" = 1'-0"




5 Shed Left Elevation
1/4" = 1'-0"



8 Shed Section 1
1/4" = 1'-0"



6 Shed Rear Elevation
1/4" = 1'-0"



7 Shed Right Elevation
1/4" = 1'-0"

THOMSON & COOKE ARCHITECTS


5155 MACARTHUR BLVD NW
WASHINGTON DC 20016
202.686.6583
WWW.THOMSONCOOKE.COM

Rhodes Residence
222 Donmore Drive Great Falls VA 22066


Shed Plans & Elevations

10-15-2019	PRELIMINARY PRICING ISSUE
11-20-2019	PPS ADDENDUM - REV 1
03-16-2020	PERMIT SET

A104



1 Front Elevation
3/16" = 1'-0"



2 Right Elevation
3/16" = 1'-0"

THOMSON & COOKE ARCHITECTS

5155 MACARTHUR BLVD NW
WASHINGTON DC 20016
202.686.6583
WWW.THOMSONCOOKE.COM


Rhodes Residence
222 Donmore Drive Great Falls VA 22066

© THOMSON & COOKE ARCHITECTS


Exterior
Elevations

10-15-2019	PRELIMINARY PRICING ISSUE
11-20-2019	PPS ADDENDUM - REV 1
03-16-2020	PERMIT SET

A200



1 Building Section 1
3/16" = 1'-0"



2 Building Section 2
3/16" = 1'-0"

NOTE:
SEE TABLE 1 ON SHEET 0001 FOR ALL INSULATION AND U-FACTORS FOR MATERIALS AND LOCATIONS TO BE INSTALLED.
SEE TABLE 2 ON SHEET 0002 FOR ALL FENESTRATION U-FACTORS FOR ALL GLAZING FOR EACH WINDOW AND DOOR TO BE INSTALLED.

THOMSON & COOKE ARCHITECTS

5155 MACARTHUR BLVD NW
WASHINGTON DC 20016
202.686.6583
WWW.THOMSONCOOKE.COM

Rhodes Residence
222 Donmore Drive Great Falls VA 22066

© THOMSONCOOKE ARCHITECTS

Building Sections	
10-15-2019	PRELIMINARY PRICING ISSUE
11-20-2019	PPS ADDENDUM - REV 1
03-16-2020	PERMIT SET

A202

WELL Only OSE/PE/WWSP Report For:

☒ Well Construction Permit☐ Well Repair Permit☐ Well Abandonment Permit☐ Well Modification Permit

Property Location:

911 Address 222 DONMORE DRIVE City GREAT FALLS VA 22064
 Lot 44A Section Subdivision SENECA FARMS
 GPIN or Tax Map # 0022020044A Health Department ID #
 Latitude Longitude

Applicant or Client Mailing Address

Name NORTHERN VIRGINIA DRILLING INC.
 Address 11356 INDUSTRIAL ROAD
 City MANASSAS State VA Zip Code 20109

Prepared by: OSE ☐ PE ☐ WWSP ☒
 Name SCOTT MILLER License # 2719000339
 Address 11356 INDUSTRIAL ROAD
 City MANASSAS State VA Zip Code 20109

Date of Submission Date Revision 1
 OSE/PE/WWSP Job ID Date Revision 2

List of attachments (e.g., Private Well Worksheet, Construction Drawings, Abandonment Worksheet, etc.)

DRILLING 5 GEOTHERMAL WELLS
400FT EACH CLOSED LOOP
GROUT FROM BOTTOM TO TOP

Certification Statement

I hereby certify that the evaluations and/or designs as submitted comply with the applicable provisions of the Private Well Regulations (12 VAC5-630-10 et seq.) and all other applicable laws and regulations enforced by the Virginia Department of Health. I further certify that I currently possess the professional license required to perform work evidenced by the application by the laws of the Commonwealth as promulgated by the supervising agency.

I recommend that a (select one): Construction permit ☒Repair permit ☐be (select one) Issued ☐Modification permit ☐Abandonment permit ☐Denied ☐2/22/21
OSE/PE/WWSP Signature

Date

2/10/2021APPROVED
FAIRFAX COUNTY HEALTH DEPARTMENT

HEALTH DEPARTMENT COPY

Well Specifications

VDH Use Only

HDIN:

Applicant Information

Name: NORTHERN VA DRILLING INC Address: 11556 INDUSTRIAL ROAD
 Phone: 703-361-6859 703-303-4601 MANASSAS VA 20109

Location Information

Tax Map/GPIN #: 0022 02 0044A Property Address: 222 DOWNHILL DRIVE
GREAT FALLS VA 22066
 Subdivision: SENECA FARMS Section: 3 Block: 22066 Lot: 44A
 Directions: SEE ATTACHMENTS


General Information

Well Purpose (select all that apply): ☐ Domestic Drinking Water ☐ Agricultural
☐ Irrigation ☐ Industrial/Commercial ☒ Geothermal
 Well Class: 4 Minimum Casing Depth: NA ft.
 Estimated Water Usage: _____ Minimum Grout Depth: 400 ft.

Horizontal Setbacks

Distance from Building Sewer: 5 ft. Distance from Pretreatment Unit(s): 20 FT ft.
 Distance from Conveyance System: 68 ft. Distance from Absorption Area: 254 ft.
 Distance from Property Line: 140 ft. Distance from foundations: 20 FT ft.
 Distance from other source(s) of contamination: 220 FT ft.
 List other source(s): HOUSE ACROSS ST


Note: DRILLING 5 GEOTHERMAL WELLS 400 FT EACH
GROUT FROM BOTTOM TO TOP



Construction Drawings - Well Only

Property ID: 0022 02 0044 A

SEE ATTACHMENT



Schematic drawing of private well and topographic features. Show the lot lines of the building lot and building site, sketch of property showing any topographic features which may impact on the design of the well, all existing and/or proposed structures including sewage disposal systems and wells (actual and permitted) within 200 feet of the well area. The scale drawing of all sewage disposal systems shall show sewer lines, pretreatment unit, pump station, conveyance system, and subsurface soil absorption system, reserve area, etc.

ALTERNATIVE TRENCH SEWAGE DISPOSAL SYSTEM DESIGN WITH PUMP SYSTEM

PROPERTY ID: 222 DONMORE DRIVE, GREAT FALLS, VA 22066
TAX MAP ID: 2-2-02-044A
SUBDIVISION NAME: SENECA FARMS, LOT 44A

CLIENT: JOHN RHODES TR
74 S PLAYER CREST CIR
SPRING, TX 77382

GENERAL NOTES

BOUNDARY, TOPOGRAPHY, AND SITE GRADING PLAN INFORMATION HEREON TAKEN FROM CIVIL SPUR.

SEWAGE SYSTEM DEPTH, LAYOUT, AND SOILS LOADING RATE PRESCRIBED BY SOILS INC. SOILS WORK PERFORMED BY SOILS INC.

ANY CHANGES TO THIS PERMIT MUST BE APPROVED BY THE SYSTEM DESIGNER.

INSPECTION(S) BY THE SEWAGE SYSTEM DESIGNER AND HEALTH DEPARTMENT ARE REQUIRED. IT IS THE SEPTIC CONTRACTOR'S RESPONSIBILITY TO CALL THE DESIGNER AND HEALTH DEPARTMENT TO ARRANGE FOR ALL INSPECTIONS.

THIS PLAN IS TO BE USED IN CONJUNCTION WITH THE APPROVED PERMIT ONLY. IT IS THE OWNER'S/INSTALLER'S RESPONSIBILITY TO VERIFY THAT THIS PLAN IS PART OF THE APPROVED HEALTH DEPARTMENT PERMIT.

SHOULD WATER CONDITIONERS BE USED IN THE DWELLING, THE BACKWASH MUST NOT BE PLUMBED INTO THE SEWER LINE OR OTHERWISE PERMITTED TO ENTER THE SEPTIC TANK AND/OR PUMP STATION.

THE SEWAGE SYSTEM CONTRACTOR INSTALLING THIS SYSTEM MUST HOLD THE REQUIRED SEWAGE DISPOSAL CONSTRUCTION INSTALLATION AND REPAIR LICENSE THROUGH DPOR. THE SEWAGE SYSTEM INSTALLATION CONTRACTOR MUST BE CERTIFIED BY THE AND APPROVED THROUGH THE SYSTEM MANUFACTURER FOR INSTALLATION OF THEIR PRODUCT.

PRIOR TO INSTALLATION OF THE SYSTEM, A PRE-CONSTRUCTION MEETING AT THE SITE WITH THE SEWAGE SYSTEM CONTRACTOR AND THE SYSTEM DESIGNER IS REQUIRED.

NO PORTION OF THE SEWAGE ABSORPTION AREA MAY BE INSTALLED IN WET WEATHER OR IN WET SOIL CONDITIONS.

CONTROL PANEL NOTE

AN AMERICAN MANUFACTURING CONTROL PANEL IS TO BE LOCATED OUTSIDE THE HOUSE, WITHIN DIRECT LINE OF SITE OF THE PUMP CHAMBER. THE CONTROL PANEL MUST COMPLY WITH LOCAL REQUIREMENTS. THERE MUST BE INDIVIDUAL CIRCUITS FOR THE PILOT, ALARM AND PUMP. BOTH AUDIO AND VISUAL ALARMS SHALL BE PLACED IN A CONSPICUOUS LOCATION AS SHOWN ON THE PLANS-WITHIN DIRECT SIGHT OF THE PUMP STATION. A REMOTE ALARM, AMERICAN MANUFACTURING MODEL A1-A OR EQUIVALENT, SHALL BE PLACED INSIDE THE HOUSE.

DESIGN CRITERIA

NUMBER OF BEDROOMS: 5
PEAK DESIGN FLOW: 750 GPD
AVERAGE DAILY FLOW: 450-525 GPD
ACTIVE AREA DESIGN PERC RATE: 40 MPI @ 20"
ACTIVE AREA SOIL LOADING RATE: 1.25 GPD/FT²
ACTIVE AREA DESIGN LOADING RATE: 1.25 GPD/FT²
ACTIVE AREA SEWAGE TREATMENT LEVEL: TL3

DESIGN CRITERIA, CONT'D

ACTIVE PERCOLATION AREA PROVIDED: 5 LINES, 75' LONG, 2' WIDE & 6' ON CENTER, ON CONTOUR
ACTIVE AREA INSTALLATION DEPTH: 20"
RESERVE AREA SOIL EFFLUENT LOADING RATE: 0.33 GPD/FT²
RESERVE AREA PERCOLATION RATE: 50 MPI @ 12"
RESERVE PERCOLATION AREA PROVIDED: DRIP SYSTEM 48.5' (AVG) x 47'.
RESERVE AREA INSTALLATION DEPTH: 62"
RESERVE AREA SEWAGE TREATMENT LEVEL: TL3

DRAINFIELD CALCULATIONS:

LENGTH OF THE TRENCH PROVIDED = 5 x 75' = 375 LF.
375 LF X 2 FT TRENCH = 750 SF TREATMENT AREA PROVIDED.
MIN OF 600 SF REQUIRED. 750 SF PROVIDED > 600 SF. REQUIRED
TL-3 TREATMENT
LOADING RATE OF 1.25 GAL/FT²/DAY.
SPACING = 6 FT O.C.
WIDTH OF TRENCH = 2.0'
GROSS FLOOR AREA ≥ 7,500 SF; PER ARCHITECTURAL PLANS
BASEMENT = WALKOUT

WATER SERVICE

THE PROPERTY IS TO BE SERVED BY THE NEW CLASS IIIB PRIVATE WELL (SEE SEPARATE WELL DESIGN PKG FOR FURTHER INFO).

NITROGEN COMPLIANCE NOTE

THIS SEWAGE TREATMENT AND DISPOSAL SYSTEM UTILIZES A VA DEPARTMENT OF HEALTH RECOGNIZED NSF STANDARD 245 APPROVED AEROBIC TREATMENT UNIT AND IS THEREFORE DEEMED TO COMPLY WITH 12VAC5-613-90.D

WATER LINE/MAIN NOTES

REFERENCE: 12VAC5-590-1150 (B & C)

1. UNDER NORMAL CONDITIONS WATER MAINS SHALL BE LAID AT LEAST 10 FEET HORIZONTALLY FROM A SEWER LINE.
2. UNDER NORMAL CONDITIONS WATER LINES CROSSING SEWERS SHALL BE LAID TO PROVIDE A SEPARATION OF AT LEAST 18 INCHES BETWEEN THE BOTTOM OF THE WATER LINE & THE TOP OF THE SEWER LINE WHENEVER POSSIBLE

COUNTY OF FAIRFAX


MAR 26 2020

(Handwritten signature)

APPROVED
FAIRFAX COUNTY HEALTH DEPARTMENT

4.7.20
Date

(Handwritten signature)
Health Official



SOILS INC.

8399 WEST MAIN ST, MARSHALL, VA 20115
P.844.447.SOIL (7645) F.540.364.2060

PROJECT: 222 DONMORE DRIVE
DATE: 03/25/2020 JOB NO. T1812
PAGE: 1 OF 8
SCALE: NTS
GPIN OR TM #: 2-2-02-0044A
COUNTY/STATE: FAIRFAX COUNTY, VA

1. ALL CONSTRUCTION MATERIALS AND METHODS MUST CONFORM TO APPLICABLE LOCAL CODES AND STATE REGULATIONS.
2. ALL PIPE JOINTS SHALL BE PRIMED AND CHEMICALLY SEALED.
3. ANY DEVIATION FROM THIS DESIGN MUST BE APPROVED BY THE DESIGNER PRIOR TO INSTALLATION OF THE SYSTEM.
4. ELECTRICAL WIRING TO BE INSTALLED UNDER THE DIRECT SUPERVISION OF OF A LICENSED ELECTRICAL CONTRACTOR, ACCORDING TO NEC, STATE & LOCAL ELECTRICAL CODES AS APPLICABLE.
5. CONTRACTOR IS TO INSTALL CONCRETE TANKS ON UNIFORMLY FIRM AND STABLE COMPACTED GROUND, CRUSHED STONE IS RECOMMENDED TO PROVIDE UNIFORM SUPPORT TO THE TANK BOTTOMS.
6. SEPTIC TANK MUST BE WATERTIGHT AND CONFORM TO APPLICABLE STATE & LOCAL CODES & REQUIREMENTS.
7. CONTRACTOR MUST NOTIFY "MISS UTILITY" AND HAVE A CLEARED TICKET PRIOR TO STARTING EXCAVATION AT THE SITE.
8. CONTRACTOR IS RESPONSIBLE FOR ANY REQUIRED AMOUNT OF IMPORTED FILL (IN PLACE).

1. REFER TO SITE DRAWINGS AND NOTES FOR SPECIAL REQUIREMENTS.
2. MACHINERY SHOULD AVOID THE PERCOLATION AREA.
3. MACHINERY MUST NEVER TRAVERSE THE EXCAVATED OR EXPOSED PERCOLATION AREA.
4. IF WOODED, SPECIAL CARE MUST BE TAKEN IN CLEARING THE DRAINFIELD AREA.
5. CONTRACTOR MUST PROVIDE ADEQUATE ACCESS FOR CORRECT INSTALLATION.
6. THE SEWAGE SYSTEM MUST BE INSTALLED DURING DRY CONDITIONS.

1. INSTALL THE ABSORPTION AREA ON CONTOUR UNLESS THERE IS A GRADE CUT SPECIFIED ON THE DRAWINGS OR IN THE NOTES PROVIDED IN THIS DESIGN PACKAGE.
2. DO NOT SMEAR OR COMPACT THE PERCOLATION AREA DURING EXCAVATION.

1. MINIMUM BACKFILL COVER OVER THE AGGREGATE IS 12".
2. MAXIMUM BACKFILL COVER OVER THE AGGREGATE IS 20".
3. BACKFILL WITH SUITABLE LOOSE MATERIAL (SANDY LOAM TO SANDY CLAY LOAM) FREE OF LARGE OR DAMAGING OBJECTS. SEED AND STRAW BACKFILLED OR DISTURBED AREAS (OR PLACE SOD WHEN REQUIRED).
4. PROVIDE EROSION PROTECTION FOR BACKFILL MATERIAL IN ACCORDANCE WITH STATE & LOCAL STANDARDS AND MAINTAIN UNTIL PERMANENT PROTECTION IS ESTABLISHED.
5. BACKFILL SHOULD BE GRADED TO PREVENT INFILTRATION OF SURFACE WATER AND DIVERT SURFACE WATER RUN OFF AWAY FROM THE SYSTEM COMPONENTS.
6. DO NOT GRADE WITHIN 20' OF THE PROPOSED SYSTEM DISPOSAL AREA(S).
7. KEEP DRIVEWAY A MINIMUM OF 10' FROM THE SEPTIC SYSTEM AND ITS COMPONENTS.
8. ALL UTILITIES TO BE $\geq 10'$ TO THE SEWAGE SYSTEM.
9. ALL DF COMPONENTS TO BE A MINIMUM OF 10' FROM THE PROPERTY LINES, 10' FROM WALKOUT BASEMENT FOUNDATION AND 20' FROM PORTIONS OF FOUNDATION THAT ARE BURIED.



[A] 138.6' SCH40 PVC SEWER LINE @
 AT 1.68%
 [B] 109.5' SCH40 PVC SEWER LINE @
 INSTALL AT 2-4%
 [C] BIOMICROBICS 0.75 MICROFAST ATU
 (DROP IN) UNIT IN HANOVER
 PRECAST 1500 GAL TANK
 IN=348.67
 OUT=348.54
 FG=352.0


- D HANOVER PRECAST 2000 GAL TJ
 PUMP TANK W/ RISER FOR
 SAMPLING
 IN=348.44
 OUT=348.27
 FG=352.0
 E 2" SCH40 PVC FORCE MAIN-242.9'
 F 6-PORT CONCRETE SURGE BOX
 WITH SANITARY "T"
 G 10-PORT CONCRETE
 DISTRIBUTION BOX
 H 6" PVC SLEEVE UNDER
 DRIVEWAY-63.4'




SOILS INC.

8399 WEST MAIN ST, MARSHALL, VA 20115
P.844.447.SOIL (7645) F.540.364.2060

PROJECT: 222 DONMORE DRIVE	
DATE: 03/25/2020	JOB NO. T1812
PAGE: 2 OF 8	
SCALE: 1"=40'	
GPIN OR TM #: 2-2-02-0044A	
COUNTY/STATE: FAIRFAX COUNTY, VA	




**BIOMICROBICS MICROFAST 0.75 UNIT
WITH DROP IN UNIT IN A HANOVER
PRECAST 1,500 GALLON TOP SEAM TANK**



- HEADER LINES ARE TO BE CONSTRUCTED AS FOLLOWS:
- INVERT OF HEADER LINES MUST BE 1' ABOVE GRAVEL IN THE TRENCHES.
 - HEADER LINES ARE TO BE BEDDED & COVERED IN STONE DUST.
 - NO MACHINERY MAY TRAVERSE OVER THE DRAINFIELD OR HEADER LINE AREA.
 - SITE MUST BE HAND CLEARED AND STUMPS GROUND IN PLACE.
 - USE 4" SCH40 PVC SMOOTH BORE PIPE FOR HEADER LINES.
 - BACKFILL 12" OVER HEADER LINES.
 - BACKFILL MIN. 6" OVER DRAINFIELD AREA AND GRADE APPROPRIATELY TO SHED WATER AWAY FROM DRAINFIELD & PROVIDE MIN. 12" OF COVER AS REQ'D

Gallons	INSIDE DIMENSIONS (Inches)			Gal/Inch.	Manufacturer
	Length	Width	Liq. depth		
2,000	144.0	72.0	56	36.4	HANOVER 2,000(TJ)



**HANOVER PRECAST
2,000 GALLON TOP SEAM PUMP TANK
WITH POLY RISER OVER INLET PORT FOR SAMPLING
36.36 GPI, 48" MAX BACKFILL DEPTH**

PUMP STATION CONTROL NOTE:

PER FAIRFAX COUNTY REQUIREMENTS, THE PEAK ENABLER FLOAT MUST FUNCTION TO "INCREASE THE DOSING FREQUENCY (NUMBER OF DOSING CYCLES) BY 1.25 TIMES THE INITIAL SETTING WHILE MAINTAINING THE SET VOLUME PER CYCLE, UNTIL THE LEVEL IN THE PUMP CHAMBER IS REDUCED TO NORMAL". THE HIGH LEVEL ALARM/LAG PUMP ENABLER "CONTINUES THE DOSING FREQUENCY WHILE MAINTAINING THE SET VOLUME PER CYCLE, UNTIL THE LEVEL IN THE PUMP CHAMBER IS REDUCED TO NORMAL".

SOILS INC.
8399 WEST MAIN ST, MARSHALL, VA 20115
P.844.447.SOIL (7645) F.540.364.2060

PROJECT: 222 DONMORE DRIVE	
DATE: 03/25/2020	JOB NO. T1812
PAGE: 4 OF 8	
SCALE: NTS	
GPIN OR TM #: 2-2-02-0044A	
COUNTY/STATE: FAIRFAX COUNTY, VA	


FAIRFAX COUNTY DIVISION OF ENVIRONMENTAL HEALTH SEWAGE EFFLUENT PUMP CALCULATIONS

Plans prepared by: SOILS INC. Permit Holders Name: John Rhodes
Address: 8399 W. MAIN STREET Property Address: 222 Donmore Drive, Great Falls, VA 22066
MARSHALL, VA 20115
Phone: 540-364-1122 Subdivision:
Date: 3/25/2020 No. of Bedrooms: 5 Tax Map I.D. 2-2-02-0044A

- 1 750 Peak Design Flow
- 2 450 Average Daily Flow (60% of Peak Design Flow)
- 3 112.5 number of gallons to be pumped each cycle
- 4 2000 Pump Chamber Size (gallons)
- 5 36.40 Gallons per Inch in Pump Chamber
- 6 3.09 Inches of Drawdown per Cycle.
- 7 488.0 Gallons Storage Above the Alarm (1/4 of Maximum Daily Flow Required)
- 8 10.50 Static Head (feet)
- 9 2 PVC Force Main Diameter (2" Minimum)
- 10 243 Length of Force Main (feet)
- 11 373 Equivalent Length of Force Main (feet)
- 12 23.24 Total Dynamic Head (TDH) @ of 40 g.p.m. (feet)
- 13 61.48 Total Dynamic Head (TDH) @ of 80 g.p.m. (feet)
- 14 32 Expected Pump Flow Rate (g.p.m.)
- 15 210 Expected Pump Run Time (seconds)

16 Recommended pump: #1 Manufacturer ZOELLER Model # N98
32 g.p.m. at 18.8 feet TDH.
115 Volts 1 phase 1/2 horsepower
17 Recommended Control Panel: Model: American Manufacturing Model # DEPRAB124ACJLOP(C)R(1)
115 Volts 1 phase
18 Pump Run Time: 3 minutes 30 seconds at system head
19 Pump "Off" Time: 5 hours 57 minutes
20 Peak Pump "Off" Time: 4 hours 47 minutes

SAMPLE PORT DETAIL



TDH CALCULATION FOR SYSTEM CURVE

Assumes: $f = 0.022$ for 2 inches pipe for typical operating range.
Static head in feet = 10.5 Measured/Estimated.
Friction headloss $h_f = (f \cdot L \cdot V^2) / (2 \cdot g \cdot D)$ = $(2.257 \times 10^{-5}) \cdot L \cdot Q^2$ (Q in gpm, L in feet)

The total equivalent pipe length = 373

TDH CALCULATIONS

Q (gpm)	L (feet)	h_{static} (feet)	h_f (feet)	TDH
0	373	10.5	0.00	10.50
10	373	10.5	0.80	11.30
20	373	10.5	3.19	13.69
30	373	10.5	7.17	17.67
40	373	10.5	12.74	23.24
50	373	10.5	19.91	30.41
60	373	10.5	28.68	39.18
70	373	10.5	39.03	49.53
80	373	10.5	50.98	61.48

EQUIVALENT LENGTH CALCULATION


Elements	2" eq. Length	Number	Eq. Length
Length (includes modules' length)	243	1	243
Reg. 90 deg	9	4	36
Reg. 45 deg	4	3	12
T-Diversion	11	1	11
Coupling (disconnected)	2	0	0
Check Valve	17	1	17
Ball Valve	54	1	54
2" Manifold (8')	12	0	0
Total Length			373

PROGRAMMABLE TIMER SETTINGS

Anticipated Pump Rate	32 gpm	From system Vs pump curve for selected pump.
Treatment Design Flow	450 gpd	From design flow from facility.
Re-circulation Volume	0 gpd	As applicable (1:1 recirc ratio will add a volume equal to that of design flow.
Drainback Volume per Dose	0 gal.	Typically 2 hrs. for single pass and 1 hr.
Dosing Interval (Pump Rate Time)	6 hrs.	for 1:1 recirculation.
Number of Doses	4 /day	
Drainback Volume per Day	0 gpd	
Pump Design Flow	450 gpd	Treatment plus Recirc. Plus Drainback.
Approx. Volume per Dose	112.5 gal.	
Pump Run Time per Dose (Min.)	3.5 min	
Pump Run Time per Dose (Sec.)	210 sec.	
Tank Volume (gal per inch)	36.4 gal/inch	From manufacturer's data.
Draw Down per Dose	3.09 inch	Prior to drainback.

DIMENSIONS OF SEPTIC TANK

Volume	Length(in)	Width(in)	Liquid Depth(in)	Free Board	Remarks
1,500	144.0	73.0	61.0	12"	MICROFAST 0.75 (Harver T3)



"QUALITY PUMPS SINCE 1939"

Product information presented here reflects conditions at time of publication. Consult factory regarding discrepancies or inconsistencies.



MAIL TO: P.O. BOX 16347 • Louisville, KY 40266-0347
SHIP TO: 3649 Cane Run Road • Louisville, KY 40211-1961
(502) 778-2731 • 1 (800) 928-PUMP • FAX (502) 774-3624

visit our web site:
www.zoeller.com

SECTION: 2.20.035
FM0973
0312
Supersedes
0310

COMPARE THESE FEATURES

- Non-clogging engineered plastic vortex impeller design
- Corrosion resistant powder coated epoxy finish
- Durable cast construction. Cast switch case, motor, pump housing and base. No sheet metal parts to rust or corrode.
- Castings - All cast iron class 25-30 25000# tensile strength
- Stainless steel screws, guard, handle, arm and seal assembly
- Float operated submersible (NEMA 6) 2-pole mechanical switch
- Motor - Permanent split capacitor, 60 Hz, 1725 RPM, oil-filled, hermetically sealed, automatic reset thermal overload protection
- Bearings - Upper & lower oil fed cast iron
- Carbon and ceramic shaft seal
- Entire unit pressure tested after assembly.
- Watertight neoprene "O" ring between motor and pump housing
- Maximum temperature for effluent or dewatering 130°F - 54°C
- Passes 1/2 inch spherical solids
- No screens to clog
- Standard cord length 15 ft. (UL Listed)
- 1 1/2" NPT Discharge (1 1/2" X 2" PVC Adapter included with BN & BE Models)
- On point - 9 1/2"
- Off point - 3"
- Major width - 10 1/8"
- Height - 12"

SIMPLEX AND DUPLEX SYSTEMS AVAILABLE

PACKAGED SYSTEMS AVAILABLE

Note: The sizing of effluent systems normally requires variable level float(s) controls and properly sized basins to achieve required pumping cycles or dosing timers with nonautomatic pumps.

98 Cast Iron Series

"FLOW-MATE"

(FOR PUMP PREFIX IDENTIFICATION SEE NEWS & VIEWS 0052)

FOR SEPTIC TANK
LOW PRESSURE PIPE (LPP)
AND ENHANCED FLOW STEP SYSTEMS

EFFLUENT OR DEWATERING PUMP

SUBMERSIBLE
1 1/2" NPT DISCHARGE

MODEL 98

MODEL BN98

POWDER COATED TOUGH

50 YEARS

UL

SP

Tested to UL Standard UL 778 and Certified to CSA Standard C22.2 No. 108

MODELS AVAILABLE

- Automatic or Nonautomatic
- 1/2 HP, 1 Ph., 115V or 230V
- Available with Piggyback Variable Level Float Switch.

© Copyright 2012 Zoeller Co. All rights reserved.

SOILS INC.

8399 WEST MAIN ST, MARSHALL, VA 20115
P.844.447.SOIL (7645) F.540.364.2060

PROJECT: 222 DONMORE DRIVE
DATE: 03/25/2020 JOB NO. T1812
PAGE: 5 OF 8
SCALE: NTS
GPIN OR TM #: 2-2-02-0044A
COUNTY/STATE: FAIRFAX COUNTY, VA

Specifications For MicroFAST 0.75 Wastewater Treatment System

1. GENERAL

The contractor shall furnish and install (1) MicroFAST 0.75 treatment system as manufactured by Bio-Microbics, Inc. The treatment system shall be complete with all needed equipment as shown on the drawings and specified herein.

The principal items of equipment shall include FAST System insert, insert lid (or leg extensions if that option is chosen), blower assembly, blower controls and alarms. The MicroFAST 0.75 unit shall be situated within a 1,500 gallon minimum compartment in a two compartment tank as shown on the plans. Tank(s) must conform to local, state, and all other applicable codes. The contractor shall provide coordination between the FAST system and tank supplier with regard to fabrication of the tank, installation of the FAST unit and delivery to the job site.

2. OPERATING CONDITIONS

The MicroFAST 0.75 treatment system shall be capable of treating the wastewater produced by typical family activities (bath, laundry, kitchen, etc.) ranging from (1) one to (10) ten persons and not to exceed 750 US Gallons per day (2842.5 LPD).

3. MEDIA

The FAST media shall be manufactured of rigid PVC, polyethylene or polypropylene and it shall be supported by the polyethylene insert. The media shall be fixed in position and contain no moving or wearing parts and shall not corrode. The media shall be designed and installed to ensure that sloughed solids immediately descend through the media to the bottom of the septic tank.

4. BLOWER

The MicroFAST 0.75 unit shall come equipped with a regenerative type blower capable of delivering 17-25 CFM. The blower assembly shall include an inlet filter with metal filter element.

5. REMOTE MOUNTED BLOWER

The blower may be mounted remote with no more than 100 ft (30.5 M) of piping and no more than four elbows, from the MicroFAST unit on a contractor supplied concrete base. The blower must not set in standing water and its elevation must be higher than the normal flood level. A two-piece, rectangular housing shall be provided with tamper-proof screws. The discharge air line from the blower to the MicroFAST shall be provided and installed by the contractor.

6. ELECTRICAL

The electrical source should be within 150 feet of the blower. Consult local code for longer wiring distances. All wiring must conform to code. The input power required for the blower is 115/230 Volts, Single Phase, 60/50 Hertz, 3.8/1.9 Full Load Amps, minimum wire size is 16 A.W.G. (Locked Rotor Amps are 18.6/9.3). All conduit and wiring between the electrical control panel (optional), the power supply, and the blower shall be furnished and installed by the contractor.

7. ALARMS

The alarm system shall consist of a visual and audible alarm to indicate loss of power to the blower and/or high water level. A manual silence switch is included.

8. INSTALLATION AND OPERATING INSTRUCTIONS

All work must be done in accordance with local codes and regulations. Installation of the MicroFAST 0.75 shall be done in accordance with the written instructions provided by the manufacturer. No more than four foot of fill may be placed over the FAST lid. Operation manuals shall be furnished which will include a description of installation, operation, and system maintenance procedures. There shall be a separate manual for the installer, service provider, and owner, tailored to each.

9. WARRANTY

The manufacturer of the MicroFAST 0.75 treatment system shall warrant for three years from the date of shipment or two years from the date of start-up, whichever occurs first, that the equipment they provide will be free from defects in material and workmanship.

In the event a mechanical component fails to perform as specified or is proven defective in service during the warranty period, the manufacturer shall repair or replace such defective parts. (Cost of labor on repair/replacement is not covered under this warranty.) The replacement or repair of those items normally consumed in service such as air filter, etc., shall be considered as part of routine maintenance and upkeep.

It is not intended that the manufacturer assume responsibility for contingent liabilities or consequential damages of any nature resulting from defects in design, material or workmanship, or delays in delivery, replacement, or otherwise.

9. FLOW AND DOSING

Wastewater treatment systems work best when influent flow is delivered as consistently as possible. FAST systems have been successfully designed, tested and certified relieving gravity, demand-based influent flow. However when influent flow is controlled (either by pump or other means) to the FAST system to help with highly variable flow conditions, then multiple feeding events should be used to help assure even flow, optimum performance, and reliability.

IN THE INTEREST OF TECHNOLOGICAL PROGRESS, ALL PRODUCTS ARE SUBJECT TO DESIGN AND/OR MATERIAL CHANGE WITHOUT NOTICE.

Date 01-03-05

BIO-MICROBICS
INCORPORATED
1-800-753-FAST (3278)

© Bio-Microbics, Inc. 2003

THE DESIGN AND DETAIL OF THIS DRAWING IS THE PROPERTY OF BIO-MICROBICS, INC. AND IS NOT TO BE USED EXCEPT IN CONNECTION WITH OUR WORK. DESIGN AND INVENTION RIGHTS ARE RESERVED. DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.


MicroFAST®0.75

Drawn by BMI

PROJECT: 222 DONMORE DRIVE
DATE: 03/25/2020 JOB NO: T1812
PAGE: 6 OF 8
SCALE: NTS
GPIN OR TM #: 2-2-02-0044A
COUNTY/STATE: FAIRFAX COUNTY, VA


SOILS INC.

8399 WEST MAIN ST, MARSHALL, VA 20115
P. 844.447.SOIL (7645) F. 540.364.2060



Opening for FAST®
module to sit on tank


PLAN VIEW



AIR SUPPLY
OPTIONS

NOTES (SEE NOTE 5)

1. Airline piping to FAST® may not exceed 100 FT [30m] total length and have a maximum of 4 elbows in the piping system. For distances greater than 100 FT [30m] consult factory. Blower must be located above flood levels on a concrete base 26" X 20" X 2" [65 X 50 X 5cm] min.
2. Vent to desired location and cover opening with a vent grate with at least 7 sq in. [45 sq. cm] open surface area. Secure with stainless steel screws. Vent piping must not allow condensate build up or create back pressure. Vent must be above finished grade or higher (see sheet 4 of 4).
3. All appurtenances to FAST® (e.g. tanks, access ports, electrical, etc.) must conform to all applicable country, state, province, and local plumbing and electrical codes. Pump out access shall be adequate to thoroughly clean out both zones.
4. All inspection, viewing and pump out ports must be secured to prevent accidental or unauthorized access.
5. Tank, piping, conduit, etc. are provided by others. Blower control system by Bio-Microbics, Inc. See Installation Manual.
6. If less than the specified minimums are considered necessary, consult factory for guidance.
7. All piping and ancillary equipment installed after FAST must not impede or restrict free flow of effluent.
8. The tank(s) shall be designed to prevent air passage between the settling zone/tank and the treatment zone and preventing an air lock. Examples include a baffle wall sealed to the lid or treatment zone inlet line with a pipe cap. Consult factory for guidance.
9. Installations using a FAST® system lid are capable of withstanding AASHTO H-10 equivalent loads. Any installation in which a FAST lid is buried deeper than 3 feet, or where additional loading conditions may occur, a professional engineer should be consulted. FAST® with feet option should be considered. Refer to Installation Manual for more details.
10. Specialized treatment levels may require specific features to be incorporated into the design. Consult factory for guidance.



Settling Zone
500 Gallon MIN

Treatment Zone
1000 Gallon MIN

ELEVATION

IN THE INTEREST OF TECHNOLOGICAL PROGRESS, ALL PRODUCTS ARE
SUBJECT TO DESIGN AND/OR MATERIAL CHANGE WITHOUT NOTICE.

Date 01-03-05

BIO-MICROBICS
INCORPORATED
1-800-753-FAST(3278)

© Bio-Microbics, Inc. 2003

MicroFAST® 0.75

THE DESIGN AND DETAIL OF THIS DRAWING IS THE PROPERTY OF BIO-MICROBICS, INC. AND IS NOT
TO BE USED EXCEPT IN CONNECTION WITH OUR WORK. DESIGN AND INVENTION RIGHTS ARE RESERVED.
DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

Drawn by BMI

PROJECT: 222 DONMORE DRIVE
DATE: 03/25/2020 JOB NO. T1812
PAGE: 7 OF 8
SCALE: NTS
GPIN OR TM #: 2-2-02-0044A
COUNTY/STATE: FAIRFAX COUNTY, VA


SOILS INC.

8399 WEST MAIN ST, MARSHALL, VA 20115
P. 844.447.SOIL (7645) F. 540.364.2060

NOTES

1. VENT TO BE LOCATED ABOVE FINISH GRADE OR HIGHER TO AVOID INFILTRATION. CAP WITH 6" VENT GRATE W/AT LEAST 7.1 SQ. IN. OF OPEN SURFACE AREA. SECURE WITH STAINLESS STEEL SCREWS (SEE MCF 0.75 L DWG).
- OR:
- RUN VENT TO DESIRED LOCATION AND COVER OPENING WITH 3" VENT GRATE W/AT LEAST 7.1 SQ. IN. OPEN SURFACE AREA. SECURE WITH STAINLESS STEEL SCREWS. VENT MUST NOT ALLOW EXCESS MOISTURE BUILDUP OR BACK PRESSURE.

NDS 6" GRATE
(6-034 ROUNDGRATE)
W/7.1 SQ IN OPEN SURFACE
AREA OR EQUIVALENT




SECURED WITH
STAINLESS
STEEL SCREWS

6" DIA
OBSERVATION
PORT

VENTS
W/FAST LID

BLOWER HOUSING BASE
DIMENSIONS (SECTION A-A)



BLOWER W/ HOOD
(BY BIO-MICROBICS)

CONCRETE
BASE

ELECTRICAL CONDUIT
(TO BLOWER
CONTROL SYSTEM)

2" MIN. AIR PIPING

BLOWER
HOUSING
DIMENSIONS

IN THE INTEREST OF TECHNOLOGICAL PROGRESS, ALL PRODUCTS ARE
SUBJECT TO DESIGN AND/OR MATERIAL CHANGE WITHOUT NOTICE.

Date 01-03-05

BIO-MICROBICS INCORPORATED

1-800-753-FAST(3278)

© Bio-Microbios, Inc. 2003

MicroFAST® 0.75

THE DESIGN AND DETAIL OF THIS DRAWING IS THE PROPERTY OF BIO-MICROBICS, INC. AND IS NOT
TO BE USED EXCEPT IN CONNECTION WITH OUR WORK. DESIGN AND INVENTION RIGHTS ARE RESERVED.
DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

Drawn by BMI

PROJECT: 222 DONMORE DRIVE	JOB NO. T1812
DATE: 03/25/2020	
PAGE: 8 OF 8	
SCALE: NTS	
GPIN OR TM #: 2-2-02-0044A	
COUNTY/STATE: FAIRFAX COUNTY, VA	

SOILS INC.

8399 WEST MAIN ST, MARSHALL, VA 20115
P. 844.447.SOIL (7645) F. 540.364.2060

LEGEND FOR GRADING PLANS


- EXISTING CONTOUR
PROPOSED CONTOUR
EXISTING SPOT ELEVATION
PROPOSED SPOT ELEVATION
PROPOSED CLEARING LIMITS
TREE PROTECTION
STD. & SPEC. 3.02
SILT FENCE
STD. & SPEC. 3.05
CONSTRUCTION ENTRANCE
STD. & SPEC. 3.02
TEMPORARY SEEDING
STD. & SPEC. 3.31
PERMANENT SEEDING
STD. & SPEC. 3.32
CULVERT INLET PROTECTION
STD. & SPEC. 3.08
SUPER SILT FENCE
INLET PROTECTION
STD. & SPEC. 3.07
DIVERSION DIKE
STD. & SPEC. 3.09
RIGHT-OF-WAY DIVERSION
STD. & SPEC. 3.11
SEDIMENT TRAP
STD. & SPEC. 3.07
XXXXXXXXXXXXXXXXX - DENOTES ROOT PRUNING

CULVERT / BRIDGE NOTE:

THE CULVERT / BRIDGE IS BEING PLACED WITHIN THE SWALE THAT CARRIES OFF-SITE RUNOFF THROUGH THE SITE. WORK TO INSTALL THE CULVERT / BRIDGE SHALL BE PERFORMED AS PART OF PHASE 2 CONSTRUCTION AND SHALL BE DONE SWIFTLY BEHIND THE PROTECTION OF A DIVERSION DIKE. ONCE THE CULVERT IS INSTALLED AND THE AREA STABILIZED THE DIKE CAN BE REMOVED AT THE INSPECTOR'S DISCRETION. THE CULVERT SHALL BE COUNTER SUNK INTO THE GROUND AND THE BOTTOM SHALL BE COVERED WITH SOIL AND TURF OR STONW TO CREATE A NATURAL SWALE THROUGH THE CULVERT AND NOT HAVE A SMOOTH CONCRETE BOTTOM THAT WILL INCREASE FLOW VELOCITY.

PHASED CONSTRUCTION NOTE:

DUE TO THE LARGE SWALE AND AMOUNT OF OFFSITE WATER RUNNING THROUGH THE SITE AND ENTERING THE CULVERT UNDER DONMORE DRIVE A PHASED CONSTRUCTION DESIGN IS PROPOSED. THE FIRST PHASE WILL CONSIST OF THE HOUSE AREA, PROPOSED POND AND A PORTION OF THE DRIVEWAY. THIS AREA WILL BE WORKED AND STABILIZED PRIOR TO CONSTRUCTION WITHIN THE PHASE 2 WORK AREA WHICH CONSISTS OF THE REMAINDER OF THE DRIVEWAY, CULVERT BRIDGE AND SEPTIC FIELD. AT SITE INSPECTOR'S DISCRETION THERE MAY BE MINIMAL OVERLAP OF WORK WITHIN THE TWO AREAS. THE PHASED DESIGN IS TO MAINTAIN OFF-SITE WATER FLOW THROUGH THE SITE IN THE LEAST DISRUPTIVE MANNER THROUGHOUT CONSTRUCTION. THIS SHEET SHOWS THE PHASE 2 CONSTRUCTION. THIS CONSTRUCTION WILL WORK WITHIN THE SWALE RUNNING THROUGH THE SITE. THE DESIGN CALLS FOR A RIP-RAP LEVEL SPREADER AT THE UPPER SWALE CROSSING AND A DIVERSION DIKE AT THE LOWER PORTION TO DIRECT RUNOFF AROUND THE AREA OF CULVERT INSTALLATION. ONCE THE CULVERT IS INSTALLED AND THE AREA STABILIZED THEN THE DIVERSION DIKE CAN BE REMOVED AND THE SWALE ALLOWED TO FOLLOW ITS NATURAL COURSE. WORK WITHIN THE SWALE AREA SHOULD BE APPROACHED AS IF WORKING WITHIN A LIVE STREAM. WORK SHOULD BE SWIFT AND DONE DURING TIMES OF MINIMAL RAIN. AREAS SHALL BE STABILIZED QUICKLY ONCE WORK IS COMPLETED.



CIVIL SPUR

SITE PLANNING - DESIGN - CONSULTING
929 WEST BROAD STREET #200, FALLS CHURCH VA. 22046
OFFICE (703) 663-7173 CELL (540) 207-5681
EMAIL: ROGER@CIVILSPUR.COM

PHASE 2 CONSTRUCTION PLAN
222 DONMORE DRIVE
LOT 44A SEC. 3
SENECA FARMS
DRANESVILLE DISTRICT #1
FAIRFAX, VIRGINIA

SEPTIC SYSTEM DESIGN LEGEND:

- 138.6' SCH40 PVC SEWER LINE @ AT 1.68%
- 109.5' SCH40 PVC SEWER LINE @ INSTALL AT 2-4%
- BIOMICROBICS 0.75 MICROFAST ATU (DROP IN) UNIT IN HANOVER PRECAST 1500 GAL TANK
IN=348.67
OUT=348.54
FG=352.0
- HANOVER PRECAST 2000 GAL TJ PUMP TANK W/ RISER FOR SAMPLING
IN=348.44
OUT=348.27
FG=352.0
- 2' SCH40 PVC FORCE MAIN-242.9'
- 6-PORT CONCRETE SURGE BOX WITH SANITARY "T"
- 10-PORT CONCRETE DISTRIBUTION BOX
- 6" PVC SLEEVE UNDER DRIVEWAY-63.4'

REVISION NOTE:

THIS REVISION IS FOR THE REDESIGN OF THE PROPOSED DETENTION POND ON-SITE. POND WAS REVISED TO REMOVE A GRAVEL STORAGE AREA UNDERNEATH AND TO SOFTEN GRADES ALONG SIDES OF POND.

RETAINING WALL NOTE:

THE PROJECT PROPOSES RETAINING WALLS OF VARIOUS HEIGHTS. ANY NEW RETAINING WALL OVER 30 INCHES (2.5' IN HEIGHT) SHALL REQUIRE A SEPARATE PERMIT AND SHALL BE DESIGNED BY OTHERS. THIS PLAN IS SHOWING THE GRADES AND LOCATION FOR THE WALL AND DOES NOT CONSTITUTE A FULL DESIGN FOR PERMIT. WALL TYPE, FOUNDATION, SUPPORT, TIE-BACKS AND MATERIALS SHALL BE DETERMINED BY THE DESIGN ENGINEER FOR DURING THE WALL PERMITTING PROCESS.


GRAPHIC SCALE


0' 15' 30' 60'

SCALE: 1"=30'

REVISION	DATE

SCALE: 1"=30'





ON-SITE SEWAGE DISPOSAL SYSTEM INFORMATION:

BASEMENT ELEVATION = 353.0'
INVERT ELEV. OF SEWER LINE #1 @ HOUSE = 351.0'
INVERT ELEV. OF SEWER LINE #2 @ HOUSE = 359.0'

INVERT IN @ SEPTIC TANK = 348.67'
INVERT OUT @ SEPTIC TANK = 348.54'
GROUND ELEV. @ SEPTIC TANK = 352.0'
TOP OF SEPTIC TANK = 350.0'
PROP. GROUND COVER = 24'

INVERT IN @ PUMP TANK = 348.44'
INVERT OUT @ PUMP TANK = 348.27'
GROUND ELEV. @ PUMP TANK = 352.0'
TOP OF PUMP TANK = 349.94'
PROP. GROUND COVER = 24.7'

GROUND ELEV. @ SURGE BOX = 356.3'
INVERT IN @ SURGE BOX = 355.7'
GROUND ELEV. @ DIST. BOX #1 = 356.3'
INVERT IN @ DIST. BOX #1 = 355.5'

SEWER PIPE #1 LENGTH FROM HOUSE TO TANK = 138.6'
SLOPE = 1.68%

SEWER PIPE #2 LENGTH FROM HOUSE TO TANK = 109.5'
SLOPE = INSTALL 2-4%

MATERIALS:

- SEWER LINE: 4" PVC, SCHEDULE 40, LENGTH: 138.6' & 109.5' W/ CLEANOUTS EVERY 50'-60'.
- HEADER LINE: 4" PVC, SCH. 40
- FORCE MAIN: 242.9'
- DRAINLINE = 4" PERFORATED CORRUGATED PLASTIC PERC PIPE. USE 2' WIDE TRENCHES @ 6' CENTER TO CENTER SPACING
- SEPTIC TANK: HANDOVER 1,500 GAL. MICROFAST T/S TANK
- TREATMENT UNIT: MICROFAST 0.75 ATU W/ BLOWER
- PUMP TANK: HANDOVER 2,000 GAL. T/S PUMP TANK W/ RISER OVER INLET AND OUTLET. INLET RISER TO PROVIDE ACCESS FOR SAMPLING.

NOTE:

ALL SYSTEM COMPONENTS TO BE A MINIMUM OF 10' FROM ALL PROPERTY LINES



Soils Inc.

8399 WEST MAIN ST, MARSHALL, VA 20115
P. 447.SOIL (7645) F.540.364.2060

PROJECT: 222 DONMORE DRIVE	
DATE: 04/02/2020	JOB NO. T1812
PAGE: 3 OF 8	
SCALE: 1"=50'	
GPIN OR TM #: 2-2-02-0044A	
COUNTY: STATE: FAIRFAX COUNTY, VA	