Pohick Interceptor Rehabilitation Project – Community Meeting

Project No. WW-000028-44 Wastewater Design and Construction Division

> Department of Public Works and Environmental Services Working for You!



Project Team

- Wastewater Design and Construction Division (WDCD)
 - Phillip Hunt
 - Matt Doyle
- Wastewater Collection Division


Justin Ferguson

- Dewberry Engineers Inc.
 - (Fairfax Office)
- Contractor
 - Job Order Contract



Overall Pohick Program


- Pohick Interceptor Rehabilitation Program
 - The overall program has three phases.
 - Phase 1 (Construction Fall 2024) (Green)
 - Phase 2 (Construction Spring 2024) (Blue)
 - Phase 3 (Construction TBD) (Orange)
 - The overall program was broken down into multiple phases due to the nature of the rehabilitation that is needed.
 - Different type of permitting needs,
 - Different type of Contractor that are needed,
 - Useful life remaining/priority of the pipe,





Project – Phase I


- Pohick Large Diameter Phase I
 - Rehabilitate of 5,000 LF
 - 54" diameter
 - CIPP Lining
- Contact Information
 - Justin Ferguson
 - Project Manager Wastewater Collection Division
 - justin.ferguson@fairfaxcounty.gov





Project – Phase 2


- Pohick Large Diameter Phase 2
 - Rehabilitate 72" tunnel
 - Geopolymer liner
- Contact Information
 - Matthew Doyle
 - Phillip Hunt





Project – Phase 3

- Pohick Large Diameter Phase 3
 - Rehab to be determined
- Contact Information
 - This project hasn't started yet.
 - Beyond FY 2026-time frame





Phase 2

Today's Discussion is only about Phase 2




Project Description

- Primary Goals
 - Rehabilitate the tunnel entrance manhole
 - Rehabilitate the 72" tunnel
 - Provide a safety access to the tunnel entrance



Existing Conditions

- 72" concrete tunnel 600 linear feet
- Manhole is located at the end of Wadebrook Terrance
- Carbon Steel reinforcement is exposed to hydrogen sulfide gas
- Crosses under I-95 and CSX railroad tracks










Activities

Activities

Project Activities

The Sequence of the Project

- Setup Erosion and Sediment Control
- Provide an access road to the tunnel entrance
- Setup a by-pass pumping system
- Rehab the tunnel with a Geopolymer liner
- Rehab the entrance manhole with an epoxy liner
- Remove the bypass pumping system
- Remove Erosion and Sediment Control
- Site Restoration






Community Impacts

Community Impacts

Project Activities - Bypass

Setup a by-pass pumping system





Project Expectations

- Community Impacts
 - No expected odor Issues.
 - Noise from the Generator
 - Sound attenuation cover
 - 65 decibels
 - 24 /7-hour operation until done










Project Expectations - Trail

- Community Impacts
 - Detour of the Trail head
 - MOT signage
 - 6 months







Project Expectations - Parking

- Community Impacts
 - 10 side street parking spots



Project Schedule

Project Schedule

Anticipated Schedule


This is the anticipated schedule only. Ongoing supply chain issues may impact necessary material deliveries and impact the construction schedule.

Phases	Dates
Beginning of Design	5/15/2023
35% Design Submission	9/11/2023
70% Design Submission	12/8/2023
90% Design Submission	January 2024
Community Planning Meeting	January 2024
Final Design Submission	February 2024
Construction Start	April 2024

POHICK LARGE DIAMETER REHABILITATION

Community Outreach

Citizen letters
Community Meeting
Project Website
Project Signage







Questions and Answers



Additional Information

For additional information, please contact

Phillip Hunt – phillip.hunt@fairfaxcounty.gov

Matthew Doyle - <u>matthew.doyle2@fairfaxcounty.gov</u>

www.fairfaxcounty.gov/publicworks

